

NA
1
I56
V.46
no.4

NOVEMBER, 1905



IRVING K. POND, DES.

LORADO TAFT, SCULPT.

UNIVERSITY OF MICHIGAN
GENERAL LIBRARY



Entered at the Postoffice at Chicago as second-class matter, June 1, 1905.

CONTENTS

EDITORIAL	37
Why not Simplify Plumbing Laws—Reasons for Condemning Trap Venting—Proposed State Law for Fire Protection—Municipal School Buildings—Interesting Details of School Building.	
SANITARY ENGINEERING IN THE MODERN OFFICE BUILDING, PART IV.....	39
By J. Pickering Putnam, Architect.	
MUNICIPAL IMPROVEMENTS. PART IV.....	41
By Albert Kelsey, Architect.	
THE PLANNING OF HOSPITALS. PART II.....	48
By T. M. Clark, Architect.	
STATE FIRE PROTECTION	45
By F. W. Fitzpatrick.	
ARTISTIC HARDWARE	47
By Montgomery Schuyler.	
OBITUARY, F. E. Kidder	48
ASSOCIATION NOTES	48
OUR ILLUSTRATIONS	48

NORTH-WESTERN TERRA COTTA CO.

WORKS AND OFFICE:

Clybourn and Wrightwood Avenues.

BRANCH OFFICE: 1415 Railway Exchange Building
CHICAGO.

J. W. TAYLOR

MONON BLDG., 324 Dearborn St. Telephone 1500 Harrison

ARCHITECTURAL PHOTOGRAPHS.

BUILDINGS, INTERIORS, DETAILS, ETC.

Promise to purchase two dozen from the lot at \$4.00 per dozen, unmounted, and I will send 200 from which to make the selection.

Advance News

INDICATING

Chances to Sell

PLANS, FIXTURES,
MATERIALS, FURNITURE,
MACHINERY.

May be secured with promptness, accuracy and thoroughness, and at reasonable rates, from

THE PRESS CLIPPING BUREAU,

ROBERT AND LINN LUCE,

26 Vesey St., NEW YORK. 68 Devonshire St., BOSTON.
286 E. Fourth St., CINCINNATI. Railroad Bldg., DENVER.

National Fire Proofing Company

Manufacturers

All Kinds of Hollow Building Tile

also

Engineers and Contractors for
the Fireproofing of Buildings

Our engineering department
is at your service for the prepa-
ration of complete plans
and details for fireproof work



Annual
Capacity 1,600,000 tons

Factories located near
all the large cities

For data and more detailed information, write us at either
of the following addresses:

NEW YORK, N. Y., 170 Broadway CHICAGO, ILL., Hartford, Building
BOSTON, MASS., 840 Old South Bldg. WASHINGTON, D. C., Colorado Bldg.
PHILADELPHIA, PA., Land Title Bldg. MINNEAPOLIS, MINN., Lumber Exch.
PITTSBURG, PA., Bessemer Building BALTIMORE, MD., Calvert Building

TREES AND SHRUBS

in sizes suitable for giving
immediate effect.


Prices right. Catalogue
free on application.

We are pleased to co-operate
with architects in laying
out grounds.

PETERSON NURSERY

506 W. Peterson Ave., CHICAGO

City Office and Landscape Dept.,
1501 No. 108 La Salle St.



JAMES A. MILLER & BRO.

133 So. Clinton St., Chicago

Manufacturers

Fire Retarding Wire Glass Windows


Sheet Metal Frames and Sash

SKYLIGHTS, TILE, SLATE
AND METAL ROOFING...

Please mention THE INLAND ARCHITECT when corresponding with Advertisers.

The STURTEVANT SYSTEM of Heating and Ventilation

By a Forced Circulation of Warm Air is Applicable to all Classes of Buildings



THE STURTEVANT SYSTEM IS SUPERIOR TO DIRECT HEATING

Because The apparatus is centralized and under one man's control. There is no steam piping scattered around the building. Consequently no danger of freezing or of damage from leaky joints, valves or air cocks. The heater is specially adapted to the use of exhaust steam. Heating can be accomplished with great rapidity. Building can be cooled and ventilated in summer. Humidity can be regulated.

Because Ample and positive ventilation is provided. Quantity and quality of air are under absolute control. Constant temperature can be maintained and air volume varied when "hot and cold system" is used. The heating surface is enclosed in a fire-proof casing. The air ducts are fire-proof. There is no tendency to noise. Operation is independent of wind and weather.

Send for Catalogue No. 112, describing the system in detail

B. F. STURTEVANT COMPANY, Boston, Mass.

New York. Philadelphia. General Office and Works, Hyde Park, Mass. Chicago. London.
Designers and Builders of Heating, Ventilating, Drying and Mechanical Draft Apparatus; Fans, Blowers and Exhausters; Steam Engines, Electric Motors and Generating Sets; Fuel Economizers; Forges, Exhaust Heads, Steam Traps, Etc. 511

Engineers AND Contractors

FOR
Deep or Difficult
Foundations
FOR
Buildings, Bridges, etc.

BY
Pneumatic Caissons
Concrete Piles
Steel and Wood Sheet piling

Complete Waterproof Cellar
Ready for Steel

THE FOUNDATION CO.

35 Nassau Street, NEW YORK.
KANSAS CITY, MO. NEW ORLEANS, LA.

LOW COLONIST RATES

TO

Colorado, Utah, California
and the Northwest

Through Tourist Cars from all principal points via

**THE DENVER and
RIO GRANDE
SYSTEM**



"The Scenic Line of the World"

Traverses all the world-famed points of interest in the Rocky Mountain region and you should see that your ticket reads via this route in order to make your trip most enjoyable. Write for free illustrated literature.


R. C. NICHOL, Genl. Agt.,
S. K. HOOPER, 242 Clark Street,
G. P. T. A., Denver. Chicago

Please mention THE INLAND ARCHITECT when corresponding with Advertisers.

"3" Point Prisms Pay Their Cost

When Installed as Pavements With "BAR-LOCK" Galvanized Wrought Steel Construction By Saving the Expense of Artificial Light

Maximum Glass Area, Perfect Refraction, Greatest Strength, Absolutely Watertight.



For further information or the name of representative in your section, address

American Bar-Lock Company

Offices and Works, 26th Street and Pennsylvania Ave., PHILADELPHIA, PA.

CAUTION:—Any person using or selling any infringement of this Company's patents will be promptly prosecuted.

In Every Village

There are some houses that stand forth conspicuous in the beauty of durable, clean paint. Such houses are always those that have been painted with high grade paints based on OXIDE OF ZINC. Architects capable of logic will draw their own conclusions.

FREE:

OUR PRACTICAL PAMPHLETS:

- "The Paint Question"
- "Paints in Architecture"
- "Specifications for Architects"
- "French Government Decrees"
- "Paint: How, Why and When"

The
New Jersey Zinc Co.
71 BROADWAY, NEW YORK

We do not grind zinc in oil. Lists of manufacturers of high grade zinc white paints sent on request.

COLORS AND SPECIFICATIONS

(ILLUSTRATED)

PROTECTIVE PAINT FOR CONSTRUCTION AND MAINTENANCE OF STEEL AND IRON WORK.

PUBLISHED FOR FREE DISTRIBUTION BY THE

Joseph Dixon Crucible Co., Jersey City, U.S.A.

CRANE VALVES

ESTABLISHED 1855

THE WINKLE TERRA COTTA CO.

MANUFACTURERS OF

**Architectural
Terra Cotta**

IN ALL COLORS.

OFFICE:

Rooms 502 and 503, Century Building,
ST. LOUIS, MO.

Works: CHELTENHAM, ST. LOUIS.

Please mention THE INLAND ARCHITECT when corresponding with Advertisers.

W. & J. SLOANE CARPETS MADE BY HAND

THE luxurious furnishings of the modern home demand the highest grade of floor coverings. They must also possess these three important features: Perfect harmony of color, correct style of design, and appropriate size.

In this connection we offer our unequalled facilities, enhanced by years of experience and wide foreign connections, for the execution of orders for carpets or rugs in the French Aubusson and Savonnerie,

Berlin, Turkey and other weaves. The designs are prepared by our own artists to maintain the style of decoration in the carpet or rug, and the fabric is woven in one piece to fit the room where it is to be used.

We have in stock at all times a large collection of these beautiful floor coverings, especially woven by us in designs of the periods.

No Catalogues are issued. Full details on application.



French Aubusson Carpet. Style Louis XIV

888 BROADWAY
NEW YORK

**MISSOURI
PACIFIC
RAILWAY**

THE
"Colorado Short Line"
DIRECT TO
Glenwood Springs, Colorado
Springs, Manitou
AND ALL THE
Famous Resorts of the Rockies.

Elegant Pullman Sleeping Cars, Observation
Parlor Cafe Dining Cars, with Electric
Lights and Fans, and Free
Reclining Chair Cars.

BEST LINE TO THE
PORTLAND EXPOSITION

H. C. TOWNSEND, G. P. and T. Agent, St. Louis.

The Perfect Map of the West

A new edition roller map, 60 by 40 inches in size, showing the United States from the Great Lakes to the Pacific Coast. All railroads are shown in different colors and characters. All geographical points west of the Missouri River and practically all east thereof are included. The most complete reference map of the West ever published.

It ought to have a prominent place in every office and business house. Copies sent free for 25 cents (stamps will do) to pay transportation, etc. Address, P. S. Eustis, Passenger Traffic Manager, 209 Adams Street, Chicago, Ill.

THE J. W. REEDY ELEVATOR CO.
Passenger and Freight
ELEVATORS.

63 to 91 Illinois Street,
CHICAGO.

31-33 Tenth Avenue,
NEW YORK CITY.

ORNAMENTAL IRON

STAIRS

STORE FRONTS

ELEVATOR ENCLOSURES

FENCES AND RAILINGS

SIDEWALK LIGHTS

SKYLIGHTS

Brown Bros. Mfg. Co.

Established in 1860

22d St. and Campbell Avenue

CHICAGO

Telephone Canal 115

Please mention THE INLAND ARCHITECT when corresponding with Advertisers.

"Standard"

Porcelain Enameled Closets

AND HIGH GRADE

Sanitary Wood Work

Possess Qualities which make them Superior to all Other Closet Combinations

"Standard" Porcelain Enameled Closet Bowls are neat in design and will not stain or discolor. The surface is more vitreous than of earthenware, and is absolutely non-porous. They will not craze under frost or crack when frozen. **"Standard"** Sanitary Wood Work is made in our own wood-working plant and the wood is properly cured to prevent warping or opening of joints.

The "Delecto"

is a popular **"Standard"** Closet and should be specified by architects who are specially particular about this most important fixture of the bathroom. *Like all other "Standard" Ware, it bears our "GREEN and GOLD" label, the guarantee of quality and durability which relieves you of all risk.*

We will mail our book "MODERN BATH-ROOMS" to your clients, with your compliments, if you will send us their names.



THE "DELECTO"—PLATE P 802

Standard Sanitary Mfg. Co.

**PITTSBURGH, PA.,
U. S. A.**

THE CHEAPEST GOODS
Do not always cost the least

Established 1844

Peerless Mortar Colors

Are the Brightest, Strongest and Most Durable
Their Ultimate Cost is Therefore the Lowest

SAMUEL H. FRENCH & CO.

Send for Samples.

PHILADELPHIA

Put into the White House by the U. S. Government.



F. E. CUDELL'S

Patent Sewer-Gas and Backwater Trap

For Wash-Bowls, Sinks, Bath and Wash Tubs,

CLEVELAND, OHIO.



Butcher's Boston Polish

Is the best finish made for
FLOORS, Interior Wood-
work and Furniture

Not brittle; will neither scratch nor deface, like shellac or varnish. Is not soft and sticky, like bees-wax. Perfectly transparent, preserving the natural color and beauty of the wood. Without doubt the most economical and satisfactory POLISH known for HARDWOOD FLOORS.

For Sale by Dealers in Paints, Hardware and House Furnishings.

Send for our FREE BOOKLET, telling of the many advantages of BUTCHER'S BOSTON POLISH.

THE BUTCHER POLISH CO.,

356 Atlantic Avenue, Boston, Mass.

Our No. 3 Reviver is a superior finish for kitchen and piazza floors.



We make more than 200 Steel Ceiling designs, finely illustrated in our 148-page Catalogue. Write for copy if you are interested. Awarded the only Gold Medal at St. Louis.

BERGER'S "Classik" Steel Ceilings

We also make Roofing, Siding, Metal Shingles, Cornices, Finials, Skylights, Metal Lath, and Fireproofing Specialties. Send us your plans.

THE BERGER MFG. CO., Canton, Ohio
I. A. 10-5

Please mention THE INLAND ARCHITECT when corresponding with Advertisers.



Imposing Architectural Effects


are obtained by the intelligent use of statuary in connection with the architecture of buildings.

Mullins Art Architectural Sheet Metal Work

has genuine artistic merit—is light and very durable—made from artists' own models or selected, if you prefer, from our great variety of artistic stock designs. There is a wide range for selection and charming architectural effects are assured.

Our Large Catalogue of designs will be sent you on request.

The W. H. Mullins Co., 211 Franklin St., Salem, O.
Makers of everything in Sheet Metal.



Detail of Bronze Railing, Trinity Bldg., New York.
Francis H. Kimball, Architect.

THE WINSLOW BROS. COMPANY

CHICAGO—NEW YORK

Ornamental Iron and Bronze

THE DELTA LANDS OF THE SAN JOAQUIN RIVER

are as rich as any in Holland and
under the sunshine of

CALIFORNIA

growth is simply amazing. They are
attracting the attention of Eastern
Experts, and are among the remark-
able lands of the world. Descriptive
pamphlets free of Agents of

SOUTHERN PACIFIC

Send 10 cents for March SUNSET
MAGAZINE, containing illustrated
description of the Delta lands

Also books about opportunities and
advantages of Life in California

WRITE

W. G. NEIMYER, General Agent,
120 Jackson Boulevard CHICAGO, ILL.

TALKING POINTS FOR

THE FOUR-TRACK NEWS

Which Explain Its Emphatic Success

Here are a few reasons why you want THE
FOUR-TRACK NEWS on the reading table in your
home. Look them over, think them over—then
send for a sample copy and see if you don't think
THE FOUR-TRACK NEWS is worth \$1.00 a year to
yourself and your family.

Its scope is confined to no geographical section;
the world is its field.

It instructs.

It entertains.

It's different.

It is a universal favorite.

It is always and forever up-to-date.

It is a great help to students in history classes.

There is much in every issue of educational
value to every reader.

It is entertaining to the father and mother as
well as to the children.

It is eloquent with bright, brief, valuable
articles and superb pictures.

Subscriptions, \$1.00 a Year; Foreign Countries,
\$1.50; at News-stands 10 Cents a Copy.

A sample copy and our special terms to agents
will cost you nothing. Send your address and two
references to GEORGE H. DANIELS, Publisher,
Room No. 115A, 7 East 42d St., New York.

Please mention THE INLAND ARCHITECT when corresponding with Advertisers.



Trinity Building, New York City

"Giant" and "Red Metal" Sash Chains

This cut illustrates one of many high class buildings in which our chains are used. We are the *originators* of SASH Chain as a substitute for cord. Our Chains are "STANDARD" and are acknowledged as such by the leading architects and are specified by them * *

Samples of chains on application

The Smith & Egge Mfg. Co., Bridgeport, Conn.

POROUS FIREPROOFING

Illinois Terra Cotta Lumber Co.

Manufacturers and Contractors for the Fireproofing of Buildings

OFFICE

439 "The Rookery," CHICAGO

Telephone, HARRISON 1705

WORKS AT FULLMAN

CRANE FITTINGS

ESTABLISHED 1855

SOLID THROUGH TRAINS
BETWEEN
CHICAGO, BUFFALO, NEW YORK AND PHILADELPHIA
"VIA NIAGARA FALLS."

Also to BOSTON via the important business centers of CANADA and NEW ENGLAND.

For Information, Time Tables, etc., apply to any Agent of the Company, or to
GEO. W. VAUX,
ASST. GEN. PASS. & TKT. AGT.,
103 ADAMS ST.,
CHICAGO.

GRAND TRUNK RAILWAY SYSTEM

Please mention THE INLAND ARCHITECT when corresponding with Advertisers.

CHICAGO & ALTON RAILWAY

"THE ONLY WAY"



THE CHICAGO & ALTON runs the largest passenger engines in the world

They keep the trains on time

Between Chicago, St. Louis, Kansas City and Peoria

GEO. J. CHARLTON, General Passenger Agent
CHICAGO, ILL.



Busy Business Men

Prefer The California Limited when they travel between Chicago, Los Angeles and San Francisco.

It's quick—Only 68¾ hours.

It's luxurious—Compartment and observation Pullmans, dining car and buffet-smoker.

And Harvay serves the meals.

Daily service begins early in November—until then, semi-weekly.

All the facts, if you address Passenger Dept. A. T. & S. F. Ry., Chicago.



All the Way

Architects' Specification Reminders

	Page		Page		Page		Page
Architectural Instruction.		Exhaust Fans.		Mortar Colors.		Sash Cords and Chains.	
Architectural Iron Works.		Sturtevant Co., B. F.	III	French, S. H. & Co.	IV	Smith & Egge Mfg. Co.	VIII
The Winslow Bros. Co.	VII	Exhaust Heads.		Motors (Electric).		Samson Cordage Works	XVI
Brown Bros. Mfg. Co.	V	Sturtevant Co., B. F.	III	Crocker, Wheeler Co.	XIV	Shingle Stain.	
Architectural Photographers.		Fans.		Sturtevant Co., B. F.	III	Dexter Bros.	XV
Taylor, J. W.	II	Sturtevant Co., B. F.	III	Ornamental Sheet Metal Work.		Showers, Permanent and Port-	
Architectural Views.		Fireproof Doors.		Mullins, W. H. Co.	VII	able.	
Taylor, J. W.	II	Fireproof Shutters.		Paints, Oils and Varnishes.		Standard Sanitary Mfg.	
Art Metal Tile Roofing.		Fireproofing.		Joseph Dixon Crucible		Co.	IV
Mullins, W. H. Co.	VII	Illinois Terra Cotta		Co.	VI	Sidewalk and Vault Lights.	
Bath Room Fixtures.		Lumber Co.	VIII	New Jersey Zinc Co.	VI	American Luxfer Prism Co.	XI
Standard Sanitary Mfg.		National Fireproofing		Smith, Edward & Co.	XVI	American Bar-Lock Co.	VI
Co.	IV	Co.	II	Pencils.		Brown Bros. Mfg. Co.	V
Bath Tubs.		The Roebling Construc-		Joseph Dixon Crucible		Sinks, Porcelain Enameled.	
Standard Sanitary Mfg.		tion Co.	X	Co.	VI	Standard Sanitary Mfg.	
Co.	IV	Fire Retarding Windows.		Plumbers' Fittings.		Co.	IV
Blinds and Screens.		James A. Miller & Bro.		Standard Sanitary Mfg.		Skylight (Gal. Iron).	
Willer Mfg. Co., Mil-		Mullins, W. H. Co.	VII	Co.	IV	Mullins, W. H. Co.	VII
waukee, Wis.	IX	Floor Polish.		Plumbers' Ware, Porcelain		Snow Guards.	
Blowers.		Butcher Polish Co.	IV	Enameled.		Spring Hinges.	
Sturtevant Co., B. F.	III	Forges.		Standard Sanitary Mfg.		Smith & Egge Mfg. Co.	VIII
Brass Goods (Plumbers').		Sturtevant Co., B. F.	III	Co.	IV	Statuary.	
Standard Sanitary Mfg.		Foundations.		Prisms.		Mullins, W. H. Co.	VII
Co.	IV	Foundation Co., The.	III	American Bar Lock Co.	VI	Steam Hot Blast Apparatus.	
Builders' Hardware.		Fuel Economizers.		American Luxfer Prism Co.	XI	Sturtevant Co., B. F.	III
The Yale & Towne Mfg.		B. F. Sturtevant Co.	III	Railroads.		Steel Construction.	
Co.	XI	Gas Blowers and Exhausters.		Baltimore & Ohio R. R.	XII	Volkman, Chas. & Co.	X
Builders' Sundries.		Sturtevant Co., B. F.	III	Burlington Route.		Steel Ceilings.	
The Yale & Towne Mfg.		Generating Sets.		Chicago & Alton R'y.	VIII	Mullins, W. H. Co.	VII
Co.	XI	Crocker, Wheeler Co.	XIV	Denver & Rio Grande R.		Steel Rolling Doors.	
Cements.		Sturtevant Co., B. F.	III	R.	III	Steel Rolling Shutters.	
French, S. H. & Co.	IV	Hardware.		Grand Trunk Lines.	VIII	Steel Shutters.	
Closets.		The Yale & Towne Mfg.		The Lake Shore Route.	XV	Terra Cotta.	
Naturo Co.	XIV	Co.	XI	Michigan Central R. R.	XIII	Northwestern Terra Cot-	
Standard Sanitary Mfg.		Heating.		Missouri Pacific R'y.	V	ta Works	II
Co.	IV	B. F. Sturtevant Co.	III	New York Central R. R.		Winkle Terra Cotta Co.	VI
Concrete Construction.		Heating and Ventilating Appa-		Northern Pacific Line.	VII	Tile (Rubber).	
Cornices.		ratus.		Santa Fe R'y.	VIII	Traps (Steam).	
Mullins, W. H. Co.	VII	B. F. Sturtevant Co.	III	Southern Pacific Co.	VII	Sturtevant Co., B. F.	III
Conduit.		Hollow Blocs.		Union Pacific Route.	XII	Trees.	
National Fireproofing		National Fireproofing		Range Closets.		Peterson Nursery	II
Co.	XIV	Co.	II	Standard Sanitary Mfg.		Urinals, Porcelain Enameled.	
Cordage.		Interior Decorations.		Co.	IV	Standard Sanitary Mfg.	
Samson Cordage Works		W. & J. Sloane.	V	Roofing Tile.		Co.	IV
XVI		Laundry Tubs.		Celadon Roofing Tile		Valves and Fittings.	
Draft (Mechanical)		Standard Sanitary Mfg.		Co., Manufacturers of		Crane Co.	VI
Sturtevant Co., B. F.	III	Co.	IV	High Grade Roofing		Ventilating Apparatus.	
Drawing Material and Imple-		Lavatories.		Tile, 204 Dearborn St.,		Sturtevant Co., B. F.	III
ments.		Standard Sanitary Mfg.		Chicago; 156 Fifth		Vimometers.	
Abbott, A. H. & Co.	X	Co.	IV	Ave., New York. Fac-		Standard Sanitary Mfg.	
Drinking Fountains.		Lead Pipe.		tories; Alfred, N. Y.,		Co.	IV
Standard Sanitary Mfg.		Standard Sanitary Mfg.		and Ottawa, Ill.		Window Guard.	
Co.	IV	Co.	IV	Roofing Tin.		Perfection Safety Window	
Drying Apparatus.		Locks.		Follansbee Bros. Co.	XVI	Guard Co.	XVI
Sturtevant Co., B. F.	III	The Yale & Towne Mfg.		Rolling Doors and Shutters		Window Lines.	
Dynamos.		Co.	XI	(Steel).		Samson Cordage Works	XVI
Sturtevant Co., B. F.	III	Lumber.		Rubber Tiling.		Wire Glass.	
Economizers (Fuel).		Mail Chutes.		Sanitary Appliances.		Wrought Iron Railings and	
Sturtevant Co., B. F.	III	Cutler Manufacturing Co.	XVI	Cudell, F. E.	IV	Grilles.	
Elevators.		Marble.		Naturo Co.	XVI	Mullins, W. H. Co.	VII
The J. W. Reedy Eleva-		Standard Sanitary Mfg.		Standard Sanitary Mfg.		Winslow Bros. Co.	VII
tor Co.	V	Co.	IV	Co.	IV		
Enameled Iron (Plumbers'		Metal Ceilings.		Sanitary Woodwork.			
Ware).		Berger Mfg. Co.	IV	Never Split Seat Co.	X		
Standard Sanitary Mfg.				Standard Sanitary Mfg.			
Co.	IV			Co.	IV		
Engines (Steam).							
Sturtevant Co., B. F.	III						

Alphabetical Index of Advertisers

	Page		Page		Page		Page
Abbott, A. H. & Co.	X	Denver & Rio Grande R. R.	III	National Fireproofing Co.	II	Samson Cordage Works.	XVI
American Bar Lock Co.	VI	Dexter Bros.	XV	National Builder.	XIII	Santa Fe R'y.	VIII
American Luxfer Prism Co.	XI	Dixon, Jos. Crucible Co.	VI	Naturo Co.	XVI	Sloane, W. & J.	V
				Never Split Seat Co.	X	Smith, E. & Co.	XVI
Baltimore & Ohio R. R.		Follansbee Bros. Co.	XVI	New Jersey Zinc Co.	VI	Smith & Egge Mfg. Co.	VIII
Co.	XII	Foundation Co.	III	New York Central R'y.	VII	Southern Pacific Co.	VII
Berger Mfg. Co.	IV	French, S. H. & Co.	IV	Northern Pacific Line.	XII	Standard Sanitary Mfg. Co.	IV
Brown Bros. Mfg. Co.	V	Grand Trunk R. R.	VIII	Northwestern Terra Cotta		Sturtevant, B. F. Co.	III
Burlington Route.				Co.	II	Taylor, J. W.	II
Butcher Polish Co.	IV	Illinois Terra Cotta Lum-		Peterson Nursery	II	Union Pacific Route.	XII
		ber Co.	VIII	Perfect Safety Window			
Celadon Roofing Tile Co.	IX	Lake Shore Route.	XV	Guard Co.	XVI	Volkman, Chas. & Co.	X
Chicago & Alton R. R.	VIII			Porter, Taylor & Co.	XIII	Willer Mfg. Co.	IX
Crane Co.	VIII, VI	Michigan Central R. R.	XIII	Press Clipping Bureau.	II	Winkle Terra Cotta Co.	VI
Crocker, Wheeler Co.	XIV	Miller, James A. & Bro.	II			Winslow Bros. Co.	VII
Cudell, F. E.	IV	Missouri Pacific R'y.	V	Reedy, J. W., Elevator Co	V	Yale & Towne Mfg. Co.	XI
Cutler Mfg. Co.	XVI	Mullins, W. H. Co.	VII	Roebling Construction Co.	X		

*Roman figures refer to advertising pages.

Please mention THE INLAND ARCHITECT when corresponding with Advertisers.


4,500 TONS OF STEEL ERECTED IN LESS THAN 50 DAYS



View Taken April 21, 1904.

The above is the record established by us on section B, of the **FIRST NATIONAL BANK BLDG., Chicago,** and illustrated by the accompanying cuts.

Let us make a record for you.



View Taken June 18, 1904.

CHAS. VOLKMANN & CO. IRON SETTERS AND GENERAL CONTRACTORS

Tel. Central 6068

Suite 22, 184 Dearborn Street, CHICAGO, ILL.

The Roebling System of Fire-Proof Construction.

HIGHEST EFFICIENCY IN THE FIRE AND WATER TESTS OF THE NEW YORK BUILDING DEPARTMENT, AND NOW THE RECOGNIZED STANDARD OF FIRE-PROOF CONSTRUCTION.

THE ROEBLING CONSTRUCTION CO.,
Fuller Bldg., Broadway and 23rd St. 906 Tribune Building
NEW YORK CITY. CHICAGO, ILL

SEND FOR CATALOGUE.



A. H. ABBOTT & CO.

Drawing Supplies,

Instruments, Tracing Cloth, Papers, Colors
Scales, Levels, Transits, Etc.

BLUE-PRINTS.

50 Madison Street, CHICAGO.



"The Tie That Binds"

Makes it absolutely impossible for **NEVER-SPLIT SEATS** to pull apart because each joint is held together by an **IRON BOLT**. No glue to break loose—no dowels to pull out. The most comfortable and durable seats made.

NEVER-SPLIT SEAT COMPANY

EVANSVILLE, IND.

CATALOGUE

Please mention THE INLAND ARCHITECT when corresponding with Advertisers.

THE INLAND ARCHITECT AND NEWS RECORD

VOL. XLVI.

NOVEMBER, 1905

No. 4



A Monthly Journal Devoted to

ARCHITECTURE

CONSTRUCTION, DECORATION AND FURNISHING

ISSUED ON THE 15TH OF EACH MONTH

PUBLISHED BY PORTER, TAYLOR & CO.

PONTIAC BUILDING, CHICAGO, ILL.

Entered at Chicago, Ill., Postoffice as second-class matter.

SUBSCRIPTION, \$10.00 a year in advance. Single copies, \$1.00.

All communications intended for The Inland Architect should be addressed to Porter, Taylor & Co., 505 Pontiac Building.

AMERICAN INSTITUTE OF ARCHITECTS

PRESIDENT	*W. S. EAMES, St. Louis, Mo.
FIRST VICE-PRESIDENT	ALFRED STONE, Providence, R. I.
SECOND VICE-PRESIDENT	CASS GILBERT, New York.
SECRETARY AND TREASURER . . .	*GLENN BROWN, Washington, D. C.
AUDITOR FOR TWO YEARS	ROBERT STEAD, Washington, D. C.
AUDITOR FOR ONE YEAR	JAMES G. HILL, Washington, D. C.

BOARD OF DIRECTORS FOR 1905.

For Three Years.—W. A. Boring, New York; J. M. Donaldson, Detroit; *Frank Miles Day, Philadelphia.

For Two Years.—Charles F. McKim, New York; *Geo. B. Post, New York; *R. D. Andrews, Boston, Mass.

For One Year.—Robert S. Peabody, Boston, Mass.; W. B. Mundie, Chicago; Isaac E. Ditmars, New York.

*Executive Committee.

THE ARCHITECTURAL LEAGUE OF AMERICA

(ORGANIZED 1899.)

The Architectural League of New York.	The Detroit Architectural Club.
The T Square Club, Philadelphia.	The St. Louis Architectural Club.
The Cleveland Architectural Club.	The Washington Architectural Club.
The Toronto Architectural Club.	The Architect's Club, U. of Ill.
The Pittsburg Architectural Club.	The Toledo Architectural Club.
The Cincinnati Chapter A. I. A.	The National Sculpture Society.
The Brooklyn Chapter A. I. A.	The National Society of Mural Painters.
The Chicago Architectural Club.	

EXECUTIVE COMMITTEE, 84 ADAMS ST., CHICAGO.

N. Max Dunning, President.	
Richard E. Schmidt, Vice-President.	Alfred H. Granger.
Herman Von Holst, Treasurer.	Elmer Jensen.
J. L. Hamilton, Secretary.	Howard Shaw.

NEXT CONVENTION AT NEW YORK, N. Y., 1906.

Why Not Simplify Plumbing Laws.

Arguments in favor of simplifying our plumbing laws have been presented in our columns in a number of articles by Mr. Putnam in some detail so far as relates to a repeal of the requirements for the back venting of traps, and we do not recollect having seen any strong presentation of the other side of the case.

So far as we are aware no attempt, based on careful, scientific tests, has ever been made either by private or by public enterprise to defend the complication at present required by the law in the majority of the large cities of this country. The experiments of Hellyer and of Bowditch and Philbrick, which seem to have been largely responsible for the present law, were made about a quarter of a century ago, and recommendations which might have had some excuse at that time are no longer applicable to the present conditions. Greatly improved methods, materials and appliances in plumbing have entirely altered the data. Main stacks of soil and waste pipes are now universally ventilated from top to bottom as was not the case at that time. Fixtures are constructed with better flushing devices. Large drum traps have been found to be secure against siphonage, and back pressure and evaporation without back venting, and other antisiphon traps have been invented which are equally reliable. Means of keeping the air of sewers and drains well aerated and perfectly safe without recourse to back venting have been devised and we know more about the constitution of sewer air and what can be done to render it innocuous than we did in those days. It seems as if some strong answer to Mr. Putnam's advocacy of greater simplicity is considerably overdue and that the burden of proof now lies with those who wish the complication and enormously increased cost to the public to continue. As Mr. Putnam rightly says, if the public are to be put to all this extra expense they have a right to demand not only that the result shall be capable of providing security but also that the simpler method shall not.

Reasons for Condemning Trap Venting.

Mr. Putnam holds that trap venting must be condemned on both counts and gives briefly these reasons for his contention: (1.) That it licks up the water seal by evaporation with a rapidity corresponding to the strength, dryness and high temperature of the ventilating current, and that in practice it often destroys the seal of the common S trap within a fortnight. (2.) That its efficacy is easily destroyed by friction created by the walls of the vent pipe and by clogging as by grease, snow or sediment; (3.) that it increases the unscored area of the trap system, making the trap partake of the nature of a cesspool, the vent mouth forming a sediment chamber at or near its crown, and indeed the whole pipe being nothing but a vast elongated cesspool; (4.) that it complicates the plumbing leading to dangerous errors called "by passes," and increases the chances of faulty joints where they are least likely to be discovered, because never receiving a water scour; (5.) that it increases the danger of freezing the water in the trap, and finally (6), that it greatly increases the cost

and public dread of plumbing. What, on the other hand, are the alleged advantages to offset these very serious and positive objections to trap venting? It is not required to prevent siphonage, because all now admit that anti-siphon traps are more reliable in this respect and are more easily kept clean.

It is no longer required to "aerate the waste pipes," because the modern custom of having all main stacks of piping open both at the top and bottom, and the construction of the modern flushing fixtures, which scour the whole system with their powerful water charges followed by a corresponding volume of pure air from the room, amply fills this need. We agree with Mr. Putnam that it is time this important matter should be settled at once and settled correctly in the interest of the people, and that to do this investigations should be made by impartial commissions appointed by the authorities having charge of the health of our cities. Boards of health or plumbing inspectors should equip themselves with apparatus suitable to test the appliances they allow to be used, that the public may be relieved at once of the burden of back venting if it be found that it is continued solely for the benefit of dealers in piping. We would suggest that the architects, both personally and through the American Institute and its various chapters in the large cities, where they are obliged to charge their clients with this expense, lend their influence to urge the authorities to appoint such expert commissions as may seem to them to be best, for the purpose of making the investigations we have advocated.

**Proposed State
Law for Fire
Protection.**

The INLAND ARCHITECT has several times taken occasion, perhaps unnecessarily, to call its readers' attention to the good work in the way of artistic, municipal and building reforms that have been suggested and so earnestly worked upon (generally successfully) by that earnest reformer, F. W. Fitzpatrick, reforms that, in many cases, have been first exploited in these columns. None of them are of more importance nor can be more far-reaching for ultimate good in their effects than the one that, as executive officer of the International Society of Building Inspectors, he has planned and that first sees the light of day in this issue of the INLAND ARCHITECT. Our fire losses have indeed reached appalling proportions; our municipalities, the best of them are, to say the least, tardy in their efforts to prevent them. The proposed State legislation is virtually a blanket building ordinance, prescribing the least that can be done in the way of good construction, below which standard no one will be permitted to build within the State. The advantages of its being a uniform law in all the States are obvious. We recommend its most careful perusal to all our readers and further suggest that those directly interested in the subject write Mr. Fitzpatrick, giving him the benefit of any criticisms and suggestions they may have to offer of advantage to the proposed legislation.

**Municipal
School
Buildings.**

In school buildings, each city, naturally, has its special problems for solution which determine to a considerable degree the characteristics of the designs and plans of buildings of this class in the individual city. Interesting data and comparisons of school buildings are afforded by the

last annual reports, prepared by the schoolhouse departments of Boston, Chicago and St. Louis. In all of these cities, as in New York, the present practice is for the erection of buildings of the first class, fireproof throughout, and fully equipped with safety appliances for the occupants. In St. Louis and Boston the exterior walls are of brick with the simplest use of stone for trimmings, a pleasing effect being produced by using brick of mixed colors. The exterior treatment of the Chicago buildings is dignified and attractive. The walls are of brick with a considerable use of stone for pilasters, cornices, and to accent entrances. The new buildings in Boston and Chicago are usually three stories in height. In St. Louis few are above two stories high, with basement wholly above grade, which with the comparatively large lots, gives favorable opportunity for architectural and landscape effects not possible with higher buildings on more restricted sites. In the typical St. Louis plan the rooms are arranged on three sides only of the corridor, which allows good light and ventilation to the corridors and quick egress by stairways located at each end of them. The wardrobes, as in Boston, open only into class rooms which gives the teacher full control over them and also allows ventilating the room through the wardrobe, which in practice has been found very desirable. In the three cities the best results for temperature are obtained by mechanical heating and ventilating, automatically controlled; the plumbing is of the highest sanitary type, and natural slate blackboards are preferred. The rooms and corridors in St. Louis are made attractive by a stenciled frieze.

**Interesting
Details of
School Building.**

Some interesting conclusions have been reached in Boston. While sunlight in classrooms is thought desirable, it is not considered necessary; it is best to concentrate the toilets in the basement instead of distributing them throughout the building; a gymnasium and roof playground are favored, especially where the lot is restricted; An economical area of floor plan should not exceed on a floor double the area of the class-rooms; windows, one-fifth of floor area; rooms to be thirteen feet high; corridors eight to ten feet wide; play-grounds, walks and roadways brick paved. All new buildings in Chicago are to have an assembly hall on the first floor, kindergarten, bathroom, manual training room and cooking room; small lots are to give way to enlarged play-grounds; grounds are enclosed with substantial iron fences. In both Chicago and St. Louis portable houses are found useful to relieve congested districts till permanent buildings can be provided. With labor and materials abnormally high the cost of buildings in St. Louis in 1904-05, per pupil, ranged from \$124 to \$159; in Boston the average is nearly the same; while in Chicago the cost ranges from \$123 to \$142. In management, the departments in these cities are practically free from political influence. The designing in Chicago and St. Louis is in the hands of the architect of the board of education; in Boston, an architect is selected for each building, and engineers are employed for the heating and electric work. These facts, drawn from varying conditions and covering a wide range of territory, indicate that the school building of the country is proceeding under favorable auspices, that the work averages of a high order, and that there is rapid progress toward all that is best in building and surroundings.

SANITARY ENGINEERING IN THE MODERN OFFICE BUILDING

BY J. PICKERING PUTNAM, ARCHITECT

PART IV

FIGURES 18 to 20 inclusive show some of the different forms of apparatus which have been used in this country for trap testing. One of these, Fig. 19, is an extension or elaboration of actual plumbing work built for ordinary service. The others were erected directly and solely for trap testing. All conform to conditions which may be encountered in ordinary practice.

They all consist in a main soil or waste pipe into which the traps are discharged, and in more or less back vent piping, both straight and bent, to determine the effect of friction in reducing the efficiency of the system.

All demonstrate that back venting, even when the pipes are clean and new and correctly installed in accordance with the law, is unreliable, and that, as a means of protection against siphonage it can not be compared with

put together in order to permit of the greatest possible variety of tests to be made on a single apparatus. But as openings were made in the pipes at various points, we were able to cut off at will one or all of the bends and any part of the length of the pipe. Hence the apparatus could be made to correspond with that in any form of building we desired to imitate. In the high modern office building a much greater length of pipe is encountered than could be represented in any apparatus. But the friction afforded by this great length is in a measure obtained in our apparatus by using the full number of return bends provided.

The soil pipe consisted of ordinary four-inch cast iron hub pipe, put together with putty. Two plunger water closets in common use at the time when these experiments were made were connected with the soil pipe at a platform ten feet above the traps to be tested, and furnished the siphoning discharges. Ordinary two-inch cast iron pipe was used for back venting.

The closets used were the Zane and the Jennings, which were perhaps at that time the most popular in this country. They produced, however, a much severer siphoning strain than any fixture in common use today. Nevertheless the value of thorough water flushing is only now beginning to be understood, and it is certain that the early future will see all fixtures constructed with a view to producing the most powerful possible scour. To effect this they must be constructed, as far as possible, on the principle of the automatic flush tank, and we shall therefore once more encounter the strong siphoning action of the Zane and Jennings closets, and once again the strain on our trap seals will be as great as was provided by this apparatus.

Some years ago, before it became customary to ventilate all the main lines of soil and waste pipes, as all sanitary engineers are agreed in recommending now, there accumulated in the upper part of the pipe system large volumes of dangerous and corrosive gas generated by the decomposition of the heavy deposits in the large soil pipes throughout their entire length. These gases, never liberated as they are now by a constant current of fresh air passing through the main pipes, sometimes formed in such large quantities as to eat through the metal and escape into the house. The water-flushing from the feeble pan closets and restricted basin outlets of that time was quite insufficient to purify the main pipe lines, and serious difficulties arose.

Now, however, the case is very different. All our main pipes are thoroughly ventilated, and a far more liberal flushing is occasioned by the use of modern closets and scientific fixtures of all kinds. This comparatively fresh air of the soil pipes distributes itself by diffusion through the branch wastes, and is forced through by powerful water scour, and gases can no longer collect to any harmful degree.

Consider the case of a branch waste leading from a well constructed wash basin and connected with a well




FIG. 18.
APPARATUS USED AT THE MASSACHUSETTS INSTITUTE OF TECHNOLOGY.

the use of ordinary unvented antisiphon traps in efficiency. If we are to be forced by law to go to the great expense and danger of ventilating every trap, we have a right to demand, first, that the means employed shall actually afford us the security it pretends to, and not fail at the first critical moment, and second, that no other simpler and better means exist for securing the desired result. Our apparatus demonstrates that trap venting must be condemned on both of these counts.

Fig. 18 shows the apparatus used at the Massachusetts Institute of Technology to illustrate a course of lectures on the principles of house drainage, delivered by the writer before the Suffolk District Medical Society and the Boston Society of Architects in 1885. A large number of return bends and a very long stack of piping was

ventilated soil pipe. Fresh air is constantly passing through the soil pipe, carrying off the products of decomposition as fast as they are formed. If the lavatory be frequently used and properly constructed the branch waste pipe is scoured from end to end and kept very free from foul matter. Fresh air is diffused easily from the soil pipe through this branch as far up as to the trap. If, on the other hand, the fixture is rarely used, the last thin deposit of soap dries up on the sides of the pipe, and what little decomposition goes on then is inappreciable, and the products are removed by diffusion, or if they are absorbed in the water of the trap, what could escape from its surface would, as has been demonstrated by the inter-

esting researches of Carmichael and others, be quite infinitesimal and harmless.

Air flushing alone is incapable of removing solid impurities from the waste pipe system, but a strong water flush may be relied upon to keep the entire system clean and safe.

When in addition to these considerations of the growing popularity of strong water-flushing through all fixtures we find, in the combined system of sewage disposal, the soil pipes serving more and more as rain water conductors and when we consider the great height of modern office buildings, we shall see that the use of the plunger closets in these old forms of trap testing apparatus does not give a severer strain on the trap seals than we should provide for as a possibility in the plumbing of the near future.

This technology apparatus demonstrated not only that




FIG. 19.
APPARATUS USED IN THE EXPERIMENTS FOR
THE BOSTON CITY BOARD OF HEALTH.

the seal of an ordinary S trap could be destroyed even when guarded by a new and clean vent pipe applied in accordance with the law, but that the vented S offered much less resistance to siphonage than a simple "pot" or "drum" trap of large diameter without any vent pipe at all.

The seal of the vented S was destroyed by the discharge either of both the closets simultaneously or of either one alone. It was destroyed after two or more discharges, even when the length of the vent pipe was

reduced to fifteen feet by cutting off the two-inch iron pipe and all its bends altogether. This gives us a shorter vent pipe than we should often be likely to encounter in practice. Hence if the friction produced in this short length of pipe is enough to destroy its effectiveness, anything longer than this would be correspondingly more disastrous.

Experiments were made on this apparatus with a partially clogged vent pipe. The supply of air through the vent is then, of course, proportionally retarded, and it affords less and less resistance to siphonage. We have made a great many experiments in this field on a great many different forms of apparatus and on plumbing piping installed for regular use, and have found in all the resistance exactly proportioned, other things being equal, to the size and length of the vent pipe. In our tests for the Boston City Board of Health we used a straight stack of pipes without bends. The siphoning action was equally severe.

In all the different forms of apparatus it has been found that the

large unvented drum traps in common use afford vastly more resistance to siphonage than S traps vented in the best and most approved manner. Indeed, it is found entirely impossible to siphon out an unvented drum trap of six or eight inches in diameter so long as it remains clean inside and retains its full capacity. It is easier to keep a drum trap than a vent pipe clean, because the former is accessible and the latter for the most part inaccessible and can not be made otherwise.

Fig. 19 shows the Boston Board of Health apparatus, except that, for greater clearness, the vent pipe is drawn on the right instead of on the left side of the soil pipe. An extremely powerful strain could be produced on this apparatus by the combined discharges of the large tank and of the Zane water closet on the fourth floor.

In order to permit also of a series of experiments on evaporation a galvanized iron ventilation flue was erected by the side of the soil pipe. This flue was heated by gas as shown, and the speed of the induced air current recorded by an anemometer placed in the enlargement in the basement. The branch pipe for testing the traps was provided with several vent openings in order to show the effect of evaporation when the mouth of the vent was placed at varying distances from the crown of the trap.

Further tests in evaporation were made by connecting a second branch waste below the first with a brick flue heated by a stove. On this and on all the other forms of apparatus we have used and illustrated the results have been identical, namely, a clear demonstration that the vented S is incapable of retaining its seal under severe strains, whereas ordinary anti-siphon traps like the common drum trap of large diameter retain their seals indefinitely so long as their waterway is kept open. Fig. 20 shows a simpler form of apparatus erected at the North End Union of Boston to illustrate a course of lectures on sanitary plumbing, delivered by the writer in 1901.

(To be continued.)







FIG. 20.
APPARATUS USED AT THE
NORTH END UNION.






RESIDENCE FOR W. W. SYLVESTER, KANSAS CITY, MO.
ROOT & SIEMENS, ARCHITECTS.







GENERAL VIEW, BALL-ROOM, RESIDENCE, ST. LOUIS, MO.
MAURAN, RUSSELL & GARDEN.





RESIDENCE FOR L. WOLFF, JR., CHICAGO.
RICHARD E. SCHMIDT, ARCHITECT








RESIDENCE OF F. N. COR
GEORGE W. MAHER, A



F. N. CORBIN, KENILWORTH, ILL.
V. MAHER, ARCHITECT, CHICAGO.




DETAILS, SHEPARD SCHOOL BUILDING, ST. LOUIS, MO.


WILLIAM B. ITTNER, ARCHITECT.




STATION FOR LACKAWANNA RAILROAD, NEW YORK CITY.



STATION FOR BALTIMORE & OHIO RAILROAD, YOUNGSTOWN, OHIO.






Shepard School

Wisconsin Ave near Cherokee St.
St Louis Mo.

WILLIAM B. ITTNER, ARCHITECT.

FIRST FLOOR.




Shepard School.


Wisconsin Ave near Cherokee St.
St Louis Mo.

WILLIAM B. ITTNER, ARCHITECT.

BASEMENT FLOOR



WEST ELEVATION



THE SHEPARD SCHOOL BUILDING, ST. LOUIS, MO.
WILLIAM B. ITTNER, ARCHITECT




FIRST NATIONAL BANK BUILDING, CHICAGO
D. H. BURNHAM & Co., ARCHITECTS






VIEW INTO BANK ROOM FROM LANDING OF MAIN STAIRWAY, FIRST NATIONAL BANK BUILDING, CHICAGO
D. H. BURNHAM & Co., ARCHITECTS.






VIEW TOWARD ENTRANCE.
VIEW IN BALL-ROOM, RESIDENCE, ST. LOUIS, MO.
MAURAN, RUSSELL & GARDEN, ARCHITECTS.






MANTEL IN BALL-ROOM, RESIDENCE, ST. LOUIS, MO.
MAVRAN, RUSSELL & GARDEN, ARCHITECTS.



RESIDENCE OF MRS. L. A. TODD, OAK PARK, ILL.
F. E. ROBERTS, ARCHITECT.










VIEW IN PRESIDENT'S ROOM,
FIRST NATIONAL BANK, CHICAGO.
D. H. BURNHAM & CO., ARCHITECTS.







VIEW OF MAIN BANK FLOOR.
FIRST NATIONAL BANK, CHICAGO.
D. H. BURNHAM & CO., ARCHITECTS.






MAIN STAIRWAY TO BANK FLOOR, FIRST NATIONAL BANK BUILDING, CHICAGO
D. H. BURNHAM & CO., ARCHITECTS.








KENWOOD CHURCH, KENWOOD, CHICAGO.
JOHN S. WOOLLACOTT, ARCHITECT.






MUNICIPAL BUILDING FOR THE DISTRICT OF COLUMBIA
COPE & STEWARDSON, ARCHITECTS, PHILADELPHIA.





THE ILLINOIS APARTMENT BUILDING, KANSAS CITY, MO.
ROOT & SIEMENS, ARCHITECTS.



MUNICIPAL IMPROVEMENTS

BY ALBERT KELSEY, CHAIRMAN OF THE COMMITTEE OF EXPERTS OF THE ART FEDERATION
OF PHILADELPHIA

PART IV—WATER FRONTS

WE have seen that to start right it is necessary to have a good plan—that if a good plan is adopted and adhered to, good results must follow, no matter what is erected upon it. Manufacturing plants for a time may pollute its streams, scores of industrial establishments may foul the air, and private property owners may rain down torrents of ugliness upon their own holdings, and yet there will remain inherent in the plan a beauty that the blackest smoke of industrialism can not obscure.

What are the controlling elements in such a plan? They are geographical and topographical conditions. By geographical conditions is meant the relation of the site to contiguous areas, including both land and water, while topographical conditions refer to the conformation of the site itself. When a site conforms to an interesting shore line, is traversed by a river, or distributed, like Venice or Boston, between and in among water-ways, these liquid areas control the plan—or should control the plan if it is intelligently studied—and in fact does in a measure control even such a poor plan as Manhattan's, where the avenues are all forced to run north and south on account of the narrowness of the island, but much better illustrated by Venice, which without a formal and organic plan, is made uniquely beautiful by its network of sunny lagoons and shady canals. The opposite is unfortunately true of Boston's old cow-path plan, since there all thoughts of water frontages and refreshing street vistas terminating across glistening sheets of water have been until recently ignored.

An observant traveler approaching an American city from its water front can not fail to be struck by the contrast between the natural beauty of our harbors and rivers and the disorder and ugliness that have come upon nearly every place that man has chosen for a center of life and activity. Cities have been called the earth's festers, and one who arrives at New York, either by way of the open harbor or from the Hudson, after passing through scenes of natural magnificence, must indeed feel that this assertion is justified. It is a strange truth, but most American cities, bad as are their approaches by rail or by road, are still at their worst along their water fronts. Even in New York, in spite of its enormous commerce and great wealth, in spite of the fact that it is the official entrance port of the continent and so recognized by the colossal figure of Liberty Enlightening the World, presented by France at a time when light was even more sadly needed in the improvement of that harbor than it is today, and in spite of the fact that it is the one place where diplomats and distinguished visitors make their entrance, yet this metropolis has no official or even worthy landing place, but treats its visitors with indignities that increase from the moment he sees the garbage float down the river until he is landed in a street roughly paved and often full of puddles and refuse, where his life is more or less endangered by rough wagons and other vehicles bent upon commercial pursuits.

The disgraceful confusion attending the mob-like reception of the Czar's envoys in August, was but the nat-

ural outcome of existing conditions. To be sure a granite sea-wall at last forms a bulk-head along part of both arms of the harbor, and West street is theoretically 250 feet wide but actually less, owing to the erection of large head-houses for most of the steamship companies' piers and for all ferry houses, out on the roadway. Also, several promising recreation grounds have been opened on the East Side, and it can not be denied that the parking of Riverside drive on the North river is truly encouraging, but these scattered improvements—which do not impress one from the harbor, are in crude contrast with the inviting entrance Palermo offers with its massive, unified breakwater and clean docks, with its permanent and even monumental reception place facing a wide and smooth sea-walled road, which serves as a reviewing stand and orchestra shelter on ordinary occasions. Or to come to a more democratic example and a case more parallel to that of New York, we might be proud to take a lesson from the city of Bordeaux, where the place of entry is marked by two large rostral columns and an open space set apart for occasions of ceremony. Such a place would serve as an official entrance, and also as a place where individuals could land without the inconvenience that attends the hundreds who now come daily to New York on private yachts.

New York harbor is not our only slipshod harbor, and in fact it is a great improvement on many, where filthy, inflammable and malodorous private docks on flimsy, creaking piles only offer safe shelter and real hospitality to wharf rats and river thieves. This condition is the more shocking to every sense of decency since it is so wantonly needless. Portland, Maine, San Francisco and Boston have glorious scenic advantages and are natural harbors, requiring but a little uniformity to make them more efficient and to preserve their beauty, while many of the great ports abroad have been artificially constructed at an enormous cost, and every basin and dry-dock had to be constructed to especially overcome forces of nature; and yet, working against such odds, every maritime country of Europe has more orderly, more hygienic and more permanent harbor facilities than any port in the United States.

A water front, even though now given up exclusively to commerce, can be redeemed. In fact, the exigencies of increasing traffic by rail and water may be much better met under a comprehensively readjusted scheme. Such a system is being completed at Salina Cruze, in Mexico, as a terminal for the Tehauntepec railroad, which, if the writer is correctly informed, will soon rival in acreage, in equipment and in permanence, the great dock-yards of Hamburg. This system is all of a piece because it was done all according to a far-seeing plan.

A commercial water front must provide ample railway facilities, but not as many wide-awake Americans seem to think, to the exclusion of everything else. At Algiers, in North Africa, an extensive track yard, with many low freight houses, occupies the immediate water front, while the natural slope of the land has made it possible to

construct a great elevated stone arched viaduct on the hillside above. It is the famous Boulevard de la Republique, and from every point along its entire length one gets a superb view, to which interest is largely added by the busy shipping below. At Antwerp, where the shore is flat, a popular promenade is supported on slender steel columns for several hundred yards directly over the busiest docks, thus actually securing a twofold utility from the same area, and in both these cases aesthetic considerations appear to dominate. The French in Algiers had the cleverness to leave a beautiful white mosque at the end of the great modern thoroughfare, whose name so incisively recalls the Mother Country, and the Belgians have likewise kept local conditions alive by restoring an old Flemish building to form a focal point at the end of their strikingly modern promenade.

Now, turning exclusively to river front treatment, we have on the one hand the squalid manufacturing town with its ungainly factories built along banks between the river and the race, thus obscuring an open view, and on the other we have the walled rivers of Europe, of which Paris and Buda Pest offer the best examples. The quays and shaded river drives of Paris are famous. Here the requirements of commerce and recreation are carried on side by side, and yet entirely independent of one another, but to be sure the Seine is not a river from which much power is drawn. Throughout Germany, however, there are many such streams where factories and communal parks alternate along race-ways, thus giving a partial air of tranquility and repose to these busy spots. In contrast to this inspiring picture, consider an example of industrial depravity along the Schuylkill. Dr. Edward Martin, director of public health, said two years ago: "Philadelphia wants drinking water, and not solid food." And yet, notwithstanding annual trips of inspection, followed by vigorous reports, and voluminous newspaper reports which are given wide publicity, the banks of the river from which Philadelphia draws two-thirds of its water supply today are lined with cemeteries, industrial plants, stables, privies, abattoirs, pig pens and hen coops for fifty miles above the intake, and any day, at more than one point, the river may be seen running thick with grease and opalescent oily surfaces which flash gaudy metallic colors from splotches of iron scales set adrift by the furnaces of Manayunk, Phoenixville and Reading. A facetious reporter adding that "a particularly rich deposit is injected from the Norristown Insane Asylum."

It is to be hoped that the horrors of the Schuylkill represent an extreme case, but every American knows that more or less polluted streams with banks strewn with refuse, and cluttered with filthy buildings is still the rule. Some day we shall improve all this, and at one bound we may concentrate much more than has been done abroad in like areas. In order to draw a more hopeful picture, let us consider the possibilities of a navigable river, such as the Allegheny at Pittsburg, a river subject to sudden rises and falls, which widens and narrows with every rain.

Instead of unhealthy mud flats left exposed during droughts, imagine the river compressed between clean stone docks, thus making the entire water surface navigable at all times. On the other side, a steep riprapped embankment would rise to protect railways and canals from inundation, allowing sudden floods to sweep harm-

lessly over the docks, and on top of these breastworks there would be a long, shady promenade. Then across the depressed tracks and canals would be a tree-lined road, and back and facing this would be great warehouses, approached by rail through tunnels built somewhat like Chicago's under ground freight road in the wholesale district. By such an arrangement, what is now waste land in many cities would provide on both shores, (1) warehouses on clean tree-lined streets, free from tracks; (2) direct railway lines and canals, protected from inundation and without grade crossings; (3) a narrow dike park; (4) docks such as those along the Seine, and (5) a river that would scour itself and be navigable at all times.

There is yet much more. There would be an utter detachment between these parallel avenues, freedom from congestion, freedom from loss by flood, freedom in circulation, and lastly a freedom in private and public, civic and social organization now unknown. In short, America may yet have the honor of contributing to city making an efficient system of orderliness and compactness similar in its underlying principles to the vertical filing system for business papers which has been the means of simplifying and developing modern business. Indeed, so much may be gained by bringing the units described above into closer touch with one another, that there is also room and opportunity to give back to the river a beauty equal to that which the present occupancy has taken from it. Man's possession does not necessarily mean the disordered jumble and half-mastery of his opportunities as exemplified at Albany, Cincinnati, Pittsburg, Baltimore, Washington, Norfolk, Kansas City and other cities of this type, but like the ancient treatment of the shores of the Tiber, they may be given an expression of mastery, and in addition, a many-sided usefulness suited to everyday surroundings.

Beautiful as are the banks of the Seine, they do not compare in monumental splendor with the marble and sculptured river walls that once girdled the island forming part of ancient Rome. A French student recently made a set of drawings restoring this design from such fragments as remain. It shows the entire island treated as a great ship, with temples, squares, streets and monuments arranged on a nearly symmetrical plan, while a colossal white marble prow and stern completes the composition.

Such splendor is not for a commercial age, yet at Annapolis, Md., our government is building a naval academy on truly splendid lines. The entire site is being transformed and soon from its terraces a shore line will be seen of which any modern port might well be proud.

Even this hurried article would be incomplete without considering the subject of reclaimed land, artificial lakes and the straightening of water-ways. Utica, N. Y., is about to abandon part of the old barge canal for a new length, to be built parallel with the recently straightened river, thus leaving a wide, open strip traversing the most congested part of the city, while the removal of the river channel has brought a large tract of formerly detached property into the city. But unfortunately, no many-sided plan has been adopted for the permanent treatment of these now available areas, and unless something is done soon a rare opportunity will be lost forever.

It will be remembered, as described in a previous chapter, Paris straightened a water-way by means of a

navigable tunnel, and in doing so also created a fine parkway and a salubrious residential quarter above. Such a bold example of municipal reconstruction makes our self-evident problems appear simple indeed, and yet the simplest of our undertakings are usually studied and carried out only from a single point of view. Such methods bring blundering waste, as exemplified by the new dam now building at Columbus, Ohio, for the storage of its water supply, which will back up the river for two miles, and yet, entirely independent of this undertaking, \$17,000 is being spent to build a neighboring road which has not been planned to take advantage of the fine views and other opportunities this future lake will surely afford.

Returning to the subject of harbors, our deep sea rivers offer but few of the engineering difficulties encountered in constructing the unprotected sea ports of Europe, but on the other hand frequent changes of administration place many obstacles in the way which do not have to be overcome abroad, where under a paternal government appropriations are forthcoming for such works, and such works proceed regardless of minor politics. Few, however, know of an undertaking of this kind being carried out by a philanthropic individual, yet one of the greatest ports in the world was built in this way, and the resulting benefits, as they increase and multiply, not only benefit the inhabitants of Genoa, but also the inhabitants of all northern

Italy, thus nobly glorifying the name of the Duke di Galliera, through whose intelligence and generosity it was made possible. In this is a hint for our own public-spirited citizens. One in Chicago, for instance, might add to his promised art museum a long, narrow island park along the shores of Lake Michigan, to redeem what the Illinois Central railroad has marred, terminating it in a modern port and dock-yard at the river's mouth.

In so brief and imperfect an article it is impossible to cover such a broad subject in all its phases, but it may not be amiss, in closing, to remind those who are seeking new outlets for their generosity, that no better use can be made of money than to supply a city with a far-reaching plan. And, like the Italian duke, if our merchant princes can still afford to carry out such a plan, or even a portion of it, they will add for generations to come to the material and moral prestige of the community so benefited. This is not a problem for city engineers and philanthropists only, it is one the average citizen—rich or poor—can no longer afford to ignore. He must ask himself, "Shall our water fronts be up-to-date, salubrious and starred with frequent breathing spots, or shall they remain foul power plants, sluggish traffic routes, or mere sluice-ways for drifting sewage?"

(To be continued.)

THE PLANNING OF HOSPITALS

BY T. M. CLARK, ARCHITECT

PART II

IN regard to the best arrangements of hospital wards, there is still great diversity of opinion among medical men. That they should be so completely independent that air from one ward can not enter another is agreed, but this is by no means the only question involved. Another, and practically the most important one, is that relating to the number of beds which a ward should contain. The present custom is to make each ward to a certain extent an administrative unit, under the charge of two nurses, one for day and the other for night work. As there is obvious economy in giving each nurse as many patients to look after as she can care for efficiently, the proper maximum number of beds to a ward is determined by the average capacity of a nurse; and experience has shown that thirty should be regarded as the utmost limit, for ordinary hospitals, and twenty for contagious wards. Of late years the tendency has been to reduce these figures materially, and few modern hospitals now allow more than twenty-four beds to a ward; while in many, the limit is twenty; and some of the most recent foreign hospitals have a maximum of sixteen, or even twelve.

As a hospital bed is of a fixed size, varying only within narrow limits, the dimensions of a ward depend primarily upon the number of beds to be accommodated in it. Apart from certain eccentricities of shape, such as circles or octagons, which have at times been adopted in pursuance of various theories of ventilation, or of supervision, the standard plan of a ward for a general hospital is a rectangular parallelogram, of length determined by the number of beds, and their spacing. Except in city hos-

pitals, and others where planning is hampered by lack of room, or other circumstances, the beds are arranged in two rows, with their heads against the longer sides of the parallelogram; and, in the ordinary ward, each of these longer sides is provided with windows. It was once usual to arrange the beds in pairs, with a window between each pair; but the modern practice is to space the beds at equal distances along each side of the ward, and provide a window between every two beds. In order to give room for the usual hospital table between the beds, and for the movement of nurses and attendants, a space of at least five feet in width should be allowed; and, if the beds are three feet wide, this will give a spacing from center to center of the beds of eight feet. This is regarded as the minimum permissible spacing, many hospitals requiring nine or ten feet. The beds at the ends of each row, instead of being set in the corner of the room, where the circulation of air would be less perfect, are now always placed two and one-half or three feet from the end wall, so as to be accessible from both sides; and, in modern hospitals, a window is usually put in this part of the wall, close to the corner, so as to prevent any stagnation of air there.

The importance of arranging windows in the corners of hospital wards is due to the fact, which the designer of hospitals should keep in mind, that moving air, whether foul or fresh, clings with great tenacity to surfaces, either of walls, ceilings or floors, with which it is brought in contact, and creeps along such surfaces, as a rule, with much greater rapidity than it is diffused through the main body of air in the room. Any one can test this pe-

culiarity of the movement of air, which is of great practical importance, by turning on the gas for a moment in a room, without lighting it, and tracing by the nose the rapidity and intensity of its conduction along the wall-surfaces. Most sick people, perhaps from the effort of nature to throw off the disease through the skin and lungs, give off very abundant emanations, which, in some diseases, are so characteristic that an experienced physician can often tell, blindfold, what is the matter with his patient, by the smell of the air surrounding him. These emanations of sickness, while they may not be poisonous, are, at least, not conducive to the health of persons breathing them, and they are often accompanied with particles from the skin, or germs from diseased surfaces, which are positively infectious; so that it is very necessary to sweep away rapidly and continuously all the air which has surrounded a sick person, before it can reach his neighbors by diffusion, or creep to them along walls, floors or ceilings. For this purpose it is not enough to exhaust the foul air from the room by vacuum ventilation; in addition to this all wall, floor and ceiling surfaces should be blown upon by a current of fresh air, to sweep away the stratum of foul air, and the particles of organic dust, which will continue to adhere to them even while the main body of the air is changed. Fortunately, the air which enters a room through any opening, in consequence of the same property of clinging to the surfaces with which it comes in contact, spreads laterally to a certain extent as it enters; and the wall spaces between the windows, if not too wide, are thus more or less effectually swept by the current which at the same time blows from the windows across the room; but this lateral spread of the air currents will not reach far into a corner, so that windows in the side walls, as near the end walls as possible, are a necessity for efficient ventilation. It may be observed, also, that the lateral spread of the air is checked by any sharp change of direction of the movement, so that the rounding of the internal angles of floors, walls and ceilings, now universal in hospital construction, materially assists the thorough aeration of the room, besides facilitating the removal of dust.

The length of the ward being thus determined by the number of beds required on each side, the standard of spacing adopted, and the reservation of the necessary distance between the bed at each end of the row and the corner of the room, the width is next to be considered. Here precedents vary greatly, and the conditions to be fulfilled may vary also. Supposing the beds, with their coverings, to measure six and one-half feet in length, and the head of each to be set one foot from the wall, to allow a free circulation of air around it, the space required for the two rows of beds will be fifteen feet. For the movement of nurses and attendants between the rows of beds a passageway seven feet wide is sufficient, giving a total width of twenty-two feet for the ward. This is generally accepted as the minimum satisfactory width for wards of ordinary hospitals. In practice, it is very frequently exceeded, for various reasons. Where the ward contains more than eighteen or twenty beds, the necessary passing through the central aisle is so much increased that it may be desirable to allow a foot or two of extra width to accommodate it; and accident wards, where there is much passing to and fro of stretchers, may also need a wider central aisle. An argument for wide aisles which is, perhaps, given more credit than it deserves, is that medical tradi-

tion requires that each patient in a hospital ward shall have to himself a certain number of cubic feet of space, from twelve or fifteen hundred to two or three thousand, according to the authority followed. In former days, when artificial ventilation was imperfectly understood, and, even where it was attempted, the means available for securing the aeration of a large room were feeble, and when hospital wards usually had windows only on one side, the provision of a considerable volume of air for each patient, by diluting the atmospheric pollution which it was impossible to remove entirely, undoubtedly lessened the risk to the patients; but at this time, when every hospital ward has windows on the two opposite sides, at least, and is swept night and day by streams of fresh out-door air, supplemented by currents directed by powerful fans, too great cubic capacity, by which the currents are diffused and weakened, may be a detriment, and a serious one, to the efficient aeration of the room. There is a story of a hospital in India, which was built from the directions of medical officers at a distance. One of the stipulations that they made was that a certain number of cubic feet of air-space should be provided for each bed; but they omitted to limit the height of the wards. The hospital was built according to the agreement; but the contractor had found it to his advantage to gain cubic capacity by making the rooms of preternatural height; and the hospital authorities discovered, on taking possession of their building, that if the floors of the wards were covered with beds, placed close together, with no passages between them, there would still be air space enough above them to comply with the specification, although the hygienic conditions would, of course, be otherwise intolerable.

In our case, if the beds are given the minimum spacing of eight feet from center to center, and the height of the ward is restricted to twelve feet, which is the limit in many hospitals, it follows that, in order to give each bed fifteen hundred cubic feet of space, which, under the old rules, would be a very moderate allowance, the distance from the wall to the center of the ward must be something over fifteen and one-half feet, giving a total width to the ward of more than thirty-one feet. Whether so great a width would be advantageous to the patients or not will be considered later; but it is obvious, at least, that the distribution of air-currents and sunlight in the ward may often be a matter of quite as much importance as mere cubic capacity, and that these should be regarded in the final determination of dimensions.

Where a hospital is attached to a medical school, or is used for the instruction of students, it is common to make the central passageway in the wards ten feet or more in width, so as to accommodate a group of observers around the foot of the bed during clinical lectures, without obstructing the service of the ward; and, in many hospitals, ventilation flues, sometimes with open fireplaces attached to them, are built in the middle of each ward, so that the central passageway must be made wide enough to allow beds to be carried past on each side of them. So far as accommodation for clinics is concerned, it is, perhaps, necessary in some cases to provide room for a considerable number of students in the passageway; but the central ventilation flue hardly has, for hospital purposes, sufficient virtue to justify increasing the width of the ward to accommodate it.

(To be continued.)

STATE FIRE PROTECTION

BY F. W. FITZPATRICK

THE fire record for 1904 was appalling. Nearly 7,000 lives and over \$230,000,000 in property were blotted out of existence. Besides this, and only considering the money loss, we wasted over \$500,000,000 in insurance—that is, that amount was paid out for which there was no return in indemnities—and spent probably over \$200,000,000 more for the maintenance of fire departments, sufficient water pressure, etc., in an effort to combat the progress of fires, to cure the evil when it is so very easy to prevent it. Fire really constitutes the most serious tax assessed against us. And the direct loss it entails is unlike most losses that are really but exchanges of property, for what usually means a loss to one is a gain to some one else or many others, but with fire the loss is definite and final, smoke is all that remains.

This year's record bids fair to be a serious one, too. For ten days in February last I kept an accurate record of every fire in the country. Our usual records are made up of fire department reports, insurance returns and such data, that does not by any means represent or tell all the story. I prepared an elaborate scheme to get at all the information during that period and am reasonably sure that I succeeded. I kept that machinery at work for ten days only simply because I deemed that a sufficient test and the cost of making it was about all that an enthusiastic individual not in the millionaire class could stand. During those ten days there were 2,275 fires, involving a total loss of \$14,809,800! On one of those days, February 23d, there were 165 fires, with a loss of \$2,015,700. Think of it, the ten days averaged nearly a million and a half dollars a day! True, some pretty heavy fires occurred during that period, the Hot Springs, the Boston docks and the New Orleans terminal. I had no prophetic knowledge of those fires at the time I started keeping the record. That awful average has not continued steadily, Heaven be praised! But for last year it was \$630,000 a day. Who tells us that from now to the end of the year there may not be fires destructive enough to make our general average the million and a half it was during that test period?

What are we doing to prevent it? We are spending millions for water and fire departments and other alleviations, but blessed little for prevention. Why, there are scarce 3,000 fireproof buildings in the entire country, buildings that justly merit the appellation of being even moderately fireproof. What is directly wasted in fires, our actual loss in money, would be more than sufficient to make every building that is erected in the year absolutely fireproof in all its parts, fittings and furnishings. And our total direct and indirect loss by fire represents just about what we spend every year in new buildings!

We Americans boast of our progress and our leadership among the peoples of the earth, and, I grant you, with justice in a great many respects, but in a great many other respects we are deplorably slow, behind the times, fossilized. For instance, we knew that the Australian ballot system was the proper way of voting, yet every other civilized nation on earth adopted that system before we did. It has been amply demonstrated to us that

postal savings banks under government control are an incalculable boon to the people, yet our legislators have listened to the cooing of our private bankers, and postal savings banks seem as far off as ever they were, though all the countries that amount to anything have them in successful operation. So with fire. We know that building of wood is no longer economy, sensible, rapid, or anything else that would recommend it to a sane man, yet we keep right on using the most inflammable of materials for the construction of our homes, our places of business, and daily exposing the lives of those we hold dear, our own and our property to the imminent danger of destruction. It is as if a man would take all his family and earthly belongings in a wagon and promenade up and down a busy railroad track declaring that he liked the exercise of dodging trains!

There comes a time, spite of the theory of individual rights and all that sort of thing, when for the protection of the many against the insanity of a comparative few, it becomes the duty of the State to step in and say how things shall be done. That duty is recognized by some cities that have passed moderately wise building laws and regulations and enforced them more or less rigorously. But there are still cities lagging behind, cities, even crowded cities, where you can build anything you care to, where it becomes a case of competition among builders as to who can erect the shoddiest construction that will stand up and secure rental returns for a few years. There are goodly sized towns where there is not only no building regulation, but where seemingly the authorities deem that any attempt at regulation of building would be detrimental to the welfare of the place. And it is these small places of today that aspire to and often become the cities of tomorrow. Chicago, New York, Baltimore, all the great cities of our continent, have suffered and are suffering grievously for the sins of their older citizens. The regulations in most of those larger cities are fair, as far as new buildings are concerned, but there are the hoary old fire-traps, built when regulations were not so severe, a constant menace and danger.

Recognizing the folly of lukewarm regulation, the criminality of the absolute absence of regulation and the foolish indifference of the great masses of our people, it has been deemed wise to endeavor to secure State legislation upon the subject. A concerted and strong movement is being made to have all the States adopt a uniform code of building regulations, something quite general in terms, divested of any technical verbiage, brief, though all comprehensive, that will work no particular hardship upon any individual and that will secure a better class of buildings throughout the entire country, a lessening of our horrible fire losses, a prevention rather than any attempted cure of the evil. We are not endeavoring to have any special serum or anti-toxin ready at hand in an attempt to save the patient when once affected, but we are endeavoring to establish a sane quarantine, that will keep out a low, degraded class of building, dangerous to the community and the individual.

With that purpose in view, the following rough draft

of a bill has been made and at the proper time will be urged for adoption by every legislature in the land.

A BILL TO REGULATE THE CONSTRUCTION OF BUILDINGS IN
CITIES, TOWNS AND OTHER SETTLEMENTS IN

THE STATE OF

WHEREAS; The loss of life and of property, both public and private, through fires, having reached appalling proportions, and there being danger that such losses will continue increasing as years go on, by reason of the careless, if not criminal mode of construction of buildings that now generally obtains, and very largely because the people still labor under the mistaken impression that wood and other inflammable materials constitute economical means of construction, and that in most cities and towns there are not sufficiently stringent municipal regulations on that head, or else through negligence or other causes such regulations as do exist are not rigorously enforced, it has become expedient and necessary that the State interfere for the protection of the lives and property of its people. Therefore,

Be it enacted by the Senate and House of Representatives of the State of; That upon the date of approval of this bill the following regulations anent building will become operative throughout the State, and that all parties thereafter constructing buildings in contravention of the spirit and wording of this Act shall be guilty of a misdemeanor and held punishable for such offences as herein provided.

1—In no city or town, village, settlement or aggregation of buildings adjacent but owned by different individuals, shall there be built a frame building of any description more than three stories high, or forty feet above the ground.

2—If such frame structures be built up solidly or continuously upon a block, or along any street or highway, there shall be dividing walls, without any openings in the same, and carried up to at least two feet above the roof line, at least every sixty feet in width and to the full depth of the buildings. Such walls to be at least two bricks thick or their equivalent in fireproof tile, stone, concrete or other incombustible material. And in such continuous buildings, where there are more than four such divided spaces, then the roofs shall be of metal or slate or other spark-proof material.

3—Detached houses and other buildings not higher than three stories and built entirely of wood, or with wooden outer walls and roofs, must be at least ten feet apart. If built of brick walls and unflammable roofs, residences and other buildings may be five feet apart, but the windows in all such walls must not be opposite each other; and if windows be further provided with automatically closing fire shutters or wired glass sash such adjacent walls may be even closer together. The same regulation as to width between buildings is to govern widths of light courts or other openings in the buildings themselves when the solid parts of such buildings are thirty feet wide and over.

4—If a 3-story wooden building is to be used as a tenement, school or hotel, or where more than forty people are housed on a ground space equivalent to 1,500 square feet or less, there shall be two stairways in separate parts of the building and giving directly upon exits from the building, and such stairs shall be accessible from each story and from all parts of the building.

5—In all wooden churches, halls and other places of occasional public assemblage, the auditorium floor proper shall not be over one story, or eighteen feet above the ground, and there shall be a clear and direct stairway of at least six feet width, giving directly upon the main exit to the street from such auditorium floor. If there is a gallery in such hall or church then there must be a separate stairway of at least four feet width giving directly upon the street, and in no case shall such hall or church, built of wood, wood walls, floors and roofs, accommodate more than 200 people in the gallery and 700 on the auditorium floor, nor shall there be more than one gallery in such building.

6—Churches and halls of greater capacity must be constructed as to walls, floors and roof, of unflammable material, and all stairs must be of iron or other unflammable material, and the main or auditorium floor must not be over six feet from the ground. In all such halls or churches there shall be separate and direct exits of at least four feet width, one for every

300 people on the auditorium floor and independent fire proof stairways for each gallery and the equivalent of five feet in width per 300 people accommodated, such gallery stairs giving directly to the street and inclosed in fireproof walls with doors only from the gallery served. Besides this there shall be an outer fire exit with an iron stair at least three feet wide, provided with metal handrails and so arranged as not to cross or be exposed to flame from any window or door in the wall, one such stairway to every gallery over twenty feet from the ground.

7—Hotels, shops or other buildings housing many people may be five stories high or seventy feet if constructed of brick or other unflammable walls and spark proof roofs and wooden floor joists and partitions, but with the air spaces between all joists and studding cut off by bricks, tiles, metal or boards the full size of the square of the air spaces, and that all the plastering be done upon wire lath or expanded metal and that there be tanks and water supply, adequate hose and other necessary precautions taken to minimize the danger of spread of fire. But in all such buildings of five stories in height there shall be a stairway from the street level to the top story inclosed in a fireproof wall, the stairs of unflammable material and absolutely cut off from the basement by fireproof flooring and giving directly to an exit on the street and accessible from every story by an automatically closing fireproof door opening outward, at the landings of the said stair. And in all such buildings there must be brick or other fireproof walls cutting up the floor area in sections of not over 10,000 square feet, and if openings are desired in such walls they shall be protected with automatically closing fireproof doors. All such buildings shall also have, far removed from the aforementioned stairway a fire escape of metal and of approved construction, from the roof to the ground and accessible from open hall-ways at every story.

8—Warehouses or other such buildings, or workshops may be six stories high or eighty feet provided they be enclosed in fireproof walls and roof and their interior structure be of what is known as "mill construction," and if served by enclosed fireproof stairs as described in section 7, and the floor area similarly cut up into sections of not to exceed 10,000 square feet by fire walls and automatically closing fire doors.

9—In all such buildings described in sections 7 and 8 there shall be stairs of the character specified and at least five feet wide in the clear, from story to story, proportioned per 300 employees or people usually or at any time present in such building. And there shall be no open elevator or other wells or skylight shafts or shafting spaces open vertically through the floors. All such necessary openings in the floors must be enclosed in continuous fireproof walls with automatically closing doors thereto or wired glass in metal sash.

10—Buildings of semi-fireproof construction, that is fireproof outer walls and roof, floor construction of wide span concrete or tile and unflammable partitions, but with wood or other combustible floor covering, doors, windows and "finish" generally, though without any open spaces back of such woodwork, and all such woodwork coated with some form of approved fire-retarding paint, may be eight stories or 100 feet high, provided the regulations prescribed about stairs and elevators and fire escapes in former sections be likewise applied to this section, though there may be light wells and other openings vertically in the floors in buildings serving purposes of stores or workshops. In all such structures ample provision of hose and fire apparatus, power for pumps, etc., must be made and constantly kept ready for service.

11—Buildings of absolutely fireproof construction, that is, of walls and roof and all exposed structural parts of fire and waterproof material, and all structural steel members properly encased in cement and protected with at least two inches of brick, fireproof tile, concrete (other than cinder concrete) or other fireproof materials, and the floor construction of flat arches not over eight feet spans or segmental arches of not over sixteen feet spans and of brick or fireproof clay tile or of reinforced concrete of not less than six inches thick and of no weaker amalgamation than one part cement to two parts sand to three parts crushed stone or brick or tile or slag (no cinders) and all the floor coverings, the interior "finish" and the doors and sash and other trimming of the building of unflammable material, and the exposed windows on alleys or courts covered with fire shutters or glazed with wire glass in metal

sash and the stairs and elevators protected by inclosures and doors as provided in other sections, may be of any height desired or as regulated by the municipality; provided that in all such buildings over 100 feet high there shall be maintained tanks on the roof with water in sufficient quantity with necessary hose, pumps in constant readiness and other such individual protection as the fire warden shall deem necessary for that building.

12—Further, the State fire warden may issue special permits or dispensations from these requirements to builders of grain elevators or other such special buildings, to erect them of greater height than the classes above described for buildings built in the different modes of construction, provided he deem them of not extra danger to the surroundings or creating any extra hazard there where they are proposed, and such buildings must be at least 500 feet removed from any other structure and in no way directly endangering any other party's property. And such special buildings must not be used for manufacturing or other purposes than storage only and where not over ten employees are at any time at work upon any one of the upper stories.

13—The fire warden of the State shall be the officer empowered to enforce these regulations. And the governor shall appoint such assistants as the said fire warden may require, who shall be State inspectors of buildings (and whose salaries and the maintenance of suitable offices, providing of stationery, furniture, traveling and other necessary expenses shall be paid from the general fund), and the duties of said inspectors shall be to see that these regulations are enforced throughout the State and to them are hereby given full police powers to enforce the said regulations and to bring offenders there against before the courts of proper jurisdiction.

14—The owner or owners of any building, structure, wall, flooring or any part thereof, where anything in violation of these regulations shall be placed or shall exist, and any architect, builder, plumber, carpenter, mason or other craftsman or laborer who may be employed or assist in the commission of any such violation, and all persons who shall violate any of the provisions of these regulations, or fail to comply therewith, or any requirement thereof, or shall build in violation of any certificate or permit issued thereunder, shall for every and each violation or non-compliance be guilty of a misdemeanor and upon conviction thereof shall be fined not less than \$5.00 nor shall the punishment for the first offense be more than a fine of \$500 or imprisonment for six months, but any subsequent offense or violation of these regulations shall make one amenable to punishment at the discretion of the court.

In the restoration of the senate chamber of the old State house at Annapolis the architects Baldwin and Pennington will be advised by a sub-committee selected from the historical societies of the state.

MANUEL MENDOZA, a Spanish architect, has been awarded the prize for the best plans for the new parliament building for Uruguay. The contest was international in its scope. Mr. Mendoza has charge of the construction.

ARTISTIC HARDWARE*—Continued.

LATER work upon the same lines showed a real development, and it continued to be made by some firms, and with increasing success, down almost to the present decade.

But meanwhile a much more comprehensive movement had been begun, and it had been begun under happier auspices. That is to say, it was marked by the coöperation of artistic designers and of manufacturers who were willing to take trouble and to spend money in securing artistic results. It was about 1883 that the Romanesque revival, stimulated by the success and vogue of the works of Richardson, had begun to make its way over the country, and had enlisted the active-minded and progressive young architects, the successors of those who, in the previous decade, had given themselves to the advancement of Victorian Gothic, and in some cases the same persons. The



ABOUT 1890.

Romanesque had taken almost undisputed possession of the

West, and along with those of its practitioners, who followed it simply because it was the fashion, there were others who believed in it and who were earnest in following out its possibilities. Chicago was the center of this cult in the West, and several of the most capable of the designers of Chicago became interested in the efforts to produce much more artistic work in cast metal than had been produced heretofore. Among these were John W. Root, Louis H. Sullivan and W. B. Mundie. Many of the designs procured from them are still current and among the standard products of the company for which they were made. They were so manifestly superior to anything that had been done before in this country that a distinct demand for artistic hardware followed upon the supply of it. The demand thus created soon stimulated other manufacturers to follow the lead thus opened, sometimes through more or less direct imitations of successful designs, more rarely by the same means by which those designs had been produced—that is to say, by the employment of competent designers.




ABOUT 1891.



ABOUT 1892

drawing by a mere mechanic, never so highly skilled, can replace the attractiveness of the work in which the workman is shaping the creation of his own mind. It is this which distinguishes the stone capitals, the wooden furniture, the metallic grilles and hinges and latches of the best mediæval work from the most successful modern reproductions or imitations. Of course, this method is not directly applicable to modern manufacturing conditions, in which the artistic end must be attained within a predetermined limit of cost. The closest approach to it is made when the designer works in the closest possible connection with the workman; when he does his designing in the factory in which it is to be executed, and acquires by daily contact an intimate, almost intuitive knowledge of the possibilities of



ABOUT 1892.



ABOUT 1893.

the means by which his design is to be reproduced. This is the first condition of progress in industrial art.

Moreover, in cast work there is necessary the intervention between the design and the product of a sympathetic and highly skilled artisan in the modeler, whose intelligent coöperation is required for the interpretation of the design. After the casting is produced, hand work is again brought into requisition for the finishing touches. In the work of the highest class, and also, necessarily, of the greatest cost, there is scarcely any limit to the extent to which this finishing work may be carried. When hand chasing is applied by an artistic artisan without restriction of time or money, the result even of a casting is an original work of art. But evidently for the production of such work by modern industrial methods it is necessary that the employer should himself be appreciative of the value of artistic effect.

*Written at the author's suggestion by the well known architectural critic, Mr. Montgomery Schuyler, of New York, and reproduced by permission from "A History of Architecture in New York," 1898.

*An article forming part of "A Treatise on Locks and Builders' Hardware," by Henry R. Towne, president of the Yale & Towne Manufacturing Company, and past president of the American Society of Mechanical Engineers. John Wiley & Sons, publishers. Price, \$3.00. It is the intention of the publishers of the INLAND ARCHITECT to publish other selections from this work. The book is profusely illustrated and contains more than 1,100 pages, 4x6½ inches.

OBITUARY.

FRANK EUGENE KIDDER, architect, engineer and author of works on building, died October 27th last at Denver, aged 46 years. He graduated in 1879 from Maine State College and about that time had completed his first compilation of the "Pocketbook," destined to become a standard work of reference for architects and builders. He studied architecture at Cornell University and the Massachusetts Institute of Technology, and after practical experience in prominent offices located as architect in Boston. Seventeen years ago, from considerations of health, he removed to Denver, where he engaged in practice as architect and consulting engineer. He was a past president of the Colorado Chapter of the American Institute of Architects and an honorable fellow of the A. I. A. To the building public at large he was best known through his published works and writings, prominent among which are his "Building Construction and Superintendence" and "Churches and Chapels." He was esteemed by the community in which he lived for his uprightness of character.

ASSOCIATION NOTES.

KANSAS CITY CHAPTER, A. I. A.

The officers recently elected are: President, Walter C. Root; vice-president, George Carman; secretary, Francis J. Plym; treasurer, George M. Siemens; directors, F. B. Hamilton, Horace La Pierre and J. W. McKecknie.

CINCINNATI CHAPTER, A. I. A.

The election of officers at the annual meeting, October 19th, resulted in the selection of the following: Gustave Drach, president; Harvey E. Hannaford, vice-president; A. O. Elzner, secretary; George W. Rapp, treasurer; Joseph Marty, member of executive committee.

CONNECTICUT CHAPTER, A. I. A.

At the annual meeting held October 19th, the following officers were elected: President, L. W. Robinson, of New Haven; vice-president, George Keller, of Hartford; secretary and treasurer, W. C. Brocklesby, of Hartford; director, Charles O. Whitmore, of Hartford.

SOUTHERN CALIFORNIA CHAPTER, A. I. A.

In connection with the annual meeting a banquet was served, followed by a literary program. The election of officers resulted as follows: President, A. F. Rosenheim; vice-president, John Parkinson; secretary, Fernand Parmentier; treasurer, August Wackerbarth; board of directors, R. B. Young, Octavius Morgan, Frank D. Hudson. The subject of discussion for the evening was a paper on "Reinforced Concrete," by Louis Ritter, of Chicago, and read by W. L. B. Jenney.

TORONTO ARCHITECTURAL EIGHTEEN CLUB.

At the annual meeting held Tuesday, September 26, the following officers were elected: Mr. Henry Sproatt, president; Mr. E. R. Rolph, first vice-president; Mr. J. C. B. Horwood, second vice-president; Mr. C. D. Lennox, third vice-president; Mr. J. P. Hynes, secretary-treasurer. The regular meetings will be held at noon luncheon every Tuesday, special evening meetings being held from time to time as special subjects arise.

CHICAGO ARCHITECTURAL CLUB.

The meeting of October 16 was of exceptional interest. The feature of the evening was a reading by Louis H. Sullivan from his own writings entitled "Kindergarten Chats." These chats, Mr. Sullivan stated, embodied the experience of his life. They record the development of an architectural student after he has finished with the schools. In answering his questions Mr. Sullivan's well known views on architectural education are elaborated. Those in attendance were greatly interested both in the reader's matter and manner. On the Monday following Henry G. Foreman spoke of "The Outer Belt Park System for Chicago."

NATIONAL SCULPTURE SOCIETY.

The beginning of the society's activity was marked by an exhibition of portraits in the society's room, 215 West Fifty-seventh street, from Wednesday, November 8th, to Saturday, November 18, 1905. The exhibition was open to all members of the society and their friends. The sculptor members of the society were

requested to contribute to this exhibition examples of their work in portraiture. Works that in any way were classed as portraits, busts, single or in groups, reliefs, medals, etc., were admissible. A prominent feature of the exhibition was the special competition for the prizes offered by Mr. J. Q. A. Ward and Mr. I. Wyman Drummond.

COLORADO CHAPTER, A. I. A.

The Chapter expresses its sorrow for the loss of one of its most prominent members in the following memorial:

We, the Colorado Chapter of the American Institute of Architects, contemplate with pride the life, and in genuine sorrow the death, of one of our most prominent members, Mr. Frank Eugene Kidder. Mr. Kidder was born in Bangor, Maine, on November 3, 1859, and died at Denver, Colo., October 27, 1905, in the prime of his manhood, at a time when his life's labors were developing into fruitage, and there was a call for further service at his hands. A graduate from Maine State College in 1879, whence he received the degrees of C. E. and Ph. D.; a student in architecture at Cornell University, and the Massachusetts Institute of Technology, 1878-80; assistant in the office of Ware and Van Brunt, and prominent offices in New York City; experience as a practicing architect in Boston and Denver; he was well equipped to become the author of various text books which are perhaps the crowning achievements of his professional life. His "Churches and Chapels", "Building Construction and Superintendence" and "Roof Trusses" are valuable additions to the library of an architect, and every student and practitioner in building lines knows of "Kidder's Architect and Builders' Pocket Book." Mr. Kidder had been a practicing architect and consulting engineer in Denver for seventeen years, and was highly thought of generally by the profession. He was an active member of the Colorado Chapter of the American Institute of Architects, and its president during the years 1903 and 1904, and an honorable Fellow of the A. I. A. He was a kindly Christian gentleman, and his good offices will be sadly missed in the immediate community in which he lived and labored. In sincere friendship and love, we inscribe upon the records of our Chapter these inadequate notes in his memory, and extend to his bereaved family our heartfelt sympathies.

W. E. FISHER,

President Colorado Chapter, A. I. A.

Attest:

WILLIAM COWE, Secretary.

OUR ILLUSTRATIONS.

Station for Baltimore & Ohio Railroad, Youngstown, Ohio.

Station for Delaware & Lackawanna Railroad, New York City.

Kenwood church, Kenwood, Chicago, John S. Woollacott, architect.

Residence for L. Wolff, Jr., Chicago, Richard E. Schmidt, architect.

Residence for Mrs. L. A. Todd, Oak Park, Ill., E. E. Roberts, architect.

The Illinois apartment building, Kansas City, Mo.; Root & Siemens, architects.

Residence for W. W. Sylvester, Kansas City, Mo., Root & Siemens, architects.

Ball Room, St. Louis, Mauran, Russell & Garden, architects. Three full page views are shown.

The Municipal Building for the District of Columbia, Cope & Stewardson, architects, Philadelphia.

The Shepard School Building, St. Louis, William B. Ittner, commissioner of school buildings, architect.

Residence for F. N. Corbin, Kenilworth, Ill., George W. Maher, architect. Two exterior views, an interior and plan are shown.


First National Bank building, Chicago, D. H. Burnham & Co., architects. The following views are shown: General Exterior; Main Stairway to Bank Floor; Landing of Main Stairway; Interior View, Main Bank Floor; View in President's Room.

Luxfer Sidewalk Lights in Re-inforced Concrete Setting :: Best for Basement Lighting

"LUXFER PRISM
TILE"

No Iron Frames
No Rusting

GREAT STRENGTH
and DURABILITY



RANSOME SYSTEM

"LUXFER BLANK
TILE"

All Steel Imbedded in
Concrete

Watertight and Free from
CONDENSATION

Note the twisted
TENSION RODS
shown in illustration

LUXFER PRISMS IN RE-INFORCED CONCRETE SETTING HAVE NO EQUAL

ARCHITECTS and ENGINEERS are agreed upon EXCELLENCE of this work.

AMERICAN LUXFER PRISM COMPANY

160 Fifth Ave.
NEW YORK

346 Wabash Ave.
CHICAGO

Garfield Bldg.
CLEVELAND

Ryan Bldg.
ST. PAUL

New York Life Bldg.
KANSAS CITY

15 Federal St.
BOSTON

American Bldg.
BALTIMORE



Entrance to Office of Works
at Stamford, Conn.

Cheap Horse Seldom Wins a Race

—a cheap man seldom or never does good work—there's logic in saying that cheap hardware cannot be good hardware. It *may* look nice when bought (we sometimes wonder why its makers don't produce something *better looking* for the money) *but* time and the elements will prove its inferiority.

Time Proves **Yale Hardware** to be good hardware—there's a depth of finish that lasts.

A number of Artistic Brochures of interest to
Architects and Builders will be sent on request.

The Yale & Towne Manufacturing Company

General Offices

9 Murray Street, NEW YORK

Branch Office

88-90 Lake Street, CHICAGO

Other Local Offices : BOSTON, PHILADELPHIA AND SAN FRANCISCO

Baltimore & Ohio Railroad



STOP-OVER
TEN DAYS ALLOWED
on all first-class through tickets at
WASHINGTON
BALTIMORE
PHILADELPHIA

THE PICTURESQUE ROUTE

BETWEEN


Chicago and Eastern Seaboard Cities

Cleveland Baltimore
Pittsburg Philadelphia
Washington New York



D. B. MARTIN
M.P.T., Baltimore.

B. N. AUSTIN
G.P.A., Chicago



Returning From California

Make sure your ticket reads "Shasta-Northern Pacific Route." A beautiful journey up the Pacific Coast to Portland. Eastward over the great transcontinental highway, on the "North Coast Limited," a train without a superior. Magnificent scenery all the way—Mounts Shasta, Saint Helens, Adams, Rainier, and the Cascade and Rocky Mountain ranges.

Comfort all the way if you select the "Northern Pacific-Shasta Route." The best of service. Northern Pacific dining car meals are famous. Any information from C. A. Matthews, General Agent Passenger Dept., 208 South Clark St., Chicago, Ill. You have only to ask.

Northern Pacific Railway

A. M. CLELAND
General Passenger Agent
St. Paul, Minn.



Going to Sea by Rail

Reads like a fairy tale, but is an accomplished fact. One of the most interesting and difficult feats of railroad engineering was the building of a bridge across the waters of Great Salt Lake. This is one of the sights for passengers on their trip to

CALIFORNIA OVER THE UNION PACIFIC

Be sure your ticket reads over this line

Inquire of
E. L. LOMAX, G. P. & T. A.
OMAHA, NEB.

3 Good Books for the Architect's Library

By FRED T. HODGSON, Architect.

THE MODERN ESTIMATOR, describes reliable methods of pricing quantities for competitive work, showing in brief concise form the methods generally employed by the most successful architects. Contains many tables, rules and useful memoranda and gives full details for estimating.

Price, 12 mo. cloth.....\$1.50
Architect's Edition, half leather\$2.00

THE HARDWOOD FINISHER, gives rules and methods for working hard woods, with description of tools required and methods of using. Also treats on filling, staining, varnishing gilding and enameling woodwork of all kinds.

Price, 12 mo. cloth, 320 pages 117 illustrations, \$1.00
Architect's Edition, half leather 1.50

ARCHITECTURAL DRAWING SELF TAUGHT. This work is especially designed for architects and draughtsmen who desire to increase their knowledge of practical architecture. Rules for laying out drawings and executing the same and for drawing the plans, elevations and details of a house are given, including walls, doors, windows, stairs and all other items required to complete a building. 300 pages, 300 illustrations, 18 folding plates.

Price, 12 mo. cloth.....\$2.00
Architect's Edition, half leather..... 3.00

SEND IN YOUR ORDERS TO-DAY

PORTER, TAYLOR & CO.

360 Dearborn Street

CHICAGO, ILL.



The Best Route to Niagara

—IS VIA THE—

MICHIGAN CENTRAL

"The Niagara Falls Route."

Between Chicago, Detroit, Niagara Falls, Buffalo, New York and Boston, and to Michigan points.

Stop-over allowed at Niagara Falls on through tickets.

Reduced Rates for
the Holidays



Ask About the
Niagara Art Picture

C. F. DALY,
Pass. Traffic Mgr., Chicago.

O. W. RUGGLES,
Gen'l Pass. Agent, Chicago.

PROPOSED TESTS OF STRUCTURAL MATERIALS.

A STATEMENT has been issued as follows regarding the proposed investigations of the fire resisting qualities of cement mortars and concretes under the joint direction of the American Society of Civil Engineers, American Society of Testing Materials, Joint Committee on Concrete and Reinforced Concrete, National Association of Cement Users, National Board of Fire Underwriters, National Fire Protection Association, Association of American Portland Cement Manufacturers, Concrete Block Machine Manufacturers' Association and the United States Geological Survey:

The question of the fire resisting qualities of structures in which cement is used as a binder, has been claiming the attention of all constructors for many years, but more particularly since the Baltimore fire, with some experimental work which has given useful information on the subject.

The program for the investigation of fuels by the United States Geological Survey includes tests of the fire resisting qualities of cement mortars and concretes; it has been proposed to carry on similar studies under the joint direction of the National Fire Protection Association and the National Board of Fire Underwriters at the Underwriters' Laboratories in Chicago. The joint committee on concrete and reinforced concrete of the American Society of Civil Engineers and affiliated societies, the National Association of Cement Users, the Association of American Portland Cement Manufacturers and the Concrete Block Machine Manufacturers' Association also contemplated making similar investigations.

In order that these tests should be as exhaustive as possible it was deemed inadvisable for the various organizations to proceed on independent lines, but to unite in a joint investigation.

In response to a call by Mr. Richard L. Humphrey, representatives of the various organizations met at the House of the American Society of Civil Engineers, No. 220 West Fifty-seventh street, New York, on Tuesday, September 5, 1905, at 10 a. m.

There were present representatives of the American Society of Civil Engineers, American Society of Testing Materials,

National Board of Fire Underwriters, National Fire Protection Association, National Association of Cement Users, Association of American Portland Cement Manufacturers, Concrete Block Machine Manufacturers' Association and the United States Geological Survey.

The object of the meeting was explained and after some discussion it was decided to organize a committee for the joint investigation of the fire resisting properties of cement mortars and concretes by the above named societies.

The committee organized by the election of Mr. Richard L. Humphrey, chairman, and Mr. Robert W. Lesley, secretary pro tem.

The first series of tests will be made on sand mortars, no facing being used in the manufacture of the block, which will be of a standard size, 9x12x24.

Another series will be made, using dry, medium and very wet mixture, using three grades of mortars for each condition, viz.: rich, medium and lean.

A series of blocks will be made under the direction of the committee of the Concrete Block Manufacturers' Association, in accordance with common practice.

It is proposed to build a test oven. Three blocks of each series will be submitted to the test, two with the face toward the inside of the furnace and one with the back of the block facing the inside of the furnace. The blocks are to be laid in lime mortar, and four three-inch diameter Bunsen burner jets with a fire brick baffle will be used for heating the furnace. It is proposed to raise, at a uniform rate, the temperature of the test oven to a temperature of 1800 degrees Fahrenheit during a period of one and one-half hours and maintain this temperature for one-half hour. It is then proposed to turn two streams of water of twenty pounds pressure at the nozzle, against the inner walls of the test chamber from points diagonally opposite each other for a period of five minutes.

At the conclusion of the test, wherever possible, it is the intention to make a determination of the strength and other physical properties.

Please mention THE INLAND ARCHITECT when corresponding with Advertisers.

OTIS ELEVATOR COMPANY

NEW YORK

CHICAGO

Passenger
and Freight

ELEVATORS

"THE STANDARD OF THE WORLD"

Chicago Office: Railway Exchange Building, 9 Jackson Boul.

GENERATORS AND MOTORS

ILLUSTRATED IN THIS ISSUE, AT THE

First National Bank, Chicago

===== FURNISHED BY =====

CROCKER-WHEELER COMPANY

Old Colony Building, Chicago

WORKS: Amphere, N. J.

Please mention THE INLAND ARCHITECT when corresponding with Advertisers.

One Million

shingles on the
buildings of
Wm. C. Whit-
ney's Estate
were stained
with

DEXTER BROTHERS'
ENGLISH SHINGLE
STAINS



RESIDENCE ON THE ESTATE OF THE LATE WM. C. WHITNEY, LONG ISLAND, N. Y.

AGENTS:

H. M. Hooker Co., 57 W. Randolph St., Chicago
F. H. McDonald, 90 The Gilbert, Grand
Rapids, Mich.

WRITE FOR PARTICULARS TO

Dexter Brothers' Company
103-105-107 BROAD STREET, BOSTON

TO NEW YORK OVER NIGHT

The 20th Century Limited

Via LAKE SHORE and NEW YORK CENTRAL
The Route of the Government Fast Mail Trains

CHICAGO-NEW YORK 18-HOUR TRAIN

IT SAVES A DAY

Leave Chicago at 2.30 p. m.
Arrive New York at 9.30 a. m.

Leave New York at 3.30 p. m.
Arrive Chicago at 8.30 a. m.

City Ticket Office: 180 Clark Street, Chicago

L. F. VOSBURGH, General Western Passenger Agent

THE CUTLER MAILING SYSTEM


AS INSTALLED IN THE
TRINITY BUILDING—

FRANCIS H. KIMBALL, ARCHT.,

CONSISTS OF TWO SPECIAL CAST BRONZE MAIL BOXES AND TWO CHUTES EQUIPPED WITH LOCKING MAILING OPENINGS DIVIDING THE MAIL UNDER NORMAL CONDITIONS AND PERMITTING CLEANING OR REPAIRS WITHOUT INTERRUPTION TO THE MAIL SERVICE.

WHERE A STANDARD AUTHORIZED MAIL CHUTE EQUIPMENT IS DESIRED THE CUTLER MAILING SYSTEM SHOULD BE SPECIFIED BY NAME.

INSTALLED IN CONNECTION WITH THE U. S. FREE COLLECTION SERVICE ONLY BY THE SOLE MAKERS




THE CUTLER MANUFACTURING CO.
CUTLER BUILDINGS, ROCHESTER, NEW YORK.



Linen Shoe Thread Sash Cord
Italian Hemp Sash Cord
India Hemp Sash Cord
and Samson Spot Cord

WE LIKE TO SEND SAMPLES.

Samson Cordage Works
Boston, Mass.



Rain, Hail and Storm



TRADE MARK

beating against a front door will soon cause it to become white and weather-beaten, unless the woodwork is protected by

SPAR COATING

A perfect finish for exterior woodwork

For Booklet Write

EDWARD SMITH & COMPANY

Varnish Makers and Color Grinders

59 Market St., CHICAGO

45 Broadway, NEW YORK

"FOLLANSBEE BANFIELD PROCESS"

We
make the **BEST**
ROOFING TIN
money
has ever
bought

Our well known

"Scott's Extra Coated"
Brand


has been selling the
country over more than

20 Years

and is to-day in greater
demand than ever!

It is **ALWAYS Good**

FOLLANSBEE
BROTHERS
COMPANY
PITTSBURGH, PENNA.



The Naturo Closet

is the result of a close study of physiology and an earnest desire to better conditions in plumbing. Medical men and others familiar with the human anatomy agree that by its construction it assists nature and improves the health. Its sloping seat renders constant cleanness compulsory.

Fully described in our illustrated catalog.

THE NATURO COMPANY

C. H. Muckenhirn,
President

Salem, N.J.
S

Please mention THE INLAND ARCHITECT when corresponding with Advertisers.

