

Vol. XLVIII No. 4

OCTOBER 1923

of this Edition 7450 are printed

ONE DOLLAR A COPY

ARCHITECTURE

Published by Charles Scribner's Sons

CONSTRUCTIVE
DECORATIVE
LANDSCAPE

BUILDINGS FOR THE Y. W. C. A.
By William F. Thompson, Architect

"COLONNADE ROW," LA GRANGE
TERRACE, NEW YORK CITY, 1836-1923

THE NATIONAL MANUFACTURERS BUILDING
NEENAH, WIS. Childs & Smith, Architects

SWEDISH ARCHITECTURE

BARNABY MANOR, PRINCE
GEORGE COUNTY, MD.
Measured Drawings by Albert P. Erb

THE QUALITY OF MATERIAL
By Richard P. Wallis

STEEL AND REINFORCED
CONCRETE IN JAPAN

THE CONSTRUCTION OF THE
APARTMENT-HOUSE
By H. V. Walsh

DRAFTING-ROOM MATHEMATICS
By DeWitt Clinton Pond

COUNTRY RESIDENCES




CHARLES SCRIBNER'S SONS

CHARLES SCRIBNER, President
ARTHUR H. SCRIBNER, Treasurer
CHARLES SCRIBNER, JR., Secretary

597-599 FIFTH AVENUE, NEW YORK

Published on the 25th of the month. Entered as Second-Class Matter, March 30, 1900,
at the Post-Office at New York, New York, under the Act of March 3, 1879. 7 BEAK STREET, LONDON, W.1.




If The Architect Appreciates Progress



THE Johnson Service Company has taken every detail of its temperature regulation construction into its own hands. The dampers, for example, used are now of Johnson make; because dampers made by others were found not always reliable, not durable and sometimes difficult to operate by thermostats. Johnson made dampers are designed and included in installations with distinct knowledge of the relationship between the thermostat, the diaphragm and the damper; and exactly what power the thermostat exerts through the diaphragm motors at different times on the damper. This delicate and most seriously consequential element of automatic temperature regulation thus conquered and corrected furnishes perfect positiveness of not even the slightest variance or halt in the operation of The Johnson Pneumatic System Of Temperature Regulation. Yet, this is only another one of the reasons why automatic temperature regulation is completely successful in institutions, public buildings and large residences today; only another one of the reasons why it merits the architect's endorsement today. • • •

Johnson Service Company
Milwaukee

AUTOMATIC TEMPERATURE REGULATION FOR 37
YEARS, 26 BRANCHES—UNITED STATES AND CANADA



THIS IS NOT A CATALOG

READ what Mr. John J. Donovan, A.I.A., one of the foremost school architects in the country, has to say about natural lighting and ventilation in schools. This interesting article and a resume of the famous report of the New York State Commission on air conditioning are in "Daylighting Schools," which is just off the press.

Naturally a wide variety of Truscon Steel Windows adaptable for every type of school design are profusely illustrated in this book. To make it more complete there are nine full pages of beautiful architectural details.

"Daylighting Schools" is not a catalog but an instructive book crammed full of vital information. Every architect and engineer, and every school board member interested in the school construction, should read it. Send for your copy today.

Truscon Steel Co., - Youngstown, O.

Sales Offices and Warehouses from Atlantic to the Pacific

TRUSCON
STEEL WINDOWS

Please mention ARCHITECTURE in writing to manufacturers

Have You These Books in Your Library?

Early American Domestic Architecture

By PROFESSOR FISKE KIMBALL

Published under the auspices of the Metropolitan Museum of Art


With more than 200 photographs and plans of the best examples of Colonial houses
Special net \$12.00

The Construction of the Small House

A SIMPLE AND USEFUL SOURCE OF INFORMATION ON THE METHODS OF BUILDING SMALL AMERICAN HOMES FOR ANYONE PLANNING TO BUILD

By

H. VANDERVOORT WALSH,
Instructor of Construction in the School of Architecture, Columbia University
With many illustrations by the author \$5.00



The Chief Works of Wren.

Sir Christopher Wren, Scientist, Scholar and Architect

By SIR LAWRENCE WEAVER, K. B. E., F. S. A., Hon. A. R. I. B. A.

With portraits and illustrations of Wren's Work.

12mo. \$2.75 net

An interesting summary of Wren's life, character and achievements.

English Homes

PERIOD I, VOL. I, NORMAN AND PLANTAGENET, 1066-1485

By H. AVRAY TIPPING, M. A., F. S. A.

Over 400 illustrations and plans \$25.00 net

The English Interior

A REVIEW OF THE COURSE OF HOUSE DECORATION

FROM TUDOR TIMES TO THE END OF THE EIGHTEENTH CENTURY

By ARTHUR STRATTON, Architect

Containing upward of 100 full-page plates, presenting many illustrations printed in collotype, including a series of measured drawings, and numerous illustrations in the text, from photographs, sketches, drawings, and engravings. Large quarto \$32.00 net

Concrete Construction for Architects

By DEWITT C. POND, author of "Engineering for Architects"

With many drawings by the author \$4.00

"It shows a knowledge of the architectural aspects of the problem which is lacking in engineering books on the subject."

English Interiors from Smaller Houses of the XVIIth-XIXth Centuries (1660-1830)

By M. JOURDAIN

Author of "Decoration and Furniture in England During the Later XVIIIth Century," etc.

Containing 208 pages with 200 illustrations, finely printed in sepia, from photographs and drawings. \$10.00 net

The Enjoyment of Architecture

By TALBOT F. HAMLIN

\$3.00

A book every architect will enjoy reading and one that the student and layman will find the best possible introduction to the study of a fascinating art.

Old New England Houses

Old New England Doorways

By ALBERT G. ROBINSON

Beautifully illustrated with the author's unique photographs
Each \$5.00

English Homes

PERIOD IV, VOL. I, LATE STUART, 1649-1714

By H. AVRAY TIPPING, M. A., F. S. A. \$25.00 net

Small French Buildings

By HENRY M. POLHEMUS, LEWIS A. COFFIN, JR., and ADDISON F. WORTHINGTON

Illustrated with many original photographs, pen-and-ink drawings, and drawings of measured details. Quarto \$10.00

Architectural Rendering in Wash

By H. VAN BUREN MAGONIGLE

With illustrations by the Author and other famous Architectural draftsmen \$5.00

Mr. Magonigle's book has met with the highest approval of all the Architectural Schools and has the endorsement of the entire profession.

Write for catalogue of ARCHITECTURAL BOOKS

Any architectural book published may be ordered from our ARCHITECTURAL DEPARTMENT

CHARLES SCRIBNER'S SONS, NEW YORK



*The Ohio Valley Trust Company Building, Coraopolis, Pa. Albert Kahn, Architect.
The Foundation Company, General Contractor.*

Into the new home of the Ohio Valley Trust Company, the architect has introduced many novel ideas which make it a model banking house. No pains have been spared to produce a building affording every convenience to patrons and economy of operation for owners. Its sturdy permanence combined with beauty make it a landmark. Owners and architect sought the best and it is significant that they chose The Foundation Company as General Contractor.

THE FOUNDATION COMPANY

CITY OF NEW YORK

*Office Buildings
Industrial Plants
Warehouses
Railroads and Terminals
Foundations and Underpinning
Filtration and Sewage Plants*

ATLANTA
CHICAGO
PITTSBURGH
MONTREAL


SAN FRANCISCO
LOS ANGELES
PHOENIX
PORTLAND, ORE.

LONDON, ENGLAND
PARIS, FRANCE
LIMA, PERU
RIO DE JANEIRO

*Hydro-Electric Developments
Power Houses
Highways
River and Harbor Developments
Bridges and Bridge Piers
Mine Shafts and Tunnels*

BUILDERS OF SUPERSTRUCTURES AS WELL AS SUBSTRUCTURES

Please mention ARCHITECTURE in writing to manufacturers



Lincoln Memorial,
Washington
Henry Bacon
Architect

It has been said that no one can look upon the Lincoln Memorial, at Washington, without feeling a renewed reverence for America's most beloved president. . . . Earl Horter has reflected something of its dignity and spiritual beauty in this Eldorado drawing.

DIXON'S ELDORADO

"the master drawing pencil"

JOSEPH DIXON CRUCIBLE COMPANY

Pencil Dept. 1-J Jersey City, N. J.

Canadian Distributors:—A. R. MacDougall & Co., Ltd., Toronto



DIXON'S


Eldorado Eraser

A worthy partner of Dixon's Eldorado pencil. Soft—pliable—yet firm enough to clean the drawing without crumbling into aggravating little bits. Made in 12 sizes. Write for a sample. Free on request.

SAMPLE OFFER

Write for full-length free samples of "The master drawing pencil" and of Dixon's "BEST" Colored Pencils. In their field, the "BEST" Colored Pencils hold the same position of supremacy as Dixon's Eldorado.

Please mention ARCHITECTURE in writing to manufacturers



*“The
Adver-
tisements
In There
Will Show
You What
You Need.”*

WHAT IS YOUR JUDGMENT
OF THE ADVERTISEMENTS
IN ARCHITECTURE? DO THEY
GIVE YOU AND YOUR CLIENT
THE INFORMATION YOU NEED?

Read the advertisements both large and small
in this October issue of ARCHITECTURE
and then choose the three which you believe
are the best.

Then tell us which one of these advertisements you
consider the best; tell us what No. 2 lacks to make it
No. 1, and what you would do to improve No. 3.

If your criticism is the best we receive you will win:

FIRST PRIZE
\$50.00 in cash

SECOND PRIZE
\$25.00 in cash

THIRD PRIZE

\$15.00, your choice of architectural books
Published by Charles Scribner's Sons

FOURTH PRIZE

\$10.00, your choice of architectural books
Published by Charles Scribner's Sons

Every reader of ARCHITECTURE connected with the architectural profession is eligible
to submit a criticism. The awards will be based on the most constructive critical ideas
submitted. Competent advertising men will pass upon your suggestions and make the
awards. Send us your criticism not later than November 1, 1923.

Address “ARCHITECTURAL ACCEPTANCE”

Trade-Mark


Care of

ARCHITECTURE

Published by Charles Scribner's Sons, 597 Fifth Ave., New York

KEWANEE

Steel Boilers—*their
strength is KNOWN*



Look at this husky joint—of steel plate, riveted. The strength of such a joint is a known quantity—there's no "guess" about it. Joints like this make Kewanee Boilers as sure, and safe and solid as the Rock of Gibraltar.

*That's one reason why, in a period of more than
30 years, no Kewanee Boiler has ever worn out*

KEWANEE BOILER COMPANY

KEWANEE, ILLINOIS

Steel Heating Boilers, Radiators, Tanks, Water Heating Garbage Burners


BRANCHES

CHICAGO	822 W. Washington Boul.	MILWAUKEE	Mer. & Mfrs. Bank Bldg.
NEW YORK	47 W. 42nd St.	PITTSBURGH	Empire Bldg.
DES MOINES	315 Hubbell Bldg.	DENVER	514 Boston Bldg.
KANSAS CITY	2014 Wyandotte St.	DALLAS	809 Southwestern Life Bldg.
INDIANAPOLIS	509-510 Occidental Bldg.	DETROIT	1772 Lafayette Boul.
ST. LOUIS	4200 Forest Park Boul.	TOLEDO	1121-22 Nicholas Bldg.
MINNEAPOLIS	708 Builders Exchange	CLEVELAND	706 Rose Bldg.
COLUMBUS, O.	808 1st Natl. Bank Bldg.	ATLANTA, GA.	1521 Candler Bldg.
SALT LAKE CITY	204 Dooly Bldg.	SAN FRANCISCO	216 Pine St., Rooms 210-11


CANADIAN REPRESENTATIVES—The Dominion Radiator Co., Ltd.

Toronto, Ont., Montreal, Que., Winnipeg, Man., Hamilton, Ont., St. John, N. B., Calgary, Alta.

Please mention ARCHITECTURE in writing to manufacturers



Pile driving, in crowded quarters where delay spells expense and poor piling means catastrophe, is easily and quickly and safely accomplished by the Raymond Method—that is, the pouring of the concrete into spirally reinforced steel shells which are left in the ground.



*"A Form
for Every Pile—
A Pile
for Every Purpose"*

RAYMOND CONCRETE PILE COMPANY

New York: 140 Cedar Street


Chicago: 111 West Monroe Street

Montreal, Canada

Branch Offices in Principal Cities

RAYMOND

Please mention ARCHITECTURE in writing to manufacturers



Welte Philharmonic Pipe Organ in a residence in Brooklyn, N. Y., in which part of the basement space of the home is effectively utilized for the installation of the organ

Utilizing the Basement for Residence Pipe Organ Installation

ONE of the most practical locations for installation of Residence Pipe Organs is in the basement. We have found, through wide experience, that ample basement space is usually available in houses already built or can easily be made available in houses being planned.

In basement installation of residence pipe organs the tone can be brought up and distributed to desired points in innumerable charming and effective manners without robbing the house of valuable space which otherwise may be used for living quarters.

The services of the Welte staff of pipe organ technicians are always available to architects and any one contemplating the installation of a residence organ.

THE WELTE PHILHARMONIC RESIDENCE PIPE ORGAN

MAY BE HEARD INFORMALLY, AT ANY TIME, AT
THE WELTE-MIGNON STUDIOS, 665 FIFTH AVENUE, AT 53rd STREET, NEW YORK

ALSO OWNER OF THE WORLD-FAMOUS ORIGINAL WELTE-MIGNON

Please mention ARCHITECTURE in writing to manufacturers



An Early Louis XV

Design of Rare Beauty

The original brocade which inspired this exquisite fabric is now preserved in the Besselièvre Collection.

An achievement in modern textile weaving, this brocade is characteristic of the beauty and rare quality which distinguish Schumacher fabrics. It is appropriately used for hangings and furniture coverings in interiors reflecting the atmosphere of the transition period between Louis XIV and Louis XV.


The artistic appreciation which characterizes the designing of Schumacher brocades and damasks and the skill with which they are woven places them among the finest

fabrics of all time. In addition to brocades and damasks the Schumacher collection includes tapestries, velvets and interesting linen prints.

Your own decorator or upholsterer will make arrangements for you to see the Schumacher fabrics including the brocade illustrated. He will also arrange the purchase for you.

F. Schumacher & Co., Importers, Manufacturers and Distributors to the trade only, of Decorative Drapery and Upholstery Fabrics, 60 West 40th Street, New York City. Offices in Boston, Chicago and Philadelphia.

F. SCHUMACHER & CO.



BEAUTY! Utility! That rare combination, universally sought in all things, is here achieved.


Each roof of Johns-Manville Colorblende Asbestos Shingles has the charm of soft coloring, the pleasing beauty of ever varying tone and, withal, a hardness of structure that means permanence of beauty and permanent safety for all of those prized

possessions which the roof protects.

For Johns-Manville Colorblende Asbestos Shingles are rock, and to rock, fire and the years mean nothing. They are given highest ratings by Underwriters' Laboratories, Inc. May we send you a booklet in colors? Send a post card request to Johns-Manville, Inc., 296 Madison Avenue, New York City.

JOHNS~MANVILLE ASBESTOS SHINGLES





Straight Facts on Straight Line

Right at your finger tips too! For The Linoleum Data Book fits your files and is plainly marked with the A. I. A. index number, 28 i l.

Between its covers are the straight facts about Nairn *Straight Line* Inlaid Linoleum—what it is, where it may be used to advantage, the different grades, weights, and so on.

But that is only one division of the book.

It contains complete data regarding the many varieties of Nairn Linoleum with handy technical tables and specifications. Especially interesting are the many suggested *new uses*.

A young encyclopedia, concise and readily get-at-able. That is the Linoleum Data Book.

And it's yours for the asking.

NAIRN LINOLEUM COMPANY

201 Belgrove Drive, Kearny, N. J.

W. & J. SLOANE: Wholesale

Sole Selling Agents

NEW YORK

SAN FRANCISCO



Nairn Linoleum Company
201 Belgrove Drive
Kearny, N. J.

Gentlemen: Please send me the Linoleum Data Book.

Name

Firm

Address


City..... State.....

Please mention ARCHITECTURE in writing to manufacturers

Armstrong's Linoleum

for Every Floor in the House

Look for the
CIRCLE "A"
trademark on
the burlap back



A private office in the
American Exchange Na-
tional Bank, New York City,
floored with Armstrong's
Green Battleship Linoleum.

For Specifications, see
Sweet's, pages 442-447

Beautiful, Quiet Floors for the Bank

RESILIENCE is the quality that distinguishes linoleum from harder, denser floors—a resilience that insures quiet and means foot comfort for workers.

It is cork that makes linoleum springy. Cork also is tough, non-absorbent, waterproof. A binder of oxidized linseed oil adds to the toughness and resilience.

Cemented in place to the concrete subfloor, a smooth, seamless linoleum floor is easily and efficiently maintained by waxing and polishing. So laid and intelligently cared for, there is practically no wear out to linoleum. Floors laid twenty and

thirty years ago are still apparently as good as new.

The range of Armstrong designs enables you to assign the floor its proper part in the architectural ensemble. Marble and tile patterns, for example, for the public areas, solid color battleship gauges for the working spaces, two-tone jaspés and artistic carpet designs for the private offices and conference rooms.

Finally, if you would learn how moderate is the cost of modern floors of Armstrong's Linoleum, write for samples and the names of contractors who will cheerfully, and without obligation, furnish quick figures on any job, large or small.

Armstrong Cork Company, *Linoleum Division*, Lancaster, Pa.

A20

Please mention ARCHITECTURE in writing to manufacturers

A ROOF FOR EVERY BUILDING

THE NEW GIBSON HOTEL CINCINNATI

Gustave Drach

Architect
Cincinnati

Wells Brothers
Construction Company

Builders
Chicago

Roofed with Carey Asphalt-
Feltex Built-up Specifica-
tion Number 8.



THIS hotel reflects credit not only on the architect who designed it but on the entire profession.

It is one thing to create a work of art with unlimited endowment funds, and quite a greater thing to put quality and fine art on a paying business basis.

Carey Built-up roofing was selected not only because it was thought to be the most modern permanent roofing available, but because it was recognized that such a roof pays. Write for the complete Carey Specification Book.


THE PHILIP CAREY COMPANY

513-533 Wayne Avenue, Lockland, Cincinnati, Ohio

Carey
BUILT-UP ROOFS

1873 FIFTY YEARS OF PROGRESS 1923

Please mention ARCHITECTURE in writing to manufacturers



A Foe of Heat and Cold

*Home of C. H. Bagley, Duluth, Minn.
F. W. Perkins, Architect*

In planning a home, the most vital factor in the safeguarding of health and comfort—the roof—should be of special consideration.

Being non-conductors of heat and cold, IMPERIAL Spanish Tiles add greatly to comfort and the general health. During even the hottest weather, the air in an attic covered with these tiles is as cool as in any other part of the house. In winter, on the other hand, IMPERIAL Tiles afford the greatest possible protection from the cold.

IMPERIAL Spanish Tiles may be used with good taste on almost any structure which carries the slightest trace of Mission architecture. They are available in many different colors and textures.

 **IMPERIAL** 

Spanish Tiles

LUDOWICI-CELADON COMPANY
104 South Michigan Boulevard - Chicago, Illinois


(19)

Please mention ARCHITECTURE in writing to manufacturers

AUSTRAL WINDOW HARDWARE


Wood-Rolled Steel Construction

Metal Covered-Hollow Metal Construction



*Benj. Bosse High School, Evansville, Ind. Joseph C. Llewellyn Company, Architects; Capelle & Troutman, Associate Architects.
Light and Air in the Benjamin Bosse School will be controlled by over 395 AUSTRAL WINDOWS.*

How Schools Are Assured of Light and Fresh Air



Send for this demonstration cardboard model of the Austral Window.


Modern schoolroom efficiency demands Fresh Air Without Draft and Proper Diffusion of Light.

AUSTRAL WINDOWS provide health-giving fresh air with a flexible control of daylight. The window may be adjusted for any degree of ventilation and the shades on the sash produce a perfect awning effect without hindering the air currents.


AUSTRAL WINDOWS are so accurately balanced that they can easily be managed by the school child. They cost no more than ordinary windows and eliminate pulleys, weights, chains, adjustable screws, awnings, and all window trim and trouble.

101 PARK AVE. AUSTRAL WINDOW CO. NEW YORK CITY


Please mention ARCHITECTURE in writing to manufacturers



Polo Grounds



Yankee Stadium



Yankee Stadium Installation

A Champion Among Champions

The new Yankee Stadium, baseball's finest plant, is equipped with a battery of six RUUD Instantaneous Automatic Gas Water Heaters.

Over at the Polo Grounds, McGraw's

famous Giants bathe in RUUD Hot Water after each game.

It is altogether fitting that RUUD, the world's leading automatic water heater, should serve these baseball champions.

*Write us for Ruud Architect's Specification Folder
made to fit your permanent file*

RUUD MANUFACTURING COMPANY
PITTSBURGH, PENNA

BRANCHES IN ALL LARGE CITIES

RUUD AUTOMATIC GAS WATER HEATERS

Please mention ARCHITECTURE in writing to manufacturers




SARGENT
HARDWARE

ILLINOIS LIFE INSURANCE BUILDING
CHICAGO, ILL.

Holabird & Roche
Architects

Avery Brundage Company
General Contractors

There are three principal considerations which ordinarily influence a wise selection of finishing hardware. They are efficiency, appearance and cost. Probably the order of their importance changes with various types of buildings, but the fact that



have been so often chosen for the equipment of buildings of all types and classes seems to indicate that they possess all three requisites to an unusual degree.

SARGENT & COMPANY

NEW HAVEN, CONNECTICUT

New York

Chicago

"Details to which Standard Hardware can be applied" are printed in our catalogue. We have additional copies of these pages, bound with a cover, that we shall be pleased to send to Architects and Architectural Draftsmen upon request.

Please mention ARCHITECTURE in writing to manufacturers



ALUNDUM SAFETY TILE
makes station stairways slip-proof
and increases the life of each tread

The Metropolitan Railway Company and the Metropolitan District Railway Company of London, England, recognize the economy of equipping station stairways with this Norton product.

ALUNDUM TILE has solved their problem at Wembley Park and Victoria Stations, pictured here. It will solve the problem in any railroad or subway station.

NORTON COMPANY


Worcester, Mass.

NEW YORK CHICAGO PHILADELPHIA DETROIT


NORTON COMPANY OF CANADA, LIMITED

HAMILTON, ONTARIO

T-79



Please mention ARCHITECTURE in writing to manufacturers



“Hartford-Saxony”

A rug that fears no wear

*Made exclusively by the Bigelow-Hartford Carpet Company
at their mills in Thompsonville, Conn.*

HARTFORD-SAXONY” rugs are supreme in services where the wear is greatest. There are more yards of “Hartford-Saxony” rugs and carpets in the lobbies, corridors and public rooms of the leading hotels of this country, than of any other American-made fabric.


They have a heavy, deep pile that gives a luxurious tread, are rich in soft, blending colors, adaptable to any decorative scheme, and will stand more continuous hard wear than any other floor-covering on the market.

“Hartford-Saxony” rugs are made in twenty-seven stock sizes, from 22½ in. by 36 in. to 11 ft. 3 in. by 24 ft., and special sizes can be made to order. They are so moderate in price that a small size rug, 3 ft. by 5 ft. 3 in., can be obtained for about \$24.00; a standard room size, 9 ft. by 12 ft., for about \$135.00. Prices on other sizes are in proportion.

Most reputable dealers carry “Hartford-Saxony” rugs. If you have any difficulty in procuring them, communicate with us. We will see that you are supplied by the dealer nearest your home, who does carry them.

Bigelow-Hartford Carpet Company
385 Madison Avenue ESTABLISHED 1825 New York City

A booklet which tells, in picture and story, the interesting process of making “Hartford-Saxony” rugs, and which shows, in full color, the use of these rugs in various rooms, will be sent gladly on request.





On the floor is shown pattern No. 386—a popular wood design in warm tones of brown.



*“Dem chilluns sho’ am
‘joyin’ dat birfday party.”*

And there’s no need to worry about the crumbs or ice-cream that little fingers may drop on the new *Gold-Seal Congoleum Rug*. This attractive rug which so much resembles a handsome parquet floor has a smooth, waterproof—even accident-proof—surface. A damp mop makes it sanitary and spotless in a jiffy.

For beauty of pattern, durability, neatness and cleanliness, there’s no floor-covering better suited to nursery, maid’s room, kitchen or pantry. *Gold-Seal Congoleum Rug* designs vary from simple tile and wood effects to elaborate, Oriental motifs. Wherever they are used they bring added cheer and brightness to the room.

And another feature—*Congoleum Rugs* lie perfectly flat without fastening. There are never any curled-up edges or corners for little ones or grown-ups to trip over.

Congoleum Rugs give absolutely guaranteed service—yet are moderately priced as follows:

6 ft. x 9 ft.	\$ 9.00	Pattern No. 386 (illustrated) is made in all sizes. The other patterns illustrated are made in the five large sizes only.	1½ ft. x 3 ft.	\$.60
7½ ft. x 9 ft.	11.25		3 ft. x 3 ft.	1.40
9 ft. x 9 ft.	13.50		3 ft. x 4½ ft.	1.95
9 ft. x 10½ ft.	15.75		3 ft. x 6 ft.	2.50
9 ft. x 12 ft.	18.00			

Owing to freight rates, prices in the South and west of the Mississippi are higher than those quoted.

CONGOLEUM COMPANY INCORPORATED

Philadelphia New York Boston Chicago San Francisco Kansas City Minneapolis
Atlanta Dallas Pittsburgh Montreal London Paris Rio de Janeiro

Gold Seal
CONGOLEUM
ART-RUGS



Pattern No. 378

Pattern No. 518

Pattern No. 538



The Wrigley Building, Chicago, Ill., is trimmed with Genuine Mahogany. Architects, Graham, Anderson, Probst & White. Woodwork Contractors, Languist & Illsley Co.

THIS magnificent structure is an outstanding example of the beauty and strength of modern architectural design. It is interesting to note that the interior of this building, in keeping with its dignity, is trimmed with Genuine Mahogany.

Mahogany has been extensively used for panelling, trim and doors—whether

in large office buildings or in small residences—because it offers a rare combination of beauty and utility. The initial cost of Mahogany is only slightly higher than that of many other hard woods and in some instances it is the same. Its long life and permanent beauty impart a value to Mahogany that cannot be equalled by any other cabinet wood.

The Mahogany Association advocates the use of Genuine Mahogany for interior trim in banks, hotels, club houses, offices. Mahogany is being brought to this country from Central America, the West Indies and Africa in sufficient quantities to supply all demands. We will gladly furnish upon request any information desired relative to Mahogany, and your inquiry will not be made the subject of solicitation.

MAHOGANY ASSOCIATION, INC. 1133 BROADWAY, NEW YORK

FURNITURE

MAHOGANY

WOODWORK

Please mention ARCHITECTURE in writing to manufacturers



Architects who want a mortar of beauty as well as of strength and endurance specify Carney for buildings like the Whittier Apartments at Detroit, Michigan.

Architect: Chas. N. Agree,
Contractor: W. E. Wood Co.


A Carney Wall Is a Perfect Wall

CARNEY mortar in the wall becomes harder than the brick or tile it binds. The mason does not have to jiggle or tamp the brick in using Carney mortar, therefore, a Carney wall is a true wall. On account of the simple formula there are no mixing errors resulting from carelessness. These are some of the reasons why the Carney wall is always a perfect wall.

Carney Has These Exclusive Merits

It requires no lime, assuring protection against adulteration or errors in mixing. Being more plastic and smoother working, the mason can work faster and easier on the wall. It lays the maximum number of brick to the barrel. It works perfectly in cold

weather. It becomes harder than the brick and tile it binds, continuing to harden indefinitely as time goes on. It is ideal for wall bearing buildings. The final cost of a Carney wall is always lower. Contractors bid lower and do better work with Carney.



This book tells the complete story of Carney. It will be sent free to anyone interested in building.

The Carney Company

Cement Makers Since 1883

Mankato, Minn.

District Sales Offices:

Leader-News Bldg., Cleveland; Chamber of Commerce Bldg., Chicago;
Omaha National Bank Bldg., Omaha; Syndicate Trust Bldg., St.
Louis; Book Bldg., Detroit; Builders' Exchange, Minneapolis.


CARNEY

for Brick and Tile Mortar

Specifications: 1 part Carney to 4 parts sand.
(due to refined process of manufacture.)

Please mention ARCHITECTURE in writing to manufacturers

DULL LUXEBERRY WOOD FINISH



ATTAINING SUPERB WOOD EFFECTS WITHOUT RUBBING

Three generations ago Berry Brothers' original Hard Oil was used by expert wood finishers everywhere for all fine interior work.


Those workmen of the old school knew quality and demanded it. As a result, specimens of their work, untouched these many years and in perfect condition still, are now and then to be found in an old mansion of yesterday.

Berry's original Hard Oil is now known as Luxeberry Wood Finish.

Dull Luxeberry enables present-day painters to attain superb deep-toned effects without rubbing. Likewise it permits architects to meet prevailing requirements for dull finishes without increasing labor costs or sacrificing quality.

What can be accomplished with the brush alone when Dull Luxeberry Wood Finish is used will amaze you if you are not already familiar with this remarkable finish.

*Finished panels, samples and complete
information sent on request.*




BERRY BROTHERS INC.
Varnishes Enamels Stains
Walkerville, Ont., Detroit, Mich.

Please mention ARCHITECTURE in writing to manufacturers

Von Duprin

Self-Releasing Fire Exit Latches

Permanence



Von Duprin Self-Releasing Fire Exit Latches are made to become a permanent part of the buildings on which they are placed.

They are designed and built with the precision, extreme care and rigid inspection which make for long life and instantaneous response to pressure on the cross bar.


This care, this determination to build a supremely fine piece of mechanism, regardless of cost, is the very thing which has made **Von Duprins** standard equipment on many of America's finest buildings.

It is also responsible for the fact that no **Von Duprin** anywhere has ever failed to operate in an emergency.

Ask us for Catalog 12-O, or see "Sweet's," pages 1323-1327.

VONNEGUT HARDWARE CO.
Indianapolis, Ind.

*De LaSalle High School,
Nicollet Island, Minneapolis.
Damon, O'Meara & Hills,
Architects, St. Paul.*



Please mention ARCHITECTURE in writing to manufacturers


YOUR GUARANTEE OF GOOD WALLS

You are assured fireproof, permanently satisfactory walls when Pyrobar Partition Tile are used in your building.

Pyrobar are approved for non-bearing partitions by The Underwriters Laboratories. They afford singular resistance to both fire and sound. They are light in weight, durable and cannot stain the interior decorations.

These important advantages—coupled with rapid, economical erection—account for the mounting popularity of Pyrobar Tile among Southern architects and builders. Our engineering department will furnish estimates or other information.

PYROBAR PARTITION TILE




*Granada Apartments, Miami, Fla.
Architects: Hampton & Rievert. 59,554
sq. ft. Pyrobar Partition Tile used*

UNITED STATES GYPSUM COMPANY

World's Largest Producers of Gypsum Products

General Offices:

Dept. F, 205 West Monroe Street, Chicago, Illinois



Please mention ARCHITECTURE in writing to manufacturers

Arco Water Regulator makes every customer satisfied

IDEAL HEATING COMPANY

CONTRACTORS AND ENGINEERS
6312 WENTWORTH AVE.

American Radiator Company,
Chicago, Illinois

CHICAGO. December 12, 1922

Gentlemen:-

We have received a number of very pleasing reports from our customers regarding the performance of their ARCO WATER REGULATORS which we feel you would be interested in.


The general consensus of opinion is that they not only save coal, which is the prime factor, but save labor in the fact that the drafts are automatically controlled.

In the future, it is our intention to figure an ARCO WATER REGULATOR on every hot water heating system whether specifically mentioned or not.

Yours very truly,
IDEAL HEATING COMPANY

By

R. H. Harrison



When you make ARCO Water Regulator part of your specifications, you are going a long way toward insuring comfort for your clients.

AMERICAN RADIATOR COMPANY

IDEAL Boilers and AMERICAN Radiators for every heating need


1807 Elmwood Avenue

Dept. S-61

Buffalo, N. Y.

Please mention ARCHITECTURE in writing to manufacturers

When a house gets a bath —*what happens?*



It all depends on the kind of paint that is on it.

Some paint washes off, little by little, with every rain. If the paint contains zinc, rain merely washes the dirt off.

Paint made with zinc produces a hard, glossy, enamel-like surface. It will not "chalk" and wash off, or blow off. Rain keeps it clean, but the weather cannot penetrate its moisture resisting film.

Architects whose specifications include paint mixed with



The world's standard for zinc products

MAPAZ

can be sure of well protected jobs. Mapaz is our own pure Zinc Oxide ground in refined linseed oil. It is ground according to our formula by Master Painters Supply Co., 160 Front St., New York, Peaslee - Gaulbert Co., Incorporated, Louisville, Ky., Atlanta, Ga., and Dallas, Tex., U. S. Gutta Percha Paint Co., Providence, R. I. Booklet of mixing formulas and full information will be sent free on request by any of the above.


The New Jersey Zinc Company

160 Front Street (Established 1848) New York City

CHICAGO: Mineral Point Zinc Co.

PITTSBURGH: SAN FRANCISCO: CLEVELAND: The New Jersey Zinc Sales Co.

Please mention ARCHITECTURE in writing to manufacturers



Unit of the Frances Fox Laboratories, Ridgewood, N. J.


Retaining the Old Atmosphere in the Remodeled House

In remodeling the old home, it is essential to retain every feature that is quaint and interesting, and to avoid the introduction of any incongruous note such as the bulky iron radiators of steam or hot water heating systems.

The Kelsey Warm Air Generator has been successfully introduced in many cases of this kind, and its inconspicuous registers in the walls or floors are always placed

so as not to interfere with the arrangement of furniture or the unobstructed use of window space.

The automatic humidifier supplies the warm, fresh air with the right amount of moisture, promoting both health and comfort, while the sturdy, scientific construction of the Kelsey Warm Air Generator insures all the heat that is desired with a surprisingly small amount of fuel.



The Automatic Humidifier

Our Engineering Department will prepare estimates and detailed plans that insure satisfactory installation. Send for "Kelsey Achievements"

NEW YORK
565-M Fifth Avenue

THE KELSEY
WARM AIR GENERATOR
(Trade Mark Registered)
304 James St., Syracuse, N. Y.

BOSTON
405-M P. O. Square Bldg.


Trade Mark



Registered

Please mention ARCHITECTURE in writing to manufacturers

AEOLIAN-VOCALION



Aeolian-Vocalion, in a cabinet of the Queen Anne Period, walnut, enriched with comino wood burr. Designed and executed by W. & J. Sloane, New York

True objects of art, executed under authoritative auspices, they offer the charm and advantages of the world's most highly developed phonograph in cabinets designed for carefully appointed homes.

These instruments are of permanent value. They represent the best efforts of the world's most distinguished cabinetmakers and its leading musical instrument manufacturers. As furniture, they reflect a character of art that will be always in good taste. As phonographs, they realize a degree of perfection that makes further improvement extremely improbable.


Portfolio illustrating Aeolian-Vocalions executed by Wm. Baumgarten & Co., Inc., Charles of London, Tiffany Studios, D. S. Hess & Co., H. F. Huber & Co., W. & J. Sloane, Wm. Pierre Stymus, Jr., Inc., and The Aeolian Studios, furnished upon request. Period Aeolian-Vocalions cost from \$150 to \$5000. The least expensive models are handsome instruments of authentic designs and beautiful finish. Moderate monthly payments accepted.

Address, Department B.

THE AEOLIAN COMPANY, Aeolian Hall, New York
LONDON PARIS MADRID SYDNEY MELBOURNE

THE illustrations on this page and in subsequent issues of this magazine are new models of the Aeolian-Vocalion, executed by the world's foremost decorators and by The Aeolian Company's own staff.

The musical quality that has given the Aeolian-Vocalion its position of distinguished leadership here and abroad, is emphasized in these new and superb models.



Jacobean Period Aeolian-Vocalion. A sturdy and characteristic cabinet in walnut with burl redwood, richly shaded



Queen Anne Period Aeolian-Vocalion. This case is of mahogany with panels of walnut and burl redwood. Hand carving



Detail of Residence, Oyster Bay, L.I. Carrère & Hastings, Architects

THE country house offers an unlimited field for artistic brickwork. In the detail above, the treatment of the frieze beneath the eaves almost suggests a delicate mosaic, well within the possibilities of the material and thoroughly accordant with the solid base of brickwork. In "Architectural Details in Brickwork" you will find

many examples of artistic brickwork in which only standard brick are used. The halftone plates, issued in three series, each in an enclosed folder ready for filing, will be sent to any architect requesting them on his office stationery. Address, American Face Brick Association, 1753 Peoples Life Building, Chicago, Illinois.

• STUDIES • IN COLLECTED • NATIVE PLANTS •

NO ONE IN A SERIES

OF TWELVE STUDIES



THE intent of this series of 12 pencil studies is to show varied landscaping uses of such materials as Dogwood, Cedars, Rhododendrons and Mountain Laurel, which are found in abundance in our Collecting Fields.

Each study will be done by a member of one of New York's leading landscape firms.

Allow us to suggest your cutting out and preserving the series.

To make it complete, we will gladly send you a proof of study Number One, to paste over this printing.

Julius Roehrs Co.


At The Sign of The Tree

Rutherford N.J.

**Nurserymen
and
Collectors of native plants**

Copyright 1923—Julius Roehrs Co.

Please mention ARCHITECTURE in writing to manufacturers



Building a Human Monument

The greatest monument to the American Architect, today, are the millions of bright-eyed, alert children who attend our public schools. They are living flesh and blood testimonials to the architect who incorporates the most modern ideas on sanitation, light and ventilation in the school buildings he plans.

UNIVENT
"LIVE OUTDOORS-INDOORS"
(TRADE MARK)

If it isn't manufactured by The Herman Nelson Corporation it isn't the Univent

The Univent is the architect's ideal of perfect ventilation. Direct, vitalizing air from the windows distributed uniformly in each room without draft. We shall be glad to co-operate with architects.

Write for our book, "Univent Ventilation."

THE HERMAN NELSON CORPORATION *Moline, Ill.*
1987 Third Avenue

Branch Sales and Service Stations

BELFAST, ME.	PHILADELPHIA	CLEVELAND	MINNEAPOLIS	KANSAS CITY	PORTLAND
BOSTON	SCRANTON	COLUMBUS	CHICAGO	DENVER	SEATTLE
NEW YORK CITY	PITTSBURGH	DES MOINES	ST. LOUIS	SALT LAKE CITY	SAN FRANCISCO
ROCHESTER	GRAND RAPIDS	MILWAUKEE	EMPORIA	SPOKANE	OMAHA

Please mention ARCHITECTURE in writing to manufacturers



Educational and Research Hospital for the State of Illinois. Edgar Martin, Architect for the State of Illinois; R. E. Schmidt, Garden and Martin, Chicago, Associate Architects; Chas. A. Moses Construction Co., Chicago, General Contractors. BRIXMENT used exclusively for mortar.

BRIXMENT, instead of cement-lime mortar, used after rigid tests

WHEN the masonry work of the Educational and Research Hospital for the State of Illinois was commenced, the contractor encountered considerable difficulty with efflorescence due to low temperature.

With a view to obtaining a mortar satisfactorily adapted to cold weather work, the American Bureau of Inspections and Tests was requested to submit several mortar materials to exhaustive tests.

BRIXMENT was one of the materials tested, with the result that efflorescence was found to be entirely absent when this

mortar was used. The cement-lime mortar was therefore discarded and BRIXMENT chosen for completing the work.

So satisfactory were the results—structurally and architecturally—that the contractor is now using BRIXMENT on the second unit of this group of buildings, claiming that he not only obtained a better mortar but that he is “effecting a saving in the labor required to mix it.”



Send for this descriptive handbook


Experience is the best criterion; specify BRIXMENT and assure better, more economical masonry.

LOUISVILLE CEMENT COMPANY, Incorporated, LOUISVILLE, KY.

BRIXMENT ~ for Perfect Mortar



Please mention ARCHITECTURE in writing to manufacturers



The Annual Toll from Pipe Corrosion

AS a destroyer of property, profits and peace of mind, even fire is scarcely more ruthless than water. The money lost in buildings laid waste by the most spectacular flood would seem small compared with the annual cost of leaking pipes in the countless buildings throughout America.

A flood is a rare calamity—affecting at most only a small number of the population. Pipe corrosion is no respecter of persons, property or seasons—it takes its toll everywhere, continually. Loss of production in industry, and in homes the expensive tearing out and replacing of floors and walls, replastering, redecorating and pipe replacements are but a few results of the tremendously expensive damage it does.

Ordinary pipe forms an easy prey to corrosion. **READING** Genuine Wrought Iron Pipe endures. Ordinary pipe costs less initially; **READING** Pipe is the logical choice for true ultimate economy. Its life is many times longer, *its per year* cost is less than one-third that of the best steel pipe.

Guard against pipe corrosion when you build or remodel. Specify **READING**—the pipe that endures.

*Our interesting booklet—"The Ultimate Cost"—proves why
FIRST cost should be the last consideration in pipe buying.*

IF an annual "corrosion tax" paid by manufacturers and home owners in the United States is ever figured up, the bill will amount to millions.


It is only prudent, next time you build or repair, to consider **Reading Genuine Wrought Iron Pipe**—the pipe which offers two to three times greater resistance to corrosion than does steel pipe. The pipe which costs per year of service one-half to one-third the price of steel.

Our interesting booklet—"The Ultimate Cost"—will be mailed upon request.

READING

GUARANTEED GENUINE

WROUGHT IRON PIPE



"Reading"
on Every
Length"



READING IRON COMPANY
READING, PA.

World's largest manufacturers of Genuine Wrought Iron Pipe

Boston	Baltimore	Chicago
New York	Pittsburgh	Fort Worth
Philadelphia	Cincinnati	Los Angeles

Please mention **ARCHITECTURE** in writing to manufacturers

Capitol Boilers



For the past thirty years, architects and builders have endorsed Capitol Boilers as the acme of efficiency and dependability. Their professional knowledge enabled them to immediately recognize the soundness and reliability of Capitol heating equipment.

Now, to strengthen their recom-

mendations in the minds of the home owners they serve, we have launched a powerful series of advertisements in eleven great magazines.

We believe that telling of the merits, reliability, and the broad guarantee back of Capitol Boilers, in this way to millions of prospects will prove mutually advantageous.

UNITED STATES RADIATOR CORPORATION

General Offices, Detroit, Michigan

Branch and Sales Offices

*Boston
*Springfield, Mass.
*Portland, Me.
New York

*Brooklyn
*Harrison, N. J.
*Philadelphia
*Baltimore

Buffalo
Pittsburgh
*Cleveland

*Columbus
*Cincinnati
*Detroit

*Chicago
*Indianapolis
*Milwaukee

*Minneapolis
*Des Moines
*Omaha
*St. Louis

*Kansas City
*Seattle
*Portland, Ore.
*Louisville

*Warehouse stocks carried at points indicated by star

Please mention ARCHITECTURE in writing to manufacturers



For the monumental building whose design calls for serviceable windows of beauty and distinction, the architect's first choice should be LUPTON Steel Casements. The many reasons are fully explained in a catalogue prepared for the architect. If you do not have a copy, write for one.

An example of the use of these superior casements is shown above in a detail view of the Illinois Merchants Trust Company Bank, Chicago. Architects: Graham, Anderson, Probst & White.

DAVID LUPTON'S SONS COMPANY

Allegheny and Trenton Avenues

Philadelphia

Chicago
New York

Cleveland
Pittsburgh
Dallas

Detroit
Boston

Buffalo
St. Louis
Birmingham



Atlanta
Baltimore

Lupton
Steel Casements

Please mention ARCHITECTURE in writing to manufacturers

The
H. B. SMITH CO.
Boilers & Radiators

¶ You will find SMITH BOILERS and RADIATORS in use because their intrinsic worth has been definitely proved over thousands of aggregate years of service. They are especially built to economize coal and to give maximum results for the coal burned.



Boilers


Mills Water
Tube

Smith
Smokeless Boilers

17 Hy-Test
Menlo
H. B.

Radiators

Princess Direct
Princess Wall



PRINCESS WALL


Write us for detailed information regarding our Boilers and Radiators

The H. B. SMITH CO.

SALES OFFICES & WAREHOUSES

New York · Boston · Philadelphia · Westfield, Mass.
 10 E. 39TH ST. 640 MAIN ST. 17TH & ARCH STS. 57 MAIN ST.
 Cambridge, Mass.

Please mention ARCHITECTURE in writing to manufacturers



A glimpse of one of the Hampton Shops' Interiors, correct in architectural detail.

Hampton Shops

Original paneled rooms and skilled reproductions

TO architects who are producing houses of beauty as well as of importance, we offer among others the following paneled rooms: ¶ The first is an authentic Jacobean carved oak paneled room from "The Lower Hall," Leversedge, Yorkshire. Circ. 1680. 14 x 20 feet. Slight restorations. The overmantel and fireplace have unusual and interesting details. ¶ The second room is a Jacobean carved oak paneled room in reproduction. Copied from room in Wrishay Castle, North Wales, and made from old oaken beams. 19 x 14½ feet. The beautiful carving and

marquetry inlay perfectly reproduce the feeling of the original, which dates from 1620. ¶ There is also a Georgian suite, comprising five complete rooms from "Lord's Grove House" (circ. 1720), Enfield, London: *Room 1.* In green and gold with carved enrichment. *Room 2.* Dark waxed pine, natural finish. *Room 3.* French gray. *Room 4.* Putty color, the mouldings striped in cream. *Room 5.* Green and gold—plain mouldings. Complete details and prices upon request. ¶ The Hampton Shops will gladly put the services of their staff of skilled designers at the disposal of architects.

THE HAMPTON SHOPS SELL FURNITURE, CARPETS, RUGS, AND UPHOLSTERIES. THEY ALSO UNDERTAKE COMPLETE SCHEMES OF INTERIOR DECORATION.

18 East 50th Street . . . New York

Please mention ARCHITECTURE in writing to manufacturers

Anaconda Brass Pipe permanently protects the water supply of the Westinghouse High School, Pittsburgh, Pa. This rustless pipe, which will not clog or discolor the water, was installed at an additional expense of less than 5% of the total plumbing cost.

Anaconda Brass Pipe is permanently identified by the Trademark which is stamped in every length.

THE AMERICAN BRASS COMPANY

GENERAL OFFICES: WATERBURY, CONNECTICUT


New York, Chicago, Boston
Philadelphia, Providence, Detroit
Pittsburgh, Cleveland, Cincinnati
St. Louis, San Francisco



Mills and Factories:
Ansonia, Conn., Torrington, Conn.
Waterbury, Conn., Buffalo, N. Y.
Kenosha, Wisconsin

In Canada: ANACONDA AMERICAN BRASS LIMITED, NEW TORONTO, ONTARIO

Please mention ARCHITECTURE in writing to manufacturers



COLONNADE ROW (LA GRANGE TERRACE), NEW YORK CITY.

Designed and built by Seth Geer, 1836. Measured and drawn by James Cambaro, 1923.

ARCHITECTURE

Published by Charles Scribner's Sons
THE PROFESSIONAL ARCHITECTURAL MONTHLY
VOL. XLVIII OCTOBER, 1923 NO. 4

Colonnade Row (La Grange Terrace)

1836-1923

430-432 Lafayette Street, New York

By James Gambaro

NINETY years ago the city fathers decided to open a street through Vauxhall Gardens, "two miles out of town," which was to be called Lafayette Place (now Street) in honor of the Revolutionary Marquis, "whose recent visit to America had nearly turned the American head." This new street was to be a place of residence for those who desired to leave the thickly settled city and enjoy the pleasure of the country.

Some ten years later (1836), after the opening of Lafayette Place, one Seth Geer, a builder and designer, erected on the west side of Lafayette Street, a few doors south of Astor Place, a row of city dwellings under one roof on the site which now faces the old Astor Library. This row of houses was named "La Grange Terrace," after the country-seat of General Lafayette.

Colonnade Row in its original state consisted of a united terrace of eight houses under a long pointed slate roof (one-quarter of this roof still remains and is in good condition)

with massive stone chimneys rising between each party wall to take flues from abutting houses. While the houses were built on the same general plan, there were varied details in the interior arrangement which reflect the ideas of those whose homes they were. The services were in the basement, and the great kitchens, storerooms, and servants' dining-rooms all bear testimony to the comfort of antebellum days.

The original approach to each entrance consisted of an iron-railed parterre enclosing an area to the basement, while the main entrance doors were approached over a massive slab of stone flanked by stone balustrades. These balustrades terminated with panelled stone pedestals supporting a cast-iron candelabrum.

The door is low in proportion; the entire lower story forming little more than a base to the colonnade proper above. It is appropriately low and heavy, with channel rustication and deep-set windows (17 inches). There were no projecting porticos, as the Doric columns which were on each side of the door were set in, and their entablature did not project beyond the face of the building line.


Upon the base thus proportioned and designed rests



the lofty Corinthian colonnade rising clear to the main cornice. Their dignity and stateliness form a pleasing contrast with the surrounding buildings. The shafts of the columns are built up of five drums, and although some architects claim that the capitals are exact replicas of the Corinthian motive in the choragic monument of Lysicrates in Athens, that is not true, as the accompanying photographs and details will show. The base (with the exception that the plinth is omitted) and the entablature are a copy of the above-mentioned monument. The proportions are the same with exception of the height of the columns, which are 12 diameters as compared with the Lysicrates 10. The spacing of the columns averages about $7\frac{1}{2}$ diameters. The increase in height of the columns reflects the influence of the slender proportions usually adopted for wood architecture of the period. The residential character of the building also calls for a more graceful proportion than would be adopted for a monument.


The cornice is of stone, well bonded into the brick walls of the building, and crowned with antefixes spaced about $10\frac{1}{2}$ inches on centres. The fenestration is simple. The tall windows suggest the high-studded rooms of the principal floor, and their alignment is carried by a continuation of their architrave moulding in the form of a delicate string-course, while each window is embellished above by four wreaths. The second-story windows, to distinguish them from the more important windows below, do not carry the architrave in the form of a string-course, but return above each opening, though the architrave is decorated as below with the wreaths. An iron rail of Greek design formerly ran across the front of the columns; this was removed some time ago, and replaced by a simple wrought-iron rail, placed between the columns.

The ravages of time and the destructive hand of commercialism have had their effects, however. The marble is disintegrating very rapidly, and portions have been covered with a plaster coat of cement, applied without any regard for the original motives. Only four of the original eight houses remain, the others having been removed to make way for a garage and stable. A restaurant occupies one-half of the remaining portion, emphasized by painting that portion of the lower story white and cluttering the front with signs and "modern" candelabra. All of the entrance-door motives have been cut away to make place for various-sized windows and doorways. The windows on the upper floors have also suffered, for the original Colonial sash have been replaced by "French" casements, without regard to scale or design, leaving only the stately columns of rapidly deteriorating limestone to bespeak an early masterpiece of American architecture.











Banking Room, National Manufacturers Bank, Neenah, Wis.

Childs & Smith, Architects.

The National Manufacturers Bank, Neenah, Wis.

WHAT a good opportunity the architects had in the architecture of the two Neenah banks is shown in the illustrations. These banks, on opposite corners, line up like two guards of financial security along "Main Street." Each one reinforces the effect of the other, and both together tend to fix the centre of the town!

The First National Bank, to the right, was completed three years ago. When, two years afterward, the new National Manufacturers Bank building was contemplated, suggestion was made to the new committee that the main horizontal lines of the First National Bank, the base, the cornice, and the parapet, be carried through in the exterior of the new bank, and that the same material, Bedford stone, be adopted. The committee quickly realized the architectural advantage to the town, to the other bank, as well as to their own, and acquiesced.

While on the exterior, for the above good reasons, the two banks have many points in common, they are very dissimilar in the interior.


Interiorly the First National Bank is a "marble bank," simple, dignified, and ivory in tone. The National Manufacturers Bank, on the other hand, is full of color. It has "cathedral" tile floors; walnut-faced cage counters and cage screens; walnut wainscoting around the walls; bronzed

plaster reveals around the circular windows; neutral tinted walls and a warm colored ceiling of old blues, old golds, and magentas—a ceiling reminiscent of warm colored Italian Renaissance ceiling types. The skylight is of amber glass decorated with a moulded leaded grille work of bronze character.

In the interior, the National Manufacturers Bank of Neenah is a rare example of a Middle Western bank, having a truly hospitable atmosphere, colorful, warm, and inviting. This is a bank requirement which recently has more often been demanded in the East or the Far West.




The tile floor in particular is an innovation. The large square patterns, in the manner of the well-known Dutch marble floors, keep intact the ornamental quality of the bank. These patterns are mosaicked with brilliantly colored tiles which awaken interest in the mass but which separately take their places and blend well into the large neutral colors of the field. Tile should be as applicable as marble to bank floors. Perhaps with this example as a leader there will be many more cathedral tile floor banks in the coming years.

Some may call this bank building another experiment in the "new home bank" type. Certainly it is different—it is an endeavor of the architects to avoid the usual "bank mausoleum." Only time will show how well they have succeeded.




NATIONAL MANUFACTURERS BANK AND FIRST NATIONAL BANK, NEENAH, WIS.

Childs & Smith, Architects.



PLANS.
NATIONAL MANUFACTURERS BANK, NEENAH, WIS.

Childs & Smith, Architects.



ENTRANCE DETAIL.

Swedish Architects Working Out a National Style

THE International Town Planning Conference and Exhibition held in connection with the Gothenburg Jubilee Exposition, July 27 to August 12, served to focus attention upon the recent and interesting developments in Swedish architecture. The city of Gothenburg, which celebrated its three hundredth anniversary with the exposition, is one of north Europe's earliest examples of city planning. The city was laid out from the very start by Dutch architects brought in for the purpose by the Swedish hero-king, Gustavus Adolphus. The planning idea has been fairly constant in Gothenburg since that time. The present city architect and engineer, Mr. Albert Lilienberg, is one of the leaders of the movement in Europe, and has represented Sweden in many international conferences.

The characteristics of present day Swedish architecture are a compound of functionalism and of a regard for historical precedent. Swedish architects are striving for new solutions of present-day problems, and they emphasize, also, continuity with the tradition of Swedish building. The country has had a wide range of architectural influences. Romanesque came in with Christianity and is found in the country's earliest ecclesiastical monuments. Byzantine comes in directly, carried by Swedish traders with the East, and it filters through Russia, particularly at times when Russian prisoners of war were engaged in construction work in Sweden, at such a place, for instance, as St. Maria's at Visby. Swedish Gothic exhibits influences from Germany, England, and the Île de France, while Renaissance architecture shows strongly in the Swedish capital, as does also baroque. To the architect of the remarkably fine Swedish royal palace, Tessin the younger, who enjoyed great influence in Sweden, and to Gian Lorenzo Bernini, the country owes a large heritage of post-Renaissance style. It has taken the nobler side of baroque, freedom in handling traditional forms, the creation of new forms of plan and space rather than the elaboration of detail and ornament, attracting with ever varying perspectives and changing silhouettes and diagonals, attained by curves and projections in plan and elevation.

These historical influences, tempered by northern severity and the search for a national style, are seen in the buildings of the Gothenburg Exposition. Here the emphasis is on structure and function, and the architectural interest depends to a large extent on the expression of these elements. However, in such structures as the Memorial Hall, the Hall of Sports, and others, an intelligent and suggestive use of the orders gives a classic effect. This has led many writers on the exposition to call its architecture classical, an observation very far from the truth.

Simple ornamentation, accentuating in every case the structural elements, is characteristic of the whole exposition. The interest depends largely on the play of lines and masses. From every angle of vision the flow and interplay of volumes and spaces is full of interest. There is none of the dull and obvious balance of masses which one finds in so much exposition architecture. From one view the structures build up in a climax of eagerly aspiring verticals, from another there are variations on a horizontal theme in a diversity of tra-beated constructions, from yet another a rich succession of vaults and domes. Slight variations from exact symmetry

here and there give life and movement to the arches, while gardens and lines of trees repeat the forms and colors of the buildings, flower beds repeating wall colors and lines of façades. The irregular contour of the site, which is a hillside, makes the buildings rise in an ascending series of masses, here and there giving the effect of a modern French painting of hillside towns. One of the exposition architects, Mr. Arvid Bjerke, is authority for the statement that modern painting was the inspiration for the original plan of the buildings. If that is so then painting is beginning to pay back to architecture the heavy debt which it incurred through Giotto, who carried over into painting many things which he had learned as an architect, and whose work has had a profound influence on all Occidental painting since his time.

In the building of offices and dwelling houses, particularly country homes, Swedish architects have achieved good things. The houses here shown are by two of Sweden's leading architects, Ivar Tengbom and Carl Westman. The best known work of Tengbom is the beautiful Enskilda Bank in Stockholm, a building of limestone, black granite, and marble, distinguished by solid simplicity, good taste, and expressive character. Tengbom is especially noted for his interesting use of materials.

In Sweden, as in central Europe, the influence of the architect in the applied arts movement has been very great.

Building materials such as wood, especially the wood of coniferous trees, limestone, granite, brick, and cement are plentiful in Sweden, so one finds the greatest latitude in the use of materials. Wood is a favorite and is everywhere used in cheaper houses, particularly workmen's homes, and is handled with good effect in such places as the garden suburb of Landala, near Gothenburg, designed by Gothenburg's city architect, Mr. Albert Lilienberg.

In the homes of the well-to-do brick, cut stone, black granite, concrete, stucco, and sometimes marble, are used. Brick is used with great freedom in design, color, size, and finish, and varying widths of the mortar joints. In the Stockholm Town Hall brick is handled with fine artistic effect.

There is considerable homogeneity in the ideals of Swedish architects, though there are, of course, great individual variations in practice. All are striving for the solutions of the country's architectural problems within the limits set by the necessities and possibilities of the present day, tempered by the solutions which the past has offered. These architects are men of importance in the life of the community, and their names are as well known to the general public as are those of the painters and sculptors. Their advice is sought in all town planning schemes, movements for improving the standards of design and production in industrial art, and in all movements for the betterment of the community and the country in general, where design and plan are necessary. This phase of their activity might be described in the words of the English architect Lethaby, as "architecture as form in civilization." It is a broad and splendid application of the profession and art of architecture to the problems of the national life. But to follow it further in the Swedish state would far outrun our space.



RESIDENCE, STOCKHOLM, SWEDEN (1920).


Ivar Tengbom, Architect.



RESIDENCE, STOCKHOLM, SWEDEN (1920).

Carl Westman, Architect.

The natural rock of the neighborhood is laid in patterns in the garden walk, with grass growing in the joints.



STAIRWAY, RESIDENCE, STOCKHOLM, SWEDEN (1920).

Ivar Tengbom, Architect.

The ironwork is a typical product of modern Swedish work, based on traditional designs of the old Swedish smiths.



BRICK RESIDENCE, STOCKHOLM, SWEDEN (1920).

Ivar Tengbom, Architect.

Wall surfaces and roof suggestive of Vasa architecture, with post-Renaissance influences.



RESIDENCE, STOCKHOLM, SWEDEN (1918).

Ivar Tengbom, Architect.

Finished in stucco. Natural neighborhood rock used in gate posts and foundations.



From the Ruins

*"Oh, East is East, and West is West,
And never the twain shall meet,
Till Earth and Sky stand presently
At God's great Judgment Seat;"*

*But there is neither East nor West,
Nor Breed nor Birth,
When two strong men stand face to face,
Though they come from the ends of the earth!"*

ABOVE everything else our sympathies go out to the Japanese people in this time of trouble, disaster, and suffering. The American people have responded with their usual generosity in times of great need, and the old cities of Japan will rise again from the ruins.

In the rebuilding, the great lesson of the present will be the fact of the value of modern steel and concrete construction. The headlines in a leading newspaper read, "Skyscrapers Withstood the Shocks," and messages received by the London and New York agents of Japanese companies state that Tokio's "skyscraper" district escaped destruction. It is known as Marunouchi and is located between the Central Railway station and the Imperial Palace and consists of great blocks of reinforced concrete buildings, which were at first reported to be a mass of ruins. They withstood the shock, and the extensive station plaza saved them from the flames.

The George A. Fuller Company has received assuring reports from its Japanese representatives.

On other pages of this number appear some extracts from an article written by W. A. Starrett of Starrett Bros., who has but recently returned from Japan and who was in charge of the construction of some of the new modern buildings that have stood the test of earthquake and fire. It is a most timely and instructive contribution, and we feel sure that the readers of ARCHITECTURE will be interested in the statements of such a well known and capable member of the profession.

There will arise a new Japan from the ruins of the old, and American constructive methods and American architects and engineers will be called upon to do their full part. And we venture the prediction that in the rebuilding Japan will develop into a more formidable and modernized business competitor with the rest of the world. We have all wondered what would happen to our own tall steel structures in an earthquake, though we had practical demonstration in the San Francisco disaster.

The walls may fall, the surface that hides the immense steel cages drop, but the essential structures remain intact.

We Need More of Them

OLD ways are good enough until someone comes along and shows us that new ways are not only much better but often much more profitable. We published in the September number some of the new garden apartments that have

been built at Jackson Heights, Queens, Long Island. These have attracted wide attention in many ways, and from a purely business viewpoint they have demonstrated that creature comforts and beauty may go together and lose nothing in the partnership.

Air and light are prime essentials wherever people live, and air and light and space to move about in in the open air, are the things that make this development worthy of high praise and, what is more to the purpose, sought by many looking for a comfortable place to live in.

The Garden Village is a familiar sight in England; some of the great industrial centres over there are celebrated for their charm and perfect sanitary conditions.

All about as well as in our big cities there are spaces that might be used for building garden apartments. The first of this type, built at Jackson Heights, was designed by Andrew J. Thomas in 1919. A space of fifteen feet was left between the buildings.

"Progress in the further development of the garden and the separation of the buildings has characterized succeeding types. The minimum distance between structures in new designs is 36 feet, and only 38 per cent of the area is covered. At the same time important progress has been made in numerous other matters. Sunlight and air have characterized all the apartments, and all have been built of durable materials. But during the last three years the types have evolved from partial fireproof to entirely fireproof buildings, from flat roofs to mansard and Italian, from walk-up to elevator, from an architectural standard which permitted certain awkward combinations of service and court entrance facilities to a standard completely separating the two, from a general appearance which still preserved the severity of the city block to one which brought apartments into a structure as artistic and graceful as a large country house.

"Along with the architectural and hygienic progress represented in such improvements has gone the growth of community advantages. The selling corporation guaranteed from the beginning a perpetual lease on terms, janitor and garden service, heat, etc. It created an organization to sublet apartments and resell when occupants desired to withdraw. But in addition it has proceeded, in conjunction with the tenant-owners, to create certain community advantages."

"Art and the Skyscraper"

THIS is the title of an article by DeWitt C. Pond in the "Field of Art" of the October Scribner's, and we hope that it will be read by many laymen as well as architects. Our architecture is taken for granted by the average man in the street, and only now and then, when some one with a practical knowledge of the subject combined with vision points it out, is he aware that building and beauty may go hand in hand.

Mr. Pond writes with special knowledge and with due reserve; he is not waving the flag or making any unwar-

ranted claims for American architecture. It is a thoughtful, well-considered discussion of things with which we are all concerned.

The following reply to a too common criticism seems to us timely and well put:

"The patronizing attitude of those who claim that buildings in which the use of steel makes possible new forms cannot be good expressions of the art of architecture shows a lack of understanding of what this art really is. A building must be useful, so its plan must be simple and direct. A building must also be beautiful, and so its parts must be well proportioned and designed to form an interesting composition. To accentuate and define the various parts, various ornamental motives are used, and because these motives are inspired by Old World patterns, the critics have been disposed to belittle the achievements of American designers. It is a cheap kind of criticism, for architecture is very much more than the derivation of ornamental motives. It is the same type of criticism that is voiced against the Romans, who planned with masterly skill, but who used Greek models as inspiration for their applied ornament."

A Matter of Business

THE Editor of ARCHITECTURE recently sent out a letter to a number of architects in all parts of the country with a view to finding out from those most concerned just what projects were in hand and what the new year promised.

The general opinion is most encouraging and we have reprinted the material in the form of a report, that we shall gladly send to anyone interested.

That there is an immense amount of building going on is evident on all sides, and that it promises to continue, even in increased measure, seems to be a safe prediction.

This is not mere "optimism" but opinion based on the actual conditions as observed by men of careful and experienced judgment on the job.

The New School of Fine Arts at New York University

BEGINNING this September, the oldest of university departments of fine arts in America begins a new and vigorous life. The first university instruction in fine arts given in America was inaugurated by New York University on its foundation, through the appointment to its faculty, in 1832, of Samuel F. B. Morse, then president of the National Academy of Design. In 1835 he was made professor of the literature of the arts of design, a title he held until his death, when it was allowed to lapse. Now, through the generous support of Colonel Michael Friedsam and the Altman Foundation, the chair has been re-established, and the scope of the department of fine arts has been greatly increased. Through the co-operation of the Art-in-Trades Club of New York City, which has done so much to raise the artistic standard in manufacture and trade, the work offered in the decorative arts will be specially important.

A strong faculty has been assembled under the direction of Fiske Kimball, formerly head of the School of Fine

Arts at the University of Virginia, and author of many books and articles dealing with architecture and the other arts, who will hold the Morse professorship. The study of Italian art will be in charge of Doctor Richard Offner, who now returns after some ten years devoted to research in Italy, during which important articles from time to time have given promise of the monumental "History of Florentine Painting," on which he is engaged. Doctor R. M. Riefstahl, associated with the Anderson Galleries, and well known for his writings on textiles and on Mohammedan art, will lecture on historic textile fabrics, on tapestries, and on Oriental rugs; while Mr. William M. Odom, author of the great "History of Italian Furniture," and director of the New York School of Fine and Applied Art in Paris, will give the fruits of his long study there in a series of lectures on interiors and decoration in France. A course in the design of interiors and furniture will be under the general supervision of Mr. Francis Lenygon, equally well known for his books and for his work as a decorator, both in New York and in London, where his firm acts by appointment to His Majesty.


There will also be a number of special lecturers, headed by Edwin H. Blashfield, president of the National Academy of Design, who will inaugurate a series of Morse lectures. His addresses, which will take the form of reminiscences, extending from a meeting with Morse in Paris, in student days, will be given in the auditorium at Washington Square, on the site of the old university building, where Morse had his studio, in which, despairing of public appreciation of painting, he constructed his first telegraph.

Through an agreement recently ratified, the old relation between New York University and the National Academy of Design has been restored and extended. The two institutions will offer a combined course for art students who wish also to secure a liberal college education. This will involve a college course of four years, of which the first three will be spent in the study of academic subjects in one of the colleges of the university, and the fourth year will be devoted exclusively to the study of drawing and painting at the academy. Students of the university will thus have the advantage of taking this work under such well known masters as Charles W. Hawthorne, Francis C. Jones, Charles C. Curran, and others, under whom they may pursue further study of painting at the academy after graduation.

Among the general lecture courses, which will be opened not only to regular students of the university but to those engaged in professional or commercial work, as well as to collectors and other members of the public, will be, besides those already mentioned, courses in the history of architecture and other phases of painting and the decorative arts. Through the courtesy of the Metropolitan Museum a number of these will be given at the museum, while others will be given at Washington Square, as well as at University Heights. Many of them will be given in the evening, and most of them will be open to women as well as men.

It has seemed a great anomaly that in the city of New York, with all its valuable artistic sources, its public and private collections, and the display constantly in progress throughout the city of paintings, sculpture, and the decorative arts, there should not have been until now a university department of fine arts.





DETAIL, RESIDENCE, WM. S. JENNEY, EAST HAMPTON, LONG ISLAND.

Polhemus & Coffin, Architects.



DETAIL, RESIDENCE, WM. S. JENNEY, EAST HAMPTON, LONG ISLAND.

Polhemus & Coffin, Architects.

OCTOBER, 1923.







ARCHITECTURE

PLATE CXLVII.



RESIDENCE, WM. S. JENNEY, EAST HAMPTON, LONG ISLAND.

Polhemus & Coffin, Architects.




SCALE 0 3 6 9 12 INCHES


SCALE 12 9 6 3 0 1 2 FEET


-EARLY-
-ARCHITECTURE-
-OF-
-MARYLAND-


BARNABY MANOR
IN PRINCE GEORGE COUNTY MARYLAND
BUILT PROBABLY BETWEEN 1680-1710
ACTUAL DATE UNKNOWN

MEASURED AND DRAWN
BY
ALBERT P. ERB










- EARLY -
- ARCHITECTURE -
- OF -
- MARYLAND -

BARNABY MANOR
IN PRINCE GEORGE COUNTY MARYLAND
BUILT PROBABLY BETWEEN 1680-1710
ACTUAL DATE UNKNOWN


MEASURED AND DRAWN
BY
ALBERT P. ERB







RESIDENCE, EMERY THOMPSON, BEECHMONT, NEW ROCHELLE, N. Y.


Frederick G. Frost, Architect.



DETAIL, DOORWAY, RESIDENCE, EMERY THOMPSON, BEECHMONT, NEW ROCHELLE, N. Y.




Frederick G. Frost, Architect.




RESIDENCE, RODNEY W. JONES, BROADVIEW, NEW ROCHELLE, N. Y.


Frederick G. Frost, Architect.



DETAIL, DOORWAY, RESIDENCE, RODNEY W. JONES, BROADVIEW, NEW ROCHELLE, N. Y.



SECOND FLOOR PLAN
SCALE 1/8 INCH = 1 FOOT



FIRST FLOOR PLAN
SCALE 1/8 INCH = 1 FOOT

Frederick G. Frost, Architect.

OCTOBER, 1923,


ARCHITECTURE

PLATE CLVII.





RESIDENCE, JAMES S. ALEXANDER, NEW ROCHELLE, N. Y.

Frederick G. Frost, Architect.



DETAIL, DOORWAY, RESIDENCE, JAMES S. ALEXANDER, NEW ROCHELLE, N. Y.




Frederick G. Frost, Architect.




ACTIVITIES BUILDING, Y. W. C. A., HOUSTON, TEXAS.

Briscoe, Sullivan & Watkin, Architects. Wm. F. Thompson, Associated.





DETAIL.



ENTRANCE-HALL AND STAIRCASE.

ACTIVITIES BUILDING, Y. W. C. A., HOUSTON, TEXAS.
Briscoe, Sullivan & Watkin, Architects, Wm. F. Thompson, Associated.




GYMNASIUM.



SWIMMING-POOL.

Briscoe, Sullivan & Watkin, Architects. Wm. F. Thompson, Associate.
Y. W. C. A. ACTIVITIES BUILDING, HOUSTON, TEXAS.



SOCIAL HALL.

ACTIVITIES BUILDING, Y. W. C. A., HOUSTON, TEXAS.

Briscoe, Sullivan & Watkin, Architects. Wm. F. Thompson, Associate.



Boarding Home, Y. W. C. A., Houston, Tex.

Briscoe & Dixon, Architects. Wm. F. Thompson, Consulting Architect.

HOUSTON (TEXAS) ACTIVITIES BUILDING

The Houston (Texas) buildings' particular problem, aside from the needs of the local Association's programme, was that of climate. It was necessary to carefully consider the prevailing breezes and to so plan the buildings that they would be at all times pleasant and restful.

The prevailing breezes in Houston are southeast and the activities building is designed to afford a cross draught in all of the important rooms on each floor.

The main social room is high, and with the large window at the staircase, as well as the casement doors opening to the loggia, this room is most inviting in the climate of the Southwest.


A roof garden is

provided above the gymnasium, which is one of the practical and attractive features of this building.

HOUSTON (TEXAS) BOARDING RESIDENCE

The central court, facing southeast, is a feature very important in this climate. The court is protected from the cold north winds in winter and has the advantage of the southeast breezes in summer, while it is protected from the hot west sun of the late afternoon.

The balconies at each level on Dallas Avenue serve two purposes: one as an outdoor porch and also as a means of exit in case of emergency. A spiral fire-escape connects these balconies with the court, which makes escape possible but does not permit entrance into the building, thereby making the control of those in charge absolute.





Y. W. C. A. BUILDING, NEW BEDFORD, MASS.

Wm. F. Thompson, Architect.
Edgar B. Hammond, Asso. Architect.

Buildings for the Y. W. C. A.

By William F. Thompson, Architect

THE buildings required for the Y. W. C. A. activities in this country involve a tremendously detailed study of a most intricate plan, which may require provision for all or any of the following interests, in large or small measure, as indicated by local conditions:

<i>Business Administration.</i>	<i>Educational Department.</i>
<i>Reception and Social Rooms.</i>	<i>Employment Department.</i>
<i>Health Department—</i>	<i>Room Registry.</i>
<i>Gymnasium and Dependencies.</i>	<i>Assembly Room and Auditorium.</i>
<i>Pool and Dependencies.</i>	<i>Chapel.</i>
<i>Food Service—</i>	<i>Rest-Room.</i>
<i>Cafeteria.</i>	<i>Bedrooms.</i>
<i>Lunch-Room.</i>	<i>Roof-Garden.</i>
<i>Tea-Room.</i>	<i>Moving Pictures.</i>
<i>Club-Room Service.</i>	<i>Outdoor Recreation</i>
<i>Girls' Work Department.</i>	<i>Ground.</i>
<i>Industrial Department.</i>	
<i>Adequate help's quarters, workshop, storage, etc., etc.</i>	

In order to determine just what should go into the building full consideration must be given by the owners to the nation-wide programme of activities for Associations of that particular type and to modifications required by local conditions. The possible and probable developments or contractions of the future must be previewed and the whole scheme outlined only after a thorough study, not only of programme but of the capacity of the association's pocket-book.

To correct the erroneous idea that all Association buildings are financed from a large national fund, permit me to state that such is not the case. All buildings erected are financed by local subscription exclusively.

Economy in construction and equipment is of prime consequence, since funds raised by public subscription are not inexhaustible, and therefore one must carefully plan to keep within the allowance for building and equipment. Provision, however, should be made for future additions that may be required to complete the building, so that the full programme can be carried on.

Economy in maintenance is imperatively necessary. Every dollar's worth of operating cost must be avoided where such cut is possible.

The diversified character of each floor space indicated by the foregoing programme presents an exceedingly interesting problem; the main points of which are suitability and beauty, plus economy.

The building in each and every part must "work," so to speak, smoothly when packed from basement to roof with many people, of many types of mind; of many nationalities and interests. The well paid business and professional woman, the cash girl, the factory employee, the women of the leisure class must feel at home in their own building. To insure a domestic feeling in the design and general treatment of the exterior and interior is of prime consequence, since the Young Women's Christian Association desires everywhere to avoid institutional characteristics.

The problem of effective supervision and economical management of the building is particularly difficult in the large Y. W. C. A., since the entire building is occupied by a constantly shifting population. How to plan so that each floor is adaptable to various uses—so that the noisy elements are segregated—so that each space is properly related to all other spaces when used in their various capacities, adds something of interest to the study required in this particular problem.

The building must meet the needs of the Association's programme, and since this complex machine is for the use of women and has a decided educational value in the artistic realm, it must not only work, but it should be beautiful in design and exquisite in the simplicity of furnishing and decoration.

The architect should prepare a budget for the client so as to show approximately what the completed building will cost when ready for occupancy and operation. If this were done, it would save the architect many unpleasant interviews and reflect more favorably upon the profession as a whole.

The matter of furnishings is also of importance. Many buildings to be used by all classes are very often furnished to suit the taste of one class.

In any public building such as this, simplicity of design and furnishing is vital, inasmuch as its influence may be lasting in the matter of standards of beauty for large groups of the American public.

There are many well-meaning persons of wealth who donate a sum of money to be used to erect a building for some need or other—the architect is called in and architecturally he designs a very fine building. He is consulted regarding furnishings and makes a selection that is distinctive and suitable to the building; but it is a question oftentimes whether the whole thing has not been wrought out on too grand a scale, which leaves much to be desired in the effect upon those of small income. A monument has been erected to the donor and to the architect which produces perpetual dissatisfaction among those who can never expect to live permanently amid such surroundings.



We must, of course, strive to educate people to understand good design and good quality, but this can be done step by step with better chance for assimilation. On the other hand, when a building is to be used by people who have or can have all that they desire, then the architect and donor have a free hand; but this is not so where the poor and

the rich use a building jointly, as is the case with the Y. W. C. A. buildings.

With these requirements in mind, the architect should solve the problem only on a basis of thorough consistency, giving due regard to the type of persons frequenting the premises and the amount of the appropriation. These two items in turn determine plan, specification, design, furnishing, and equipment. Only in so far as thoroughly balanced consideration is given to each of these factors, can it be said that real design has been achieved. If the relative importance of each and every item necessary to the design and erection of a building, as well as consideration of the people who will use it, were reviewed, the following list, therefore, should be an outline of the architect's thought:

Type of Construction	} as to	Amount Appropriated.
Kind of Materials		Initial Cost.
Quality of Materials		Maintenance.
Kind of Equipment		People of various
Exterior and Interior Design		classes to use build-
Furnishings		ings.

The drawings and photographs reproduced herein show buildings in different parts of the country.





BRIDGEPORT, CONN.

A boarding residence with cafeteria, which is semi-public but principally for the girls living in this building.

The entrance is so arranged that only those living in the building have access to the living-room and other social rooms.

The reception-room, directly opposite the entrance, is a feature, since, on entering, one does not look against a dark blank wall space but instead has a view of outdoors, which is more inviting.

All of the main rooms are designed at a scale used in residential work, and the domestic character is also expressed in the exterior.




BOARDING HOME, Y. W. C. A., TRENTON, N. J.

Wm. F. Thompson, J. Osborn Hunt, Associate Architects.

TRENTON, N. J.

The activities building and boarding residence are on one plot but facing on two streets. It will be possible for girls in the boarding residence to enter the administration building by means of a corridor provided for this purpose.

The large main room of the administration building has three exposures and therefore is well lighted. The two fireplaces will make it attractive and cheerful, and by entering directly into this room one will feel more at home, which is much to be desired.



ADMINISTRATION BUILDING, Y. W. C. A., TRENTON, N. J.



Wm. F. Thompson, J. Osborn Hunt, Associate Architects.

The cafeteria is on the floor below and has a separate entrance from the street, as shown on front elevation, but is also accessible from any part of the building.

The second and third floors contain club and class rooms, gymnasium, etc., and the swimming pool is in the basement. The basement, however, is well out of ground, so that all of the rooms have natural light.

The boarding residence has the usual social rooms and bedrooms. The heating plant for both buildings is in the basement, at the rear of this building.

All supplies for both buildings are delivered through the driveway from Academy Street, as shown on drawings.




Y. W. C. A. BUILDING, ERIE, PA.

Wm. F. Thompson, Architect. Clement S. Kirby, Associate Architect.

ERIE, PA.

The property runs through from street to street. The new building is designed so that upon entering a flood of sunshine greets the visitor through the casement doors, opening upon the paved terrace. Beyond the terrace is a small garden and on one side a covered walkway to the boarding residence and recreation field.

The building will have a roof from which one can view Lake Erie and the far off hills toward the northeast. The interiors are Colonial in design and kept small in scale so as to give the idea of a private home rather than an institution. The second and third floors contain club and class rooms, while the swimming pool is the gymnasium.



WATERLOO, IOWA


One of the features of this building is the separation of the gymnasium and the social room, while the kitchen is placed so that large gatherings can be served in both of these sections.

The social room and the cafeteria can be opened into one large room, and the alcoves at the end of the social room serve also as a stage and dressing rooms.


The second floor contains club and class rooms and the third floor a few rooms for transients.

The cafeteria counter is lighted from skylights above, and the hall also borrows light from the same source through windows, as indicated on the plan.

The exterior is of red brick of various shades, with limestone entrance, band courses, and cornice.



Y. W. C. A. BUILDING, WILMINGTON, DEL.



Wm. F. Thompson, Architect. Brown & Whiteside, Associate Architects.

WILMINGTON, DEL.

The large central court (above the second floor) opens toward the south, so that all of the main rooms will be well ventilated and will benefit thereby from the prevailing breezes of summer.


This building presents a problem in elevation because of its height, and in order to keep the domestic character so essential to association

buildings, the main part was framed with marble quoins and denticulated cornice, and the balance treated in a simple manner so as to subdue the upper floors and the west wing.


The walls are of red brick of various shades with white marble entrance, quoins, and cornices.



GYMNASIUM.



ASSEMBLY-ROOM.





FEDERATION SETTLEMENT, NEW YORK CITY.


W. L. Rouse and L. A. Goldstone, Architects.



CLASS-ROOM.



FEDERATION SETTLEMENT, NEW YORK CITY.



W. L. Rouse and L. A. Goldstone, Architects.

The Quality of Material

By Richard P. Wallis

FOURTH ARTICLE

N. BUILDING STONE

I. *Laboratory Tests*: (a) Stone from other than well-known quarries, intended for use in building construction, should be subjected to chemical analysis to determine its durability and weathering quality. This analysis should be compared with that of some well-known stone of the same kind. If the sample is found to contain a larger percentage of materials subject to the attack of sulphuric acid or carbolic acid, or is soluble in water, the stone should be rejected. The presence of iron pyrites should also cause rejection of the sample.

(b) In subjecting to crushing tests the cubes should be sawed and not chiselled. They should be tested on their natural bed. Three specimens at least should be tested in each case.

II. *Field Tests*: (a) *Absorption*.—The degree of absorption shown by a sample of stone indicates the degree of durability of the sample, since the less moisture the stone absorbs the more durable it is apt to be.

A sample absorbing 10 per cent or more of its weight should be regarded with suspicion until its durability has been established by subjecting it to the weather for a considerable period of time.

In the case of a sample containing a considerable amount of lime or clayey matter, the absorption of 5 per cent by weight is considered to be too great.

To determine this absorbent power the sample should be thoroughly dried in a temperature of about 100° F., and carefully weighed, then soaked in pure water for twenty-four hours. It should then be removed from the water and the surface allowed to dry in the air, and then weighed. The increase in weight indicates the weight of the water absorbed, from which the percentage absorbed may be computed.

(b) *Weathering*.—Soaking a sample for some days in a dilute solution containing 1 per cent of sulphuric and hydrochloric acid will afford some idea as to the resistant power of the stone to ordinary city atmosphere.

(c) *Carbonates*.—A drop or two of acid on the surface of the stone will create an intense effervescence if there is a large proportion present of carbonate of lime or carbonate of magnesia.

(d) *Solubility*.—In order to determine the amount of easily dissolved earthy or mineral matter contained in a sample, the following test may be applied. Pulverize a small sample of the stone and place the fragments in a glass filled about one-third with clear water, and allow it to stand for at least half an hour. Then thoroughly agitate the glass. If the sample is highly crystalline and the particles well cemented together, the water will remain clear and transparent. If the specimen contains uncrystallized earth-powder, the water will present an appearance more or less turbid or milky, depending upon the quantity of loose material contained in the stone.

(e) *Freezing*.—Two or more stone cubes should be dried and weighed and then immersed in water for twenty-four hours. The cubes should then be frozen and thawed a

number of times. After the last thawing the sample should be dried in an oven and the loose particles removed. The cubes should then be weighed and the loss in weight caused by the action of the freezing and thawing process noted.

(f) *Quenching Test*.—The sample should be heated to a temperature of from 500° to 600° F., and, while hot, plunged into water at 70° F.

The loss in weight due to spalling and disintegration should be noted in terms of the weight of the dry stone.

(g) *Soundness*.—A good building-stone should give a clear, ringing tone when struck with a hammer. Granite is tested in this manner for the presence of seams.

III. *Inspection*: (a) *Texture*.—In comparing stones of the same class, the least porous, most dense, and strongest will generally prove to be the most durable in resisting the action of the atmosphere.

(b) *Fracture*.—A fresh fracture, when examined under a magnifying glass, should appear bright, clean, and sharp, with the grains well cemented together. A dull, earthy appearance indicates a stone subject to early deterioration.

O. SLATE

I. *Field Tests*: (a) *Absorption*.—A good slate should absorb but little water. Immerse a sample in water, so that one-half of its height is out of the water. If the water rises in the upper half it indicates that the slate is not of good quality.

II. *Inspection*.—A good slate should give a sharp metallic ring when struck with the knuckles, should not splinter under the slater's axe, should permit of drilling holes for the nails without fracturing, and should be firm at the edges, without tendency to crumble.

If a clayey odor is produced by breathing on the slate, it is an indication that the slate will not weather well.

P. STRUCTURAL STEEL

Structural steel is a manufactured article, and as such should conform to definite specifications concerning its chemical and physical properties.

I. *Laboratory Tests*.—The standards usually adopted in specifying steel are those of the American Society for Testing Materials. See document No. A 9-16 for the detailed requirements.

Briefly summarized the requirements are as follows:

STRUCTURAL STEEL RIVET STEEL		
Phosphorus	Bessemer....	Not over .10%
	Open-hearth.	Not over .06%
Sulphur	Not over .045%	

TENSILE STRENGTH

Tensile strength in pounds per square inch, 55,000–65,000, 46,000–56,000.

Structural steel should bend cold 180 degrees around a pin the diameter of which is equal to the thickness of the

specimen, without fracture on the outside of the bent portion.

Rivet steel should bend cold flat 180 degrees on itself, without fracture on the outside of the bent portion.

II. *Field Tests: (a) Rivets.*—The rivets when in place should be struck with a hammer to determine if they are tightly driven. Those found loose should be marked with a cold chisel, so that the workmen may not obliterate such markings, as is sometimes done when chalk is used for this purpose.

III. *Inspection.*—The supervisor should see that holes for field rivets are punched where required, and that they are clean-cut and do not have ragged edges.

All rust, scale, dirt, etc., must be removed before painting.

Where built-up members have pieces abutting it should be seen that the inaccessible parts are painted before fabrication. Abutting joints should be full and square, and all members should be free from twists, kinks, and bends.

Q. CAST IRON

I. *Field Tests: (a)* A good casting will give a clear sound when struck with a hammer, while an imperfect casting will give only a dull sound.

(b) A casting when struck with a hammer should indent and not break off.

II. *Inspection.*—Structural cast iron should always be examined for concealed faults, such as blow-holes, cold-shuts, and honeycombs. These are sometimes filled with sand and painted to resemble a perfect casting. Any evidence of warping or other initial strain should constitute grounds for rejection.

R. WROUGHT IRON

I. *Field Tests: (a) To Tell Wrought Iron from Soft Steel.*—Clean the sample of all grease and scale and immerse in a solution composed as follows: water 9 parts, sulphuric acid 3 parts, muriatic acid 1 part. The acids should always be poured into the water in preparing this solution. The mixture should then be allowed to cool.

The specimen should be left in the solution for 15 or 20 minutes, and then removed and rinsed in water. The fibre should show plainly; if not, the process should be continued.

Soft steel dissolves uniformly, while wrought iron pre-

sents a distinctly fibrous appearance when subjected to this test.

(b) *Texture.*—A section of wrought rod or plate, when polished, shows more or less laminations of slag and ore.

If the bar is notched on one side and bent away from the notch it will break along the slag laminations. When notched all around and broken, the fracture will be coarsely crystalline, and if broken in tension the fracture will be irregular, non-fibrous.

II. *Inspection.*—Wrought iron should be tough, ductile, fibrous, uniform in character, and should have an elastic limit of not less than 26,000 pounds per square inch. The iron should be thoroughly welded in the rolling, and should be straight, smooth, and free from injurious seams, cracks, blisters, buckles, cinder-pockets, and imperfect edges. The American Society for Testing Materials has published standard specifications for welded wrought-iron pipe, No. A 72-18.

S. PIPE

Occasionally it becomes necessary for the supervisor to determine whether certain pipe is of wrought iron or steel.

I. *Field Test: (a) Manganese Test.*—This test is based upon the well-known fact that the manufacturers of steel-pipe add to the fluid metal in the Bessemer retort or converter a certain amount of ferro-manganese in order to make it possible to roll and weld the over-oxidized metal. There is no such addition in the manufacture of genuine wrought-iron pipe.

In making this test a number of sample chips are placed in test-tubes, and from 10 to 12 drops of nitric acid, diluted with an equal amount of water, are added. The solution is then heated for a few seconds over a candle or alcohol burner.

After the test-tube has cooled off, a small amount of sodium bismuthate is added to the solution. If the sample is steel a decided pink color will show in the tube, whereas if of wrought iron the solution will show a light-brown color, which gradually fades away, leaving a brownish residue in the bottom of the tube.

II. *Inspection.*—Inspection of a fractured surface will often enable the observer to determine the nature of the material. The wrought iron will show a fibrous fracture, whereas the steel will be crystalline in appearance.

(To be continued)

Announcements

Ralph Evans Hacker, A. I. A., announces his withdrawal from the firm of Ernest Sibley, Architect, L. C. Licht, Hacker & Hacker, Associated, and the opening of his office at 1012 Palisade Avenue, Palisades, N. J., for the practice of architecture. He will continue to specialize in schools only.

G. F. Ashley and Albert J. Evers, of Ashley & Evers, architects, 58 Sutter Street, San Francisco, announce the opening of their Los Angeles offices, in charge of Mr. Ashley, 626 South Spring Street, Los Angeles. Would like to receive catalogues.

Alexander C. Eschweiler is pleased to announce that he has associated with himself his sons under the firm name of Eschweiler & Eschweiler, architects, and will be located at 210 Mason Street, Milwaukee.

Arthur T. Remick, architect, announces the removal of his office from 135 East 43d Street to 47 West 43d Street, New York City.


Leonard Anthony Gliatto, architect, announces the opening of his office at 64 East Van Buren Street, Chicago. Catalogues requested.

Raymond T. Gleeson, Thomas F. Mulrooney, and William M. Burke announce the formation of the partnership of Gleeson, Mulrooney & Burke for the practice of architecture, with offices at 404 South Broad Street, Philadelphia. Catalogues requested.


On August 1, 1923, the address of Leonard Willeke was changed from 39 Moss Avenue to 1100 Berkshire Road (Grosse Pointe Park), Detroit, Mich.

Harold Thorp Carswell, of Walker & Carswell, registered architects, announces the opening of an office at Room 1001, Jefferson Building, 1015 Chestnut Street, Philadelphia, for the practice of architecture. Formerly in the office of Cram & Ferguson, architects, Boston, Mass., and for the past eight years in the architectural department of The Cathedral at Bryn Athyn, Penna.


D. D. Merrill, Architect.



CLARK-WILLOW APARTMENTS, BROOKLYN, N. Y.



FLOOR PLAN -
7 AND 4 ROOM APARTMENTS




FLOOR PLAN -
6 AND 5 ROOM APARTMENTS



MAIN ENTRANCE.



VESTIBULE AND HALL.



LIVING-ROOM IN APARTMENT.



DINING-ROOM IN APARTMENT. D. D. Merrill, Architect.

CLARK-WILLOW APARTMENTS, BROOKLYN, N. Y.

Steel and Reinforced Concrete Structures Will Replace the Old Native Methods of Building in Japan

By W. A. Starrett

YOKOHAMA, with its modern docks and rows of dingy European structures, stolid and stodgy, not unlike the water-fronts of London or Amsterdam, its brick hotels, with illusory modernized exteriors, gives a feeling of disappointment to the visitor who on his first venture from shipboard is looking for the picturesque in Japan. The coolies and sam-pans go their accustomed way, but the little toy gardens and thatched cottages are not to be seen, and one must wander into the byways to catch even a glimpse of the remnants of the ancient native construction.

The stranger wanders in disappointment through the narrow streets, lined with these same stodgy European types of fifty years ago—stolid stone, iron-shuttered warehouses, with bolster beams projecting from above loft openings, after the manner of our merchant ancestors who traded from old India House. For it was these who opened Japan and brought with them their ideas of stone and brick warehouses—go-downs, they are called; and following came their counting-houses and office-buildings, which the imitative Japanese quickly copied, and, having copied and learned, repeated and duplicated down to the present day.

One peers behind the maze of pole scaffolding, covered with matting, that everywhere in Japan proclaims a building under construction, and is surprised to find these same old type structures being built—sometimes with a few modern gimcracks, the offering of enterprising American commercial agents—but essentially of the same types that were introduced into Japan nearly a century ago.

There are of course exceptions; particularly are they to be found in Tokio, and even in Kobe and Osaka. Even these, however, have a distinctly foreign aspect to American eyes, so used to the last word in convenience and economy of design. To us the banal German influence—"Dutch" (there is no other word that will express it)—leaves the American troubled and wondering as to how these obsolete structures ever found their way into Japan. English commercial architecture lent its disservice to the Japanese with its ponderous thick exterior walls, making windows shadowed at the back of deep reveals; with cumbersome interior cross walls, and all in a country of soft and soggy bottoms, where lightness of construction and scientific engineering design should have been the first consideration.

Japan sent her architects of the last generation to France, Germany, and England, as we did; but how differently they applied the knowledge which they acquired! Perhaps one explanation is that the Japanese did not have the opportunity on their return to collaborate with structural engineers, as our architects did, to gain and apply that structural skill which was then fast being whipped into a science—a science which might literally be said to have been developed almost in a decade by contemporary American constructors, leading the world in the art of building.

Japan builded truly and well out of that old school, and amazing indeed is the skill with which ideas brought from halfway around the world were applied by the intrepid and fortunate few who were privileged to study abroad, returning, as they did, as missionaries to persuade a nation to lay down the structural usages of a thousand years and take up with something absolutely revolutionary. And however

obsolete may seem many of the structures that one sees going up in almost any Japanese city, it must not be forgotten that these types have been, up to now, adequate to the Japanese requirements.

A tremendous metamorphosis, going to the very heart of the commercial and social life of Japan, was produced by the introduction of the European structure. The wrench necessary to accommodate the people to these novelties must have been very great. It is not to be expected that they will immediately turn again to still another form; for, from the point of view of general convenience, equipment, and arrangement, the modern American type of structure is as far ahead of the adopted European type in Japan as those old European forms are ahead of the ancient pagodas and kuras of the days of the shoguns.

While Japan largely missed our era of skeleton steel structures, concrete, when it came, fairly took the country by storm. Concrete and *nouveau* art flourished like weeds, while the conservative steel skeleton, overlaid with the adaptation of the classical designs which we in America have come to regard as our most beautiful and dignified work, was largely passed over by the Japanese. It might be said that only in the past few years did the more progressive of the Japanese appreciate that perhaps they had missed something in undertaking the rebuilding of their cities and industries—the task that fate has set for Japan.

It is easy to stand in a Japanese city and visualize a Woolworth Building or a Boston Public Library on almost any corner. It is a very different matter to construct out there a modern structure, to marshal the leadership and instruct the native labor, to organize where no organization exists, to translate drawings from shaku and metres to feet and inches, and accurate notations from Japanese to English. These are only a few of the problems.

Tokio, like most cities of Japan, stands on an alluvial plain—a river delta formed by the erosion from the mountains which everywhere abound in Japan; a soft, muddy bottom, with an evil reputation for allowing buildings to settle, and with Mother Nature pitching in frequent earthquakes of greater or less severity. But under that silty alluvial deposit there is excellent sand, and under the sand hard-pan, a splendid foundation soil, an American engineer would say; and, with the water-level only a few feet below the surface, a splendid place for a pile foundation.

When, a few years ago, American constructors were asked to undertake the building of some really modern structures in Japan, these questions and many others had to be met. Also the Japanese, with that progressive spirit which keeps them in our constant admiration, had made careful study of these questions, and had sent intelligent observers to America and elsewhere to collect data and ideas for these new buildings. Earthquakes and soggy bottoms had made the Japanese people cautious. The American pneumatic caisson had attracted their attention, but the large amount of plant and equipment necessary was a great obstacle, there being nothing of the sort in Japan. Borings showed the hard-pan to be fifty or sixty feet below the surface in Tokio, and with an admirable ingenuity the Japanese engineers devised an open caisson to be penetrated down to hard-pan. One of the features of the scheme was the use of a diving outfit, to

be worn by the workman who would dig at the bottom of the caisson. Unfortunately, when the caisson "dropped," the workman in his diving suit was apt to be catapulted up and out of the caisson, paraphernalia and all. A workman was found who could actually stand this ordeal, but the hazard was very great, however commendable his willingness; and since the operation in hand would require some hundreds of caissons, it was deemed advisable to adopt some speedier and surer method than one depending on the genial willingness of this aquatic virtuoso.

Sturdy Oregon piles were imported, long enough to reach the excellent hard-pan; the unaccustomed sound of great American steam pile-drivers rent the calm of old Tokio for two or three months, and the bogie of Tokio's soggy bottom was forever laid. How simple and how obvious, but under the circumstances a revolution, in view of the fact that many of the quasi-modern structures of other years lean and careen from settlement, caused by those earlier Japanese builders' trying to conquer the instability of the soil from above, instead of going through it to the solid foundation that nature had provided.

And yet the interest in these first American construction ventures does not lie so much in the innovations that they have introduced as in the contrasts, the transitions, that are everywhere observed, and the adaptation of that which is found best and most natural in the Japanese themselves. For make no mistake—the Japanese is a versatile and adaptable workman.

Japan will probably never build high buildings. The leading cities have wisely joined in uniform building codes, and all of them limit the height to one hundred shaku (feet)—about eight stories. No doubt many considerations of congestion, traffic, and policy dictated the wisdom of this limitation, but the earthquake problem was the determining factor. The Japanese in recent years have made a profound study of earthquakes; perhaps the most advanced scientists in the world on that particular problem are to be found in Japan, for with them it is an ever-present menace, and through the centuries the Japanese have had reason to fear this dread thing. But the truth is that only in recent years have they done anything really scientific in meeting the problem in their structures. Sentimental tourists, always alert for evidences of great subtlety in the Japanese, point out how adroitly the native house is constructed to meet the earthquake. The roofs are heavy and solid, generally covered with weighty tile. This is all very well as a protection against the weather and as a fire preventive in cities; but as an engineering expedient against earthquakes, it is a myth. When the tremor comes, the spindly corner posts of the structures rock and gyrate, setting in motion the heavy roof, which, if it does not careen from its flimsy moorings, commences to shed its tiles into the streets, and like spilled dishes they clatter

down, often causing casualties that would never have happened had the roofs been of lighter construction and properly engaged to the side walls and foundations. Inquiry develops the fact that a large number of the casualties in earthquakes in Japan come from falling roofs and tiles.

Modern structures of almost any type, built throughout Japan, prove that the native construction had been its own worst enemy and that the earthquake disturbances, however undesirable, have been largely aided and abetted by the native construction methods, from which relief has been obtained by the adoption of things Occidental in building. This is not to say that the earthquakes are not a menace, nor that modern construction solves the problem, for in fact there is no solution. No matter how severe an earthquake they may prepare for, an even more severe one will surely upset calculations; and there is no controlling of earthquakes or determining what may be the most severe possible. But for a given problem, the light skeleton structure so familiar to Americans is undoubtedly far superior to anything heretofore attempted in Japan. Every element that an earthquake of moderate severity has been known to produce can be met through the standard formulæ of strains and wind-bracing, now the common knowledge of the American engineer. The menace of earthquakes of great severity will probably always hang over the heads of the Japanese people like the sword of Damocles; but in our skeleton steel and modern reinforced concrete, America has contributed to Japan a large measure of relief from this scourge. Perhaps the Japanese in their untiring ingenuity will develop it to even greater perfection.

It is the laudable ambition of the Japanese to acquire, as early as possible, full knowledge of the best in American construction methods, so that they may carry on their new-found industry without outside assistance. Eventually they will attain this, but how soon is a matter of speculation. Few people realize the interdependence of American constructors, architects, and engineers, and how mutually helpful are the vast building enterprises constantly going on in our country—how keen the competition for new ideas and conveniences among those who furnish the accessories. Separated from this current of progress, obsolescence is apt to set in, for it is only by sustained vigilance that American constructors keep abreast of the progress in their art. Japan, far removed and not attuned to the changing scene, may find herself, after the lapse of a few years, again in the rear-guard of construction progress. Construction and methods are ephemeral, and if we may claim leadership in construction in America, close contact with American progress must be maintained.

From "New Construction in an Ancient Empire," by W. A. Starrett, in the September number of "Scribner's Magazine."

Travelling Scholarship of the Alabama Marble Company

A JURY of Award, consisting of Mr. R. Clipston Sturgis, of Boston, Mr. Abram Garfield, of Cleveland, Mr. Donn Barber and Mr. John V. Van Pelt, of New York, have awarded a travelling scholarship of \$1,800, established by the Alabama Marble Company, for the purpose of studying the use of interior marbles in Europe, to the winner of the competition for a small bank building, Mr. Frank Martinelli, of New York City.

The winner of the second place was Philip Sanfilippo. The competition was conducted under the guidance of

the Educational Committee of the American Institute of Architects.

Prize Winners in the Advertising Contest

The winners of the prizes for the best and most constructive criticisms of advertising in the September number of ARCHITECTURE are as follows: First prize, \$50, to M. C. Finley, St. Louis, Mo.; second prize, \$25, to Harold R. Sleeper, New York; third prize, \$15 worth of architectural books published by Charles Scribner's Sons to H. Vernon Lee, Boonton, N. J.; fourth prize, \$10 worth of architectural books, to R. C. Spencer, Chicago, Ill.

The Construction of the Apartment-House

By *H. Vandervoort Walsh*

Instructor of Construction, School of Architecture, Columbia University

ARTICLE IX

NOTES ON PLANNING AND WORKING DRAWINGS OF NON-FIREPROOF APARTMENTS


WE cannot separate construction from design, and so we must intrude now and then upon this topic. One cannot prepare the plans for an apartment-house unless he knows how it is to be constructed. The general project type of plan drawing will not do, for economy of space is such a factor that the width and size of every partition on the plan is important. The problem is usually presented in about the following way:

A plot of ground, say 50 by 100 feet, is the basis on which to work, and a limited sum of money is to be invested which must show a large income from the property. Into an area, limited by law to 70 per cent of the lot area, the designer must crowd living-rooms, dining-rooms, bedrooms, toilets, kitchens, and closets. They must not be too big, or they will not return enough money to the owner, and they cannot be too small, or they will violate either the laws of decency or those of the Tenement House Department. Laws governing the sizes of back yards, interior courts, exterior courts, offsets, heights of ceilings, sizes of windows, sanitary arrangements, methods of construction, fire precautions, and a thousand little details must be known and observed. To patiently solve the plan of an apartment with all the fixed conditions that are imposed by law requires something of the spirit of the Chinaman who carves, slowly, from boxwood a curious puzzle.

Now such a confusion of petty details has made many a designer of apartments forgetful of certain general principles of good domestic planning, and, as a result, we find an unusual number of badly planned middle-class walk-up apartments. It is this type of apartment that dominates in numbers, and it is usually planned by some young architect or by one sadly underpaid for his labors. The speculator builder does not often pay for wisely studied plans, being rather narrow in his knowledge of good planning. Gradually, however, conditions are being changed, and more expert designers are being permitted to enter the field.

But we would like to call attention to a curious error of planning that is found so often in this type of apartment, which seems to be the result of a loss of perspective by the designer as he plods his way through the maze of small details and restrictions. This same designer would never, in planning a detached house, mix up the triple division of rooms inherent in any house, namely the living quarters, the sleeping quarters, and the service quarters. He would never think of having his entrance-hall pass by the kitchen door or by the bedroom doors before leading into the living-room. The service quarters would be carefully separated from the living-room and the dining-room, and the bedrooms would be on the second floor, or in a bungalow set apart by a small private hall, and yet many apartment plans show an entire disregard of this simple principle of separating the three parts of any group of rooms for home life.

The plan shown in Fig. 1 is a fine illustration of this neglect of simple principles. One of the apartments in this plan requires the guest, entering it, to pass down a narrow private hall past toilets, bedrooms, kitchen, and actually through the dining-room before entering the living-room.



~EXAMPLE OF A VERY BAD PLAN~FIG. 1

Another apartment shows a long private hall shaped like an inverted T with the living-room at one end of the cross-bar and the dining-room at the other, but a toilet at the intersection. As one enters this apartment the first view is that of the bathroom. Now this plan conforms to the minor details of the law, but violates the rules of common sense. To a greater or less extent this plans shows the faults of the great majority of these apartments.

Generally speaking, the fundamental cause of such poor planning is due to an old fallacy of attempting to serve too many apartments on the same floor with one means of vertical circulation. Instead of having two or three public stairs, one was built, for this seemed to save money. But when one stair hall serves more than four apartments per floor, a great deal of rentable space is lost in long, narrow, and ugly private halls that are necessary to give communi-

cation with the public hall. Fortunately this old mistake is recognized to-day by the best designers, and more public stairs are put in the plans than formerly. This, too, simplifies the location of fire-escapes and permits of the divi-




FIGURE 2.

sion of the plan into fireproof segments separated by 8-inch fire walls.

Now in preparing the plans of any apartment, it is quite necessary to have a working knowledge of details, both of law, custom, and construction, but general principles cannot be neglected, and, after all, most of the laws are the result of an attempt to enforce certain general principles. These laws can be classified into three main divisions: those having to do with light and ventilation, those governing structural conditions, and those dealing with sanitary equipment, such as plumbing systems and fixtures. Many designers feel that these laws, which are applied to tenements, are too restrictive and complicated, and require too much attention to master. Now there is no better way of keeping within the law than to understand the motives that prompted it. To slavishly follow the details the designer will find himself cramped; but to know the principles which created the law gives freedom.




FIGURE 3.

In previous articles we have explained those principles of the laws which govern construction and fire precautions of non-fireproof apartments. It would be well to sum them up into a brief form, and so we have prepared the following outline:

Principles Underlying the Construction of Non-Fireproof Apartments

1. *They should be slow-burning.*
 - (a) Exterior walls are built of masonry.
 - (b) Floor over the cellar is made fireproof.
 - (c) Wooden floor joists are made thick—3 inches—to burn slower.
 - (d) Fire-stops are added at each floor level in interior partitions and around the ends of floor joists in exterior walls.
 - (e) Fire walls extending from basement to above the roof are used to divide building into small units.
 - (f) All vertical shafts, as stair wells and dumbwaiters, are made fireproof, and do not connect with the cellar or various floors except through fire-resisting doors.
 - (g) Wood is kept at least two inches away from chimneys.
2. *A fire should not cause unnecessary collapse of building.*
 - (a) All joists should have fire-cuts at their bearing ends




FIGURE 4.

to permit of quick release without overturning walls.

- (b) Walls should be of ample thickness not to overturn under the expansion from the heat of a fire.
 - (c) Height should be limited, preferably three stories, but usually five.
 - (d) Interior bearing partitions of wood are prohibited, and the interior ends of floor joists must be supported upon brick bearing walls or steel girders and columns.
 - (e) Plain glass is placed in skylights over stairs and dumbwaiter shafts to allow it to be shattered in a fire, permitting the escape of smoke, but protecting wire is placed above and below.
 - (f) Wire-glass is placed in windows of stair halls.
3. *Safe exits for tenants should be arranged.*
 - (a) Every apartment should have at least two means of escape, the main stairway and some secondary stairway.
 - (b) Main stairway should be fireproof and be confined within a fireproof well, starting from first floor and extending up and through the roof, and all halls connecting with it should be fireproof, and all doors into it self-closing, fire-resisting doors.

- (c) The secondary means of escape ought to be a smoke-proof tower or outside exit stairway instead of the usual fire-escape, or the so-called fire-tower.

Light and Ventilation Laws

If we examine the laws that have to do with the light and ventilation of tenements, we will notice that common sense in planning will not be out of accord with them. Every one knows that some restrictions upon the heights to which apartments can be carried must be made in order to save light and sunshine in the streets and courts. Besides a limit must be placed upon the height of non-fireproof tenements for safety against fire. The maximum height is generally restricted to one and a half times the width of the street, and not more than five stories for non-fireproof dwellings.

Another very simple arrangement is insisted upon by the law, and that is to keep an open channel for light and air down through the middle of the block. Restrictions on the depth of back yards keep this space open. The accumulated areas of all the back yards ought to make a reasonable open space. The law in this respect places a minimum on the size of this rear yard. A development, including a whole block, could wisely use more open area in sections of the city that are not too densely populated.

In addition to maintaining an open yard at the rear, it is reasonable to expect that this should be made wider as the buildings are built higher, and so the law places a minimum on the width of back yards according to the height.

And, too, when laws govern the width of courts, a minimum is established, and then the width must be increased over this as the height of the building increases. Offsets in these courts must be limited in depth, or else they will become narrow courts themselves.

With these general principles in mind it is not hard to prepare plans that check up with the technical details of the law.

Next to laws governing courts and their widths, yards and area of ground to be covered, come laws which govern the minimum sizes of rooms and window area. The window area must at least be one-tenth the floor area of the room, and placed high enough (7 feet 6 inches above the floor) to insure good ventilation. Transoms over the tops of interior doors are also needed in certain cases to give cross circulation of air. The law specifies the minimum size of rooms and height of ceilings; but a good planner would make the rooms larger than the minimum. The clear height from floor to ceiling required by law is 9 feet, and this is generally the standard. Sometimes the minimum size of rooms as required by law is made the standard (one room 120 square feet, and all others at least 70 square feet, and no room less than 7 feet in width, except in large high-class apartments servant rooms are permitted to be as narrow as 6 feet).

Proper ventilation of the public halls is also necessary. A window 2½ feet by 5 feet at least should be placed in every such hall, and if too long (over 60 feet) two or more windows are required. The ventilation of public halls is quite important, for the smell of cooking and other odors permeate the air very easily. Stair halls need to have one window at every landing, and a ventilating skylight at the top.

When janitor's apartments are placed in the basement, it is necessary for the health of his family that the windows be placed far enough above the grade, and also the ceiling,

to give these quarters good light and air (4 feet 6 inches above the curb or, when open entirely on court at rear, 2 feet 9 inches above the curb at front of building). The foundation walls and floors ought also to be made water-proof.

In addition to a knowledge of the details of the principles of securing light and air, the designer needs to know certain common dimensions which he will need in the preparations of his working plans. The following table will be found very useful in this respect.

Non-Fireproof Walk-Up Apartments


SIZES OF PARTS FOR QUARTER-SCALE WORKING DRAWINGS

1. Exterior brick walls are shown 12 inches thick, with an additional line on the interior to represent 2 inches of furring and lath and plaster.
2. Interior walls around stair wells are shown 8 inches thick, with no double line for lath and plaster.
3. Interior fire walls and bearing walls are also shown 8 inches thick.
4. Wooden partitions between rooms are shown 2 inches thick, as the rough dimension, although they are actually 4 inches thick when covered with plaster on both sides.
5. Where pipes are carried down in partitions they are shown 4 inches thick, although they are actually 6 inches when plastered.
6. Self-closing fireproof doors from stair hall to apartments are made 2 feet 8 inches by 7 feet.
7. Average door in bedrooms and kitchen is made 2 feet 4 inches to 2 feet 6 inches in width, and 6 feet 10 inches high.
8. Average door into closets is 2 feet by 6 feet 10 inches.
9. The above is also the size of door into toilets.
10. The average size of windows is as follows:

Bedrooms.....	4 feet by 6 feet
Toilets.....	2 feet by 4 feet
Kitchen.....	3 feet 4 inches by 6 feet
Living-rooms and dining-rooms,	3 feet 8 inches to 4 feet by 6 feet

These sizes are the masonry openings; the actual size between stop beads is 5 inches less in breadth and length.

11. Size of toilets is usually 5 feet by 7 feet 4 inches, with bathtub 2 feet 6 inches by 5 feet, and lavatory 2 feet by 2 feet.
12. Kitchens are about 74 square feet, and have in them a gas-stove 2 feet 3 inches by 2 feet 6 inches connected with a vent-flue 8½ inches by 13 inches for the first, second, and third floors, and 8½ inches by 8½ inches for the fourth and fifth. Sinks are indicated on the plans as 1 foot 10 inches by 2 feet, and double tubs 2 feet 4 inches by 2 feet, and refrigerators 1 foot 6 inches by 2 feet. Dressers are shown 14 inches deep, and dumbwaiters 2 feet by 1 foot 10 inches inside dimensions.
13. Dining-rooms are made 12 feet by 12 feet, or about 144 square feet area.
14. Dining-rooms and living-rooms combined, or just living-rooms, are made about 150 to 200 square feet area.




~ PART OF PLAN OF AN APARTMENT HOUSE; SHOWING ~
 ~ INDICATIONS USED ON QUARTER SCALE DRAWINGS ~
 ~ PLANS BY ANDREW J. THOMAS, ARCHT. ~

15. Width of stairs in clear is 3 feet, and total width of hall with double stairway is 7 feet 1 inch.
16. Partitions in back of gas ranges are brick-filled.
17. The average boiler flue is 27 inches in diameter, with 8 inches of brick around it.
18. Service doors in basement are made 3 feet by 7 feet.
19. Service doors into store-rooms 3 feet by 6 feet 10 inches.
20. Basement partitions are shown as 2 inches thick, being made of fireproof blocks.

21. Steam-pipe ducts are made 3 feet by 2 feet 6 inches.

In addition to the above table of sizes we have shown some general sketches of apartment-houses in the process of construction. Attention is called on them to critical parts by special notes.

Besides these drawings we have reproduced parts of the working or quarter-scale drawings of an apartment-house designed by Andrew J. Thomas, architect. These show the methods of indications, dimensioning, and other details of importance.



(To be continued)

new so-called earthquake-proof factories and office buildings which have been constructed within the past three years. There are about six of these buildings in Tokyo. The fact that this construction has proven earthquake-proof is likely to influence favorably the adoption of this type of construction in the future.

Book Reviews

THE GEORGIAN PERIOD. Historical Papers, Photographs and Measured Drawings of Colonial or XVIII Century Architecture in the United States, with Reference to Earlier Provincial and True Colonial Work. Revised Edition. By WILLIAM ROTCH WARE. Six volumes, one text bound cloth and paper, five portfolios, 10 x 14 inches, 272 pages of text with 500 illustrations, 454 full-page plates. New York: U. P. C. Book Company, Inc.

This is in truth a monumental work, a designation that too often is applied to things that are little deserving the name.

But to gather from many sources the best of our Colonial work and to present it with the authority and co-operation of many qualified architects, is to have performed a work for late generations that becomes an invaluable reference, so many of the old houses have gone and are passing every day, in these days of expediency and disregard of the past.

The old edition lacked somewhat in the arrangement of the material, and there was needless diffuseness in the text matter. In the new edition the original matter has been carefully gone over and arranged for ready reference.

It has been rearranged and divided into six parts. Part I contains complete indexes and all text matter. Portfolios II to VI contain 454 plates consisting of detailed and measured drawings and photographic reproductions.

The plates are arranged under the headings of Houses, Churches, and Public Buildings. These in turn are grouped according to location. For example, Part II contains plates of houses in Maine, New Hampshire, and Massachusetts, grouped under these geographical subdivisions. Churches and Public Buildings are also arranged according to location. Thus it is an easy matter, with the help of the complete indexes, to locate any particular subject desired.

It has been the aim of the publishers throughout the revision to follow closely in the footsteps of the distinguished editor of the original work, Mr. William Rotch Ware, and to present a work that will justify its continuance as an invaluable part of the architect's library.

Since its first publication an entirely new group of younger men in the profession have come to the front, and no doubt there are offices all over the country that are without this adequate reference on the most interesting period of our architectural history. To these and to many of the older men this new edition will be most welcome.

The period will ever be a source of inspiration in the designing and building of residences, and we hope that more practitioners will see the light to be found in such a work as this, and carry on traditions that have the approval of long usage and good taste.

ARCHITECTURE TOSCANE. By GRANDJEAN DE MONTIGNY and A. FAMIN. Reprinted with a preface and description of plates by JOHN V. VAN PELT, F. A. I. A., A. D. G. F. The Pencil Point Press, New York.

This valuable work is now made available for members of the profession and for students in a handsome volume.

This is Volume I in the Architectural Document Series and contains the full 110 plates of the original edition, an index in English as well as in French, and an introduction in English in place of the introduction of the French edition. In these plates are represented works of Brunelleschi, Ammanati, Vasari, Giuliano da San Gallo, Antonio da San Gallo, Alberti, Falconieri, Michelozzo, Grosso, Settignano, and many other architects and sculptors.

Among the palaces represented are: Pitti, Riccardi, Strozzi, Gondi, Bartolini, Guadagni, Rucellai, Ugiccioni, Giugni, Gherardesca; among the ecclesiastical buildings are the Church of St. Magdeleine, Church of the St. Esprit, and the Convent of the Augustinians, Chapel of the Pazzi, St. Mary of the Flowers in Florence. There are also several of the more interesting old market buildings and of other structures.

The plates are beautifully drawn and engraved and are reproduced by a photographic process with the utmost care to insure faithfulness to the originals.

CONSTRUCTIVE COVER DESIGNING. A Book of Seventy-six Original Designs Reproduced in Color on Sunburst Cover Paper with Introduction. By FRANK RANDOLPH SOUTHARD. Hampden Glazed Paper and Card Co., Holyoke, Mass.

This handsome book is the result of a cover-design contest in which more than thirty-five hundred artists took part. There was a first prize of a thousand dollars and additional prizes of smaller amounts. From the many designs submitted three hundred were selected and exhibited in various parts of this country and Canada.

It was a happy thought to bind in a volume the seventy-six designs shown, for it puts an interesting and suggestive collection into the hands of many artists and editors and others who will appreciate its reference value.

Many of the designs are out of the ordinary, and some of them both original in conception and notably suitable. Printed on different colored papers selected with a view to effective and harmonious contrast with the printing-inks used, the result in many cases is in good taste and at the same time effective from a purely commercial point of view.

It is surprising to see how effective the background of the paper can be made to serve as an essential part of the decorative scheme. Some of our readers may remember how skilfully the late F. Hopkinson Smith used the surface of a brown or gray paper in some of his charming charcoal drawings.

THE WATERPROOFING HANDBOOK

The sixth edition of "The Waterproofing Handbook," published by the General Fireproofing Company, Youngstown, Ohio, is now ready for distribution to architects, engineers, and contractors who have waterproofing problems to meet.

This is a reference book, 8½ x 11, 72 pages, conveniently arranged for the quick location of the answer to any waterproofing problem.

The book is subdivided into four distinct parts, each section dealing with related problems of waterproofing. Section I, Sub-Structural Waterproofing, deals with the waterproofing of foundations, basements, pits, tanks, pools and containers and other structures subjected to hydrostatic pressure and dampness. Section II, Super-Structural Waterproofing, gives the methods and materials necessary for rendering walls and roofs proof against weathering and dampness, for the stain-proofing of cut stone and for the preservation of stucco, brick and concrete walls. Section III, Cement and Wood Floor Preservation, describes the different methods for hardening, dustproofing cement and wood floors, and for accelerating the setting of cement floors. Section IV, Technical Paints and Coatings, deals with the different ways of rendering walls, floors and containers proof against acids and oils; for the protection of structural steel and galvanized surfaces from rust and timbers from dry rot and decay; for bonding new concrete to old, etc.

Complete specifications are given for all problems and the book is so completely indexed that the location of any problem or specification is a matter of seconds.

The book is for free distribution to architects, engineers, and contractors who are confronted with waterproofing or damp-proofing problems.

ESTIMATING BUILDING COSTS. By CHARLES F. DINGMAN. McGraw-Hill Book Company, Inc., 370 Seventh Avenue, New York.

A practical guide on estimating building-construction costs. Based on fifteen years' experience. Covering all operations from excavating to roofing and waterproofing. Showing how to analyze every construction job into its component parts. Explaining how to apply cost data adjusted to existing conditions to the several necessary operations and how to calculate a price that will approach the actual cost of doing the work as closely as is humanly possible.

Chapter headings: "Introduction," "Excavating, Grading, Bracing," "Brickwork," "Stone Work," "Fireproofing," "Concrete," "Timber Framing," "Boarding, Planking," "Shingling," "Finished Carpenter Work," "Structural Steel and Iron Work," "Lathing, Plastering, and Stucco Work," "Painting and Paper Hanging," "Roofing and Sheet Metal," "Short-Cut Methods," "Summary."

SITE PLANNING IN PRACTICE. An Investigation of the Principles of Housing-Estate Developments. By F. LONGSTRETH THOMPSON, B. Sc. (Eng., Lond.). With a foreword by RAYMOND UNWIN, F. R. I. B. A. Oxford University Press, American Branch.

"Housing Policy and Urban Development," "The Preliminary Survey," "The Choice of Site," "The Development Plan: Preliminary Considerations," "The Development Plan: Classification and Design of Roads," "The Development Plan: The Arrangement of the Roads," "Water Supply and Drainage," "Open Spaces, Gardens, and Allotments," "The Disposition of the Buildings," "Conclusion," "Index." Very fully illustrated, with numerous plans and photographs.

A Correction—Not Indiana Limestone

In the September number it was stated that the exterior of the Passaic National Bank building was of variegated limestone. It seems that it was the original intention to use the variegated Indiana limestone, but the plans were later changed and an artificial stone was used.

Drafting-Room Mathematics

By DeWitt Clinton Pond, M.A.

TWELFTH ARTICLE

CALCULATIONS which involve not only the characteristic considerations of the usual set-back problem but which also require the solving of an unusual algebraic expression were part of a problem which was presented to an architect when he was designing a building in which the upper floors were to be used for dormitory purposes. In




FIGURE 46

the design of a building of this type the upper floors have to be planned first, and the plan which provides the greatest number of rooms, with the smallest number of dark corners at the intersection of corridors, is the one which will influence the plans of all the other floors. In Fig. 46 is shown the outline of the typical floor plan, which is designed in the form of a large letter E. The wings in which the rooms are located are all 34 feet 6 inches wide—which is the average width for most hotel wings.

There were several things to be considered in the design of this plan. Not only must the street wall set back in accordance with the usual requirements of the Building Zone Resolution but the rear yard and courts must increase in depth or width as the building is made higher. It was desirable to have the building which is now under consideration thirteen stories high. All the bedroom stories were made 10 feet from finished floor to finished floor and the first story, second story, and third story were made 13 feet 9 inches, 13 feet, and 12 feet 9 inches high respectively. It was found that the curb level could be taken as 9 inches below the finished first floor. The street on which the building faces is a 60-foot street, the district is a one and one-half times district, a residence and a "B" district. All of these facts must be known before the design of a building in New York can be undertaken.

As the street is a 60-foot street, and as the district is a one and one-half times district, the height limit is 90 feet. It will be seen, in Fig. 47, that the set-back line cuts the building line at the beam level of the ninth floor. Therefore the main wing of the typical bedroom floor plan must be set back if it is desirable to design the building so that it will be 13 stories high. As all the typical stories are 10 feet high there will be an additional fifty feet in height above the ninth floor, as shown in the figure. According to the Resolution, "for each one foot that the building, or a portion of it, sets back from the street line three feet shall be added to the height limit of such building or such portion thereof."

This statement might be made in a somewhat different manner to the effect that for every three feet that it is required to add to the height of the building above the height limit the street wall must be set back one foot. It is desirable to add 50 feet to the height, and so the street wall must be set back one-third of this distance, or 16 feet 8 inches.

So far the calculations are simple enough. It will be seen that the main wing of the building must be set back from the building line in accordance with the calculations given above. However, the architect is allowed to take advantage of the height district exception as stated in paragraph c in section 9. He is allowed to carry up a part of the end wings on the building line to a height which must be determined by the following calculations. The frontage, on the street, of the lower parts of the building




FIGURE 47

extends from lot line to lot line and measures 200 feet. To find the height that each wing can be carried up, this frontage can be divided into halves of 100 feet each and 60 per cent of this dimension is 60 feet. This is the length of the base of the triangle which is drawn in accordance with the explanation given in the last article of this series, to which the reader should refer.

The altitude of the triangle is also 60 feet, a height common to all such triangles, and as the wing measures 34 feet 6 inches in width it will be necessary to find how high such a width can be carried up within the triangle. This is done by proportion.

$$\begin{aligned} 34.5 : 60 &= x : 60 \\ 60 \times 34.5 &= x \times 60 \\ 34.5 &= x \\ 60 - 34.5 &= 25.5 \end{aligned}$$

The height to which the end wings may be carried on the building line is 25 feet 6 inches. As the story heights each measure 10 feet, the wings can be carried up two more stories above the height limit. This is shown in Fig. 48.

In accordance with the architectural design it is thought to be desirable to carry the wings 11 stories high, so it will be necessary to set the wall back, and the following calculations are required to determine for just what distance it will be necessary to do this.

It will be seen by referring to Fig. 47 that the theoretical height to which the wing can be carried is 25 feet 6 inches. The distance between the beam level at the ninth floor and the same level at the twelfth floor is 30 feet, or 4 feet 6 inches more than is allowed. For this height the rule quoted above applies and it is required that this height be divided by 3 in order to find the dimension between the street wall of the eleventh story and the building line. This distance can be found to be 1 foot 6 inches.

So far all the calculations have been found to be very simple. For street frontages measuring 100 feet this is usually the case. However, there is another consideration which adds an interesting question to the calculations.

It will be noticed, by referring to Fig. 46, that there is an octagon indicated by dotted lines at the intersection of the wings. This represents the outline of a penthouse which the architect desires to erect at this intersection. One line of this octagon forms the wall line, which is drawn at an angle of 45 degrees at the intersection. It is desirable that there should be space for one bedroom between the building line and the intersection of the wing and the 45-degree line. It is therefore necessary to know not only the length of the line but its horizontal projection in order to find whether it will be possible to have room for the bedroom, which should be 9 feet wide.

In Fig. 48 the octagon is shown and the known dimensions are indicated. Two sides of the octagon are supposed to be directly over the centre of each wing. Therefore it is possible to see where the dimensions given as 17 feet 3 inches are obtained. The required horizontal—or vertical—projection is noted as x . The length of one side of the octagon is noted as y , and it can be seen that $2x^2$ must equal y^2 . The sum of the squares of two legs of a right triangle equals the square of the hypotenuse.

It is obvious that $17.25 - x = y$ and that $(17.25 - x)^2 = y^2$ and as y^2 equals $2x^2$ it is possible to write the expression given below:

$$(17.25 - x) \times (17.25 - x) = 2x^2$$

In this equation there is only one unknown quantity, and this is x .

As nothing has been said in previous articles with regard to multiplying algebraic expressions it might be advantageous to give the calculations necessary for squaring the expression $(17.25 - x)$ in full. For those who know that $(x - y)^2 = x^2 - 2xy + y^2$ this will not be necessary.

$$\begin{array}{r} 17.25 - x \\ \times 17.25 - x \\ \hline - 17.25x + x^2 \\ 297.562 - 17.25x \\ \hline 297.562 - 34.50x + x^2 \end{array}$$

For those who are not accustomed to multiplying such expressions an explanation might not be out of place. It will be seen that the upper expression was multiplied first by $-x$ of the lower one and then by 17.25. The two results are then added.

The result found in the manner outlined above can be equated with $2x^2$ and the following equation can be written:

$$297.562 - 34.5x + x^2 = 2x^2$$

By transposing all the expressions in which x can be found to the right of this equation the following result is obtained:

$$297.562 = 34.5x + x^2$$

In order to find the value of x it will be necessary to do a little mathematical juggling. It is, of course, possible to add to both sides of the equation equal amounts and in this case it will be necessary to add 297.562 to each side with the result that the following equation can be written:

$$595.124 = 297.562 + 34.5x + x^2$$

The algebraic expression at the right of this equation is a perfect square, as can be determined by multiplying $x + 17.25$ by itself. Because of this it is possible to extract the square root of both quantities at the left and right of the equation. The square root of 595.124 can be obtained in the ordinary arithmetical manner, or by logarithms, as has been explained in previous articles. This method will be given below:

$$\begin{aligned} \log 595.124 &= 2.77461 \\ 2.77461 \div 2 &= 1.38730 \\ 1.38730 &= \log 24.395 \end{aligned}$$

By extracting the square root of the expressions in the equation the following result is obtained:

$$\begin{aligned} 24.395 &= (17.25 + x) \\ x &= 24.395 - 17.25 = 7.145 \\ x &= 7 \text{ feet } 1\frac{3}{4} \text{ inches.} \end{aligned}$$

As has been stated, it is necessary to have 9 feet between the point of intersection of the side of the octagon with the side of the wing and the building line. By adding 7 feet $1\frac{3}{4}$ inches to 9 feet it will be found that the total distance of 16 feet $1\frac{3}{4}$ inches is slightly less than that required by the Zone Resolution and so the requirements of the Building Zone Resolution will govern the set back.

Before going on to explain the other considerations involved in designing a building for a B district, it might be necessary to explain why the number 297.562 was obtained and why it was added to each expression. The process is one used in solving certain quadratic equations




FIGURE 48

and consists of dividing the coefficient of x — (in this case 34.5—) by 2 and of finding the square of this number and adding this to each side of the equation. In this manner a perfect square is obtained for one expression of the equation, and this can be reduced to an expression in which there is simply x and a number. From this x is not difficult to find.

The required set back for the main dormitory wing of the building has been found. The height to which the end wings of the plan can be carried up on the building line and the set back required in case it is desirable to carry up the wing another story have also been determined. All of the calculations, which have been carried out, apply, however, only to the street elevation of the building. The Zoning Resolution also requires set backs for walls on courts, rear and side yards. There are, for example, the following statements in section 12 of Article IV of the Resolution: "In a B district a rear yard at any given height shall be at least two inches in least dimension for each one foot of such height. The depth of a rear yard at its lowest level shall be at least 10 per cent of the depth of the lot, but need not exceed 10 feet at such level. An outer court or a side yard at any given height shall be at least one inch in least dimension for each one foot of height."

Among the definitions in Article I are the following:

"A rear yard is an open unoccupied space on the same lot with a building between the rear line of the building and the rear line of the lot.

"The depth of a rear yard is the mean distance between the rear line of the building and the rear line of the lot.

"A court is an open unoccupied space, other than a rear yard, on the same lot with a building. A court not

extending to the street or to a rear yard is an inner court. A court extending to the street or rear yard is an outer court. A court on the lot line extending through from the street to a rear yard or another street is a side yard.

"The height of a yard or court at any given level shall be measured from the lowest level of such yard or court as actually constructed or from the curb level, if higher, to such level. The highest level of any given wall bounding a court or yard shall be deemed to be the mean height of such wall."

It is well to bear the exact meaning of these definitions in mind, for it will be seen that in measuring heights of walls bounding courts or yards according to the wording of the resolution no allowance is made for a parapet wall and the distance must be measured to the top of the wall itself and not to the top of the beams.

In the plan shown in Fig. 46 is a side yard 10 feet wide. This width is large enough for a height of side wall of 120 feet. As the building under consideration is to be 13 stories high it will be carried to a height of 140 feet to the roof beams over the thirteenth floor. The side wall must be set back above the eleventh story, and as the roof in this case is a sloping roof with no parapet, it will be necessary to set the side wall back 1 foot 8 inches.

The set-back line for the rear yard has a greater pitch than does the set-back line for the side yard. In order to draw it it is necessary to establish a horizontal distance of 10 feet and a vertical distance of 60 feet. A line drawn between two points established on horizontal and vertical ordinates will give the limits within which the rear wall of the building must be built. It will be seen, if such a line is drawn, that the rear wings must be set back above the fifth story.

Professor of Architectural Design at Carnegie

CAMILLE E. GRAPIN, a distinguished architect of France, has been appointed Professor of Architectural Design at Carnegie Institute of Technology for the coming year, according to an announcement from President Thomas S. Baker. Mr. Grapin's appointment is in line with the announced policy of the Pittsburgh institution to secure for its faculty men and women of the highest authority in their respective professions.

In Mr. Grapin Carnegie Tech is securing an artist whose unusual training qualifies him to assist in broadening the work covered in the Department of Architecture. He has repeatedly distinguished himself through his numerous accomplishments as a graduate student in the National School of Beaux Arts in Paris.

He was born in France in 1886, and was graduated from the National School of Beaux Arts in 1914, doing graduate work in the following years. While a student at the school he was awarded the Jean Leclerc Prize, which is given to the student receiving the greatest number of medals and prizes at the school. For the year of 1919-1920 he was given the Equal Second Prize in the Detouches, Delages, and Roux Competition, one of the most important competitions in France.

Among other honors conferred upon Mr. Grapin were the Destors Prize, given to the student having the greatest

number of values in problems, and the Chaplain Prize, which is given to the student winning the most values in design. Both of these awards were made by the Central Society of Architects in France. He has also been awarded a diploma by the French government to practice architecture.

Eliel Saarinen at the University of Michigan

THE College of Architecture of the University of Michigan is pleased to be able to announce that Mr. Eliel Saarinen, of Helsingfors, Finland, will be Visiting Professor in Architectural Design during 1923-24. He will criticize in advanced and graduate designing.

Mr. Saarinen, one of the leading architects of Europe, recently became better known in this country through his remarkable design submitted in the Chicago Tribune Building competition. To students of European architecture he has however long been known as an architect of unusual ability. In the international competition held in 1906 for the Peace Palace at The Hague his design was one of the noteworthy ones and is published in the volume devoted to this competition. It is interesting to note that his more recent work is marked by the same spirit. He has not only designed important buildings in his own country but, like so many European architects, has been active in the field of city planning.



Masonic Club, Newark, N.J.
Architects: C. P. Baldwin and
Henry Baechlin, Newark,
N. J. A striking example of
the perfect adaptability of
Gold-Seal Treadlite Tile.

The Place of the Floor in your Decorative Scheme

SUITABILITY is a fundamental of architectural procedure. In carrying out your plan of interior finishing, obviously it is your desire that the floors will play their part in the decorative scheme.

For, as you know, only in this way is it possible to secure the co-ordination of tones that establishes true architectural expression.

A material which offers you every opportunity to combine *suitability of design* with *utility* is Gold-Seal Treadlite Tile. At your disposal is a great variety of colored tile designs. Or our designers will be glad to suggest special patterns to conform to individual requirements.

Treadlite Tile floors are floors of marked distinction, yet entirely suitable from a practical standpoint. They have been successfully installed in lodge and club rooms, banks, offices, libraries, exclusive retail shops, residences, etc.

Gold-Seal Treadlite Tile floors, like all other resilient floors installed by Bonded Floors Company, are guaranteed against all defects in materials and workmanship by a 5-year Guaranty Bond, issued by the U. S. Fidelity and Guaranty Co.

We shall be glad to send you a copy of booklet, "Gold-Seal Treadlite Tile," showing typical installations and many pattern suggestions, as well as specifications and details.

BONDED FLOORS COMPANY, INC.

Division of Congoleum Company, Inc.

MANUFACTURERS · ENGINEERS · CONTRACTORS

New York · Boston · Philadelphia · Newark · Jamaica · Cleveland · Chicago
Detroit · San Francisco · Los Angeles (Distributors in other principal cities)

"A surety bond with every floor"

Please mention ARCHITECTURE in writing to manufacturers



Insurance Exchange Bldg.,
Des Moines, Iowa
Served by four
K&H "Variable Voltage
Control" Elevators
Boyd & Moore, Architects
George B. Peak, Owner

Applied Like Steam by a Throttle —K&H "Variable Voltage Control"

The selection of K&H Elevators for the Insurance Exchange Building, Des Moines, is another link in the chain of definite recognition of the superior performance of K&H "Variable Voltage Control" Elevators. Architects, having once experienced the smooth riding qualities of K&H "Variable Voltage Control" Elevators, having noted the swifter acceleration, the more positive control, and having checked the savings in power consumption, find it the logical thing to specify K&H "Variable Voltage Control" for the buildings of their clients.

The electric power is applied like steam by a throttle—giving a smoothness of action and a sureness of control hitherto unknown in elevator operation. Write us for a detailed explanation of K&H "Variable Voltage Control."

Kaestner & Hecht Co. • Founded 1863 • Chicago



Ask Your Architect

Kaestner & Hecht Elevators

BIRMINGHAM • CLEVELAND • DALLAS • DETROIT • INDIANAPOLIS • MILWAUKEE
MINNEAPOLIS • OMAHA • PITTSBURGH • ST. LOUIS

Please mention ARCHITECTURE in writing to manufacturers

Colonial Entrance C-101



“Standardized Woodwork Can Be Artistic” —Says Maxfield Parrish, the Painter

“There is no reason why woodwork cannot be produced in excellent taste by machinery,” he told an interviewer recently.

Search out the best, and then reproduce it on a great, standardized scale so everyone may enjoy it. That’s the principle that Maxfield Parrish commends. That’s the basis on which Curtis Standardized Woodwork is manufactured.

The designs are by Trowbridge and Ackerman of New York.

Manufacture on a big scale, guided by the 57 years of Curtis experience, has resulted in woodwork of a quality that will satisfy any architect. From the wide variety of English, Colonial, Western and Southern types you can express any of your own ideas without sacrifice of originality, and at a saving for your client.

Each piece is trade-marked. Details sheets ready to go on your drafting board will be sent free to architects maintaining offices in Curtis sales territory.

The Curtis Companies Service Bureau, 410 Curtis Bldg., Clinton, Iowa

Curtis Companies, Incorporated, Clinton, Iowa
 Curtis Bros. & Co., Clinton, Ia.
 Curtis and Yale Co., Wausau, Wis.
 Curtis Sash & Door Co., Sioux City, Ia.
 Curtis, Towle & Paine Co., Lincoln, Nebr.
 Curtis, Towle & Paine Co., Clinton, Ia.
 Curtis-Yale-Holland Co., Minneapolis, Minn.
 Curtis Door & Sash Co., Chicago, Ill.
 Curtis Detroit Co., Detroit, Mich.

Sales Offices in
 Pittsburgh - New York - Baltimore

1866 CURTIS

The makers of Curtis Woodwork are proud to identify their products by this mark, “1866 Curtis.” You will find it on every piece.

The makers of Curtis Woodwork guarantee complete satisfaction to its users. “We’re not satisfied unless you are.” Every month in the year the Curtis story is told to millions of readers in such magazines as: The Saturday Evening Post, Ladies’ Home Journal, American, House and Garden, House Beautiful, and Country Gentleman; also in Sweet’s Catalog.

STANDARD SPECIFICATION

for

TERRA COTTA

*First Edition**September, 1923*

The Standard Specification for the manufacture, furnishing and setting of Terra Cotta has been completed and is now ready for distribution.

This Specification is the result of exhaustive co-operative study and embodies the highest standard of quality, the best features of modern shop practice and the most thoroughly tested methods of incorporating Terra Cotta in sound masonry construction.

The Standard Specification enables the Architect to specify in detail every factor that makes for entirely satisfactory Terra Cotta.

Copies will be sent on request to Architects, Engineers and Building Contractors.


NATIONAL TERRA COTTA SOCIETY

19 West 44th Street, New York City

TERRA COTTA

*Permanent**Beautiful**Profitable*

Please mention ARCHITECTURE in writing to manufacturers



DOUBLE ECONOMY in use of smaller sizes of BRASS PIPE

So many requests have been received for the table of relative pipe sizes first published eleven months ago by the Copper and Brass Research Association that it is here repeated for the benefit of those who may have neglected to save the table when originally published. Additional copies may be had upon application:

In Hot Water Lines

Use $\frac{1}{2}$ inch Brass instead of 1 inch iron
 Use $\frac{3}{4}$ inch Brass instead of $1\frac{1}{4}$ inch iron
 Use 1 inch Brass instead of $1\frac{1}{2}$ inch iron
 Use $1\frac{1}{4}$ inch Brass instead of 2 inch iron
 Use $1\frac{1}{2}$ inch Brass instead of $2\frac{1}{2}$ inch iron
 Use 2 inch Brass instead of 3 inch iron

In Cold Water Lines

Use $\frac{1}{2}$ inch Brass instead of $\frac{3}{4}$ inch iron
 Use $\frac{3}{4}$ inch Brass instead of 1 inch iron
 Use 1 inch Brass instead of $1\frac{1}{4}$ inch iron
 Use $1\frac{1}{4}$ inch Brass instead of $1\frac{1}{2}$ inch iron
 Use $1\frac{1}{2}$ inch Brass instead of 2 inch iron
 Use 2 inch Brass instead of $2\frac{1}{2}$ inch iron

BRASS CANNOT RUST

From Rules and Regulations for Plumbing, Water Supply, Gas Piping and Ventilation of Buildings, adopted by the Superintendent of Buildings of the City of New York, as amended by the Board of Standards and Appeal:

RISER LINES

Sec. 153—The diameter of all riser lines in plumbing system shall be not less than three-quarters ($\frac{3}{4}$) inch; except that when . . . Brass Pipe is used, the minimum diameter may be one half ($\frac{1}{2}$) inch.

Brass is cheaper because you pay for it only ONCE.

COPPER & BRASS
RESEARCH ASSOCIATION

15 Broadway • New York

Please mention ARCHITECTURE in writing to manufacturers

Appalachian Roseal



Kenneth M. Murchison, New York Architect, designer of the beautiful Jacksonville Terminal, Jacksonville, Florida, selected Appalachian Roseal for the wainscoting of this station. Other Appalachian Marbles were used throughout the building.

Polished samples of Appalachian Roseal will be sent to any Architect interested in its use.


When strong, rich veining is desired; when mottled Persian coloring blends well with the color scheme planned; when an out-of-the-ordinary interior marble treatment or interior marble trim is needed Appalachian Roseal answers the problem perfectly.

Appalachian Roseal is quarried and milled exclusively by this company. Fortunately our supply is practically unlimited for more and more architects throughout the nation are yearly coming to specify it instead of foreign marbles of similar coloring. They have been won to its use because in Appalachian Roseal they secure equal beauty with higher quality, at a considerably lower price.

Catalog, showing complete set of color plates, mailed upon request. Send blue prints and specifications to Appalachian Service Department for cost estimate.

APPALACHIAN MARBLE COMPANY
KNOXVILLE - TENNESSEE

Appalachian Golden Vein



The banking rooms of the Fulton National Bank of Atlanta, Ga., are warm in tone—the atmosphere is one of sincere welcome—yet dignity has at no place been sacrificed. The interior marble throughout this building is Appalachian Golden Vein.

R. S. PRINGLE, of Atlanta, Ga.,
Architect.

We will be very glad to send you a polished sample of Appalachian Golden Vein, if you wish it.

Appalachian Golden Vein is the marble above all others capable of imparting to an interior the effect of mellow richness.


Interiors that would be almost repelling in their coldness if executed in a marble of less warmth become cheery and welcoming when Appalachian Golden Vein is used.

Appalachian Golden Vein is an exclusive Appalachian product. No other marble quarried resembles it. Yet notwithstanding its exclusiveness and its remarkable beauty its cost is considerably lower than marbles of like quality.

It is available in reasonable quantities.

Catalog, showing complete set of color plates, mailed upon request. Send blue prints and specifications to Appalachian Service Department for cost estimate.

APPALACHIAN MARBLE COMPANY
KNOXVILLE TENNESSEE



K O H L E R

And the S.S. Leviathan

Under the Stars and Stripes the great Leviathan sails the seas, the largest and most luxurious ship in the world—

The most luxurious, because her high destiny was a mandate to those charged with her re-conditioning to spare no effort or expense to make her the finest thing afloat.

Sharing America's pride in an

American achievement, Kohler of Kohler takes personal pride in the fact that two hundred Kohler bathtubs and four hundred Kohler lavatories were chosen to equip the Leviathan.

There is added satisfaction in the knowledge that wherever a Kohler fixture is seen, on sea or land, Kohler quality can be recognized by the name "Kohler" in the enamel.

KOHLER of KOHLER

Kohler Co., Founded 1873, Kohler, Wisconsin

Shipping Point, Sheboygan, Wisconsin

B R A N C H E S I N P R I N C I P A L C I T I E S

MANUFACTURERS OF ENAMELED PLUMBING WARE AND KOHLER AUTOMATIC POWER AND LIGHT 110 VOLT D. C.

Please mention ARCHITECTURE in writing to manufacturers

"TILEINE"
PLAIN AND INLAID
COMPOSITION FLOORING


TILEINE UNIVERSAL FLOORING INC.
305-309 West 15th Street
NEW YORK

Georgia Marble is used
in a great number of
America's finest buildings

THE GEORGIA MARBLE CO.
TATE, GEORGIA

MONADNOCK BLDG.
CHICAGO

1328 BROADWAY
NEW YORK




**ERKINS
STUDIOS**

Established 1900

Designs and estimates furnished for
gardens and garden
ornaments.

*Catalogue sent on
request*

242 Lexington Avenue
at 34th St.
New York



**Over
Mantels**

and Mural Paintings
in Cement Fresco
by Olaf Olesen

PAINTINGS
BRONZES
DECORATIONS

John E. D. Trask, Inc.
52 East Fifty-third Street
New York City

Exhibition of Paintings by Raymond P. R. Neilson throughout October

*The UNIVERSITY OF PENNSYLVANIA offers
courses in ARCHITECTURE as follows:*

1. A four-year course, leading to the Degree of Bachelor of Architecture. (Either Architectural Design or Construction may be elected as a major study in the Senior year.)
2. Graduate Courses of one year, permitting specialization in Design, Construction or History; leading to the Degree of Master of Architecture.
3. A special two-year course for qualified Draughtsmen, with options in Design or Construction; leading to a professional certificate.
4. Summer School instruction in architectural subjects.

For circular giving complete information regarding the above courses, requirements for admission, advanced standing, graduate scholarship, year book, etc., and for information upon courses in Fine Arts and Music, address

DEAN OF THE SCHOOL OF FINE ARTS,
Box A, University of Pennsylvania, Philadelphia, Pa.



HIGGINS'

DRAWING INKS
ETERNAL WRITING INK
ENGROSSING INK
TAURINE MUCILAGE
PHOTO MOUNTER
DRAWING BOARD PASTE
OFFICE PASTE
VEGETABLE GLUE

ARE the FINEST and BEST GOODS of THEIR KIND

Emancipate yourself from the use of corrosive and ill-smelling inks and adhesives and adopt the Higgins Inks and Adhesives. They will be a revelation to you

AT DEALERS GENERALLY

CHAS. M. HIGGINS & CO., Mfrs.

Branches: Chicago, London.

271 Ninth St., BROOKLYN, N. Y.



KENT-COSTIKYAN

FOUNDED 1886

485 FIFTH AVENUE—SIXTH FLOOR
NEW YORK


Opposite Public Library

IMPORTERS OF ORIENTAL RUGS
SEAMLESS CARPETS IN SOLID COLORS
RUGS WOVEN TO ORDER IN ORIENT



**AUTOMATIC
HEAT REGULATION**

ELECTRICALLY OPERATED



For the country house, Gold's Damper Control will reduce coal consumption to a minimum and yet give sufficient heat for comfort.

WRITE FOR GENERAL CATALOGUE

GOLD CAR HEATING & LIGHTING CO.

BUSH TERMINAL

220 36th STREET

BROOKLYN, N. Y.



Please mention ARCHITECTURE in writing to manufacturers

Specify McCabe Hangers

MR. ARCHITECT, your reputation, as well as the satisfaction derived from a pleased owner of the building you design, is dependent to a considerable degree on the appointments of that building. Design will attract, then man demands service.

Folding partitions, sliding and accordion doors serve many purposes in the modern building. So do "McCabe Hangers," as there is a "McCabe Hanger" for every sliding and rolling requirement.


The cumulative knowledge of twenty-five years' experience is built into every McCabe Hanger, and the QUALITY is consistent with elaborate construction. "McCabe Hangers" operate smoothly and quietly and give lasting service. We invite comparisons.

Arrange the partitions as you want them, consult our engineering department, let us prove our solution of your folding door problems, but specify "McCabe Hangers."

THE McCABE HANGER MFG. CO.

425 W. 25th Street

New York City



TYPE No. 72

Single hung from center of each alternate door. No track or guide required in floor. For Accordion doors.


TYPE No. 402

Doors hung from edge. With roller floor guide. For doors folding to one side of partition.

TYPE No. 405

Doors hung from edge. To roll on floor track and guided above. Used where headroom is limited.

McCABE
Sliding Door Hangers



High Unclimbable Impregnable

—the Anchor Post Chain Link Fence illustrated provides *real* protection. Ideal for country estates, playgrounds, industrial properties, and many other places.

Fabric is made of No. 9 steel wire. Posts are steel U-sections which keep the fence in constant alignment because they are *drive-anchored*. Every part of the fence is thoroughly *galvanized throughout* by the old-fashioned hot-dip-selter method.

The nearest A. P. office or sales agent will gladly furnish complete information on this or any other type of Anchor Post Fence.

ANCHOR POST IRON WORKS

52 Church St., New York, N. Y.

Baltimore, Md.	Cleveland, Ohio.	Mineola, L. I., N. Y.
Boston, Mass.	Detroit, Mich.	Philadelphia, Pa.
Chicago, Ill.	Hartford, Conn.	Pittsburg, Pa.
Cincinnati, Ohio.	Indianapolis, Ind.	Rochester, N. Y.
	St. Louis, Mo.	


Sales Agents in Other Cities

2500-G

ANCHOR POST Fences

Please mention ARCHITECTURE in writing to manufacturers


A Real Exterior Lighting Fixture Service for Architects



No matter what the style of building you will find a Smyser-Royer fixture to harmonize—over 360 stock designs—and special ones created upon order.

And furthermore—you can guarantee Smyser-Royer fixtures to last as long as the building.

Our Catalogue H is a mine of valuable Exterior Lighting information. Write for it.



SMYSER-ROYER CO.
Main Office and Works, YORK, PA.
Philadelphia Office, 1609 Sansom Street

SMYSER-ROYER EXTERIOR LIGHTING FIXTURES

T-M-B Defies Flood

Again T-M-B Flooring has proved its water and weather-proof qualities.

During one of the most severe storms on record the T-M-B Flooring in the celebrated Roycemore School, Evanston, Ill., was completely covered with water. After the water had passed off the floor was found to be in perfect condition. It had not buckled, rotted, or become loose. It held its color. It had not deteriorated in any way.

During the same storm the wood floor in the Church of Our Lady of Mercy, Chicago, was flooded to the depth of three feet. It buckled and swelled to such an extent that it could not be used. The authorities demanded a flooring which would survive the most rigid test—and have since installed

**T-M-B
FLOORING**

"The Floor That Keeps Its Promise"

Throughout the United States and Canada T-M-B Flooring has proved its 100 per cent quality, not only for foot traffic on all floors, but also in basements and on ground floors where moisture is prevalent, and for roof gardens and other exposed places.

Send for full information, booklet No. 1

THOS. MOULDING BRICK COMPANY

MAIN OFFICES:
133 W. Washington Street
CHICAGO, ILL.

BRANCH OFFICE:
Hartman Building
COLUMBUS, Ohio



**Jacobson Mantel and Ornament
Company**


ARTIFICIAL STONE MANTELS

322 East 44th Street, New York

ALSO COMPOSITION ORNAMENTS
FOR WOODWORK

LOUIS GEIB

ARTHUR P. WINDOLPH



A Quarter Turn of the Wrist Opens or Closes this Valve

A Packing Lock Stem, with Ground Shoulder seating in bonnet, insures a Tight Valve that Stays Tight.

Send for Catalogue showing why

GORTON & LIDGERWOOD COMPANY

96 LIBERTY STREET, NEW YORK, N. Y.

Fisher Building, Chicago, Illinois



A Residence

VENDOR DARK PURPLE-GREY ROOFING SLATE


A dark blend of genuine Vendor Purples and Pennsylvania Greys in carefully proportioned mixture for roofs that must count. Available both in

Heavy Graduated Effects
or Standard Thickness

for high class residential and public buildings or for cottages, industrial housing and speculative building work. An effect for any architecture or at any price in the much desired dark value yet possessing color and architectural interest.

Drawings loaned to us are promptly returned with a delivered price on the Purple-Grey or any other of the Vendor complete line of roofing slates.

Details Here Shown from the Work of
Jacoby & Everett, Architects



A Housing Cottage



• Largest Shippers of Roofing Slate in the World •

• VENDOR SLATE CO. INC. •
• EASTON - PENNSYLVANIA •



When It's Dry One Day and Damp the Next

THAT you'll admit is a test for any wood. But imagine the effect on a poorly made rolling partition. Hundreds of narrow wood slats that must fit and run true in their grooves if the partition is to be usable when wanted.

You have to be sure that a rolling partition is proof against warping, twisting or buckling.

That is just what one half century of specializing and over 30,000 contracts assure you.

That and the fact that you get sound-proof easily movable partitions that turn one room into many, many into one.

We have a catalogue full of suggestive hints on the various uses of rolling partitions.

A copy is yours for the asking.



Wilson

The J. G. WILSON Corporation
19 EAST 36TH STREET, NEW YORK CITY
OFFICES IN ALL PRINCIPAL CITIES



Please mention ARCHITECTURE in writing to manufacturers


COMPOSITION ORNAMENT

DURETTA FIREPROOF
COMPOSITION
ORNAMENTAL PLASTERING

Catalogue of Compo Ornament
will be sent on request to archi-
tects east of the Mississippi River.



G. E. WALTER
157 EAST 44th STREET - NEW YORK



King GREENHOUSES

are supplied in ample range of de-
signs and sizes to harmonize perfectly
with other construction.

We are always glad to give individ-
ual attention to special problems in
design. Write for Booklet 52.

When you think of good greenhouses, think of "KING"

KING CONSTRUCTION COMPANY

GENERAL OFFICES:

NORTH TONAWANDA, N. Y.

NEW YORK CITY 56 West 45th Street Telephone Murray Hill, 10050	PHILADELPHIA, PA. 15th & Market Sts. Telephone Spruce 6521	BOSTON, MASS. Board of Trade Bldg. Telephone Main 4399	SCRANTON, PA. 307 N. Irving Ave. Telephone Scranton, 7-4136
---	---	---	--



**Paint
Pointers**

Nice Liquid Wood Filler

FOR a fine finish on new woodwork everything
depends on the way the surface is prepared. To
bring out the beauty and natural characteristics
of the wood, the ground work is of paramount
importance. Fill the grain of the wood, level the
surface with "Nice" Liquid Filler and your work
is more than half done.

EUGENE E. NICE COMPANY

Manufacturers of
Varnishes, Fillers and Paints

272-274 South Second St.

Philadelphia, Pa.



SWIMMING POOL SANITATION



*The Swimming Pool at Biltmore Forest Club,
where W & T Apparatus is Protecting
the Health of the Bathers*

Don't let your children or anyone else's children bathe
in a Swimming Pool unless the water is sterilized. If
they do they are exposed to disease.

The W & T Process of Chlorination will sterilize the
water in any Swimming Pool—and make the trans-
mission of disease impossible—at a cost of less than
ten cents a day.

*Technical Publication No. 21, containing full
data and specifications will be mailed on request*

WALLACE & TIERNAN

COMPANY INCORPORATED

NEWARK : NEW JERSEY

NEW YORK CHICAGO PITTSBURG SAN FRANCISCO KANSAS CITY
ST. LOUIS SEATTLE KNOXVILLE DALLAS MINNEAPOLIS

1 WALLACE & TIERNAN, LTD., TORONTO



Walls finished with Cabot's Old Virginia White, roof stained with Cabot's Creosote Stain. Dwight J. Baum, Architect, New York

Bright but not Shiny

No other exterior finish is as brilliant white as

Cabot's Old Virginia White

but it is not a shiny white. It is as soft and cool and as bright as new whitewash, and as durable as paint, but costs much less. Gives new Colonial houses the effect of well-groomed old age. Complete color-harmony is achieved on this house by green blinds and moss-green roof of

Cabot's Creosote Stains

Send for samples and catalog

SAMUEL CABOT, INC. Manufacturing Chemists BOSTON, MASS.

342 Madison Ave., NEW YORK

24 West Kinzie St., CHICAGO

525 Market St., SAN FRANCISCO


331 E. 4th St., LOS ANGELES

Cabot's Insulating and Deadening Quilt, Brick and Stucco Stains, Conservo Wood Preservative, etc.

Ventilighter

SYSTEM

LIGHT, AIR, NO GLARE—METAL FRAMES—CLOTH VANES



All metal Ventilighter installed in Art Gallery of Joseph E. Widener, Philadelphia. Horace Trumbauer, Architect.

ART GALLERIES
MUSEUMS
LIBRARIES

SCIENTIFIC
SHADING
for

PUBLIC BUILDINGS
RESIDENCES
OFFICES

SKYLIGHTS, WINDOWS, SLEEPING-PORCHES

Designed to regulate and control light, eliminating glare and shadows, also reducing heat without loss of ventilation. Are easily controlled by conveniently located cords at side and cannot get out of order. Above cut showing special metal vanes for darkening purposes and showing motion pictures. Note one side open and the other side closed. Operated by electricity.

Simon Ventilighter Co. Inc.

101 Park Avenue

New York City




You may rest assured that the trade mark on WITCHIN DECORATIVE FABRICS, including Ullswater Cretonne, Damasks, Chintzes, Kensington Prints, Tapestry, and Velvets, carries with it the guarantee of real creative ideas in master design.

**WITCOMBE, McGEACHIN
& COMPANY**

22 West 37th St. New York

CLINTON WIRE LATH

Standard since 1856



Adapted to all kinds of plain and ornamental plastering

A GLANCE at the key side of a wall plastered on Clinton Wire Lath will show the perfect manner in which the plaster surrounds the lath. The clinch of the back plaster will so cover every wire that it is difficult to detect a single strand showing in this perfect key.

Complete information upon request

Wickwire Spencer Steel Corporation

41 East Forty-second Street, New York

Worcester

Buffalo


Detroit

Chicago

San Francisco

Please mention ARCHITECTURE in writing to manufacturers

The **WHITE HOUSE** *Line*
SECTIONAL UNIT STEEL DRESSERS



A typical kitchen in Pelbrook Hall and Peldean Hall, Pelham, N. Y., showing WHITE HOUSE Dressers

Steel Dressers in apartment-house kitchens assure perfect sanitation, as well as efficiency. And because of their construction and finish, using WHITE HOUSE Steel Dressers, eliminate the danger from fire and the unpleasantness of vermin.

The WHITE HOUSE Line is manufactured in a Unit System which enables us to fill practically any space by combining units.

We specialize in laying out kitchens and pantries and we furnish blue prints and estimates on definite spaces.

Send us *your* plans for sketch and estimate.

Some Recent Apartment Installations:

CULVER APARTMENT,
136 East 67th Street,
New York City.

Joint Ownership Const. Co.,
Walker & Gillette, Archts.

KEW HALL,
Kew Gardens, L. I.

J. K. Turton Company,
Builders.

PELBROOK HALL,
PELDEAN HALL,
Pelham, N. Y.

Geo. F. Pelham, Archt.
John T. Brook Co.,
Builders.

HUBBELL APARTMENTS,
New Rochelle, N. Y.

Laurence M. Loeb, Architect.


Catalogue and Information on Request

JANES & KIRTLAND

Established 1840

135 West 44th Street

New York, N. Y.



New Tape Hook
Makes
Pullman
Sash Balance

The 100% Window Device
With No Increase in Price

The new Tape Hook makes it possible to fasten or unfasten the tape from the sash while sash is in place. No fussing with the stop; no mars or scratches; no refinishing; no lost time.

Pullman Sash Balances are easy to install and cost less than cords and weights. They are cheaper, not alone in first cost, but also because any carpenter can fit 2 to 4 windows with Pullmans while he would ordinarily fit one with cords and weights.

Pullmans eliminate box frames too. That alone saves you real money and makes a tighter, better construction.

Pullmans are made of pressed steel, are entirely incased and constructed in 3 UNITS, K, L and M, adaptable to any kind of sash. Operate easily and quietly; last indefinitely, in fact are guaranteed for 10 years.



Free illustrated catalog, full of
Modern Window Operating In-
formation, sent on request.

Pullman Mfg. Co.
230 South Avenue
Rochester, N. Y.

"PULLMANIZE YOUR WINDOWS"

An **EVANS VANISHING DOOR** *Product*
for **SCHOOLS**



That Pays for Itself With

FLOOR SPACE SAVED

WARDROBES, Class A

made with panel Backs, Ends and Divisions, and with doors that swing—not slide—on double pivoted arms, no guides, tracks or rollers, no rattle or squeak; they rate 100% in conservation of space, easy and noiseless operation, perfect sanitation and ventilation. Doors cannot stick or bind. Hardware can also be purchased separately.

More than a Million hang their Wraps in Evans Vanishing Door Wardrobes

Trade Mark
VANISHING DOOR
U. S. Reg.

Catalog
"PICTURES THAT TALK"
Sent on Request


W. L. EVANS

700 Block C

WASHINGTON, IND.

Please mention ARCHITECTURE in writing to manufacturers

HESS WHITE STEEL



Medicine Cabinets and Lavatory Mirrors

meet the demand for better-than-wood cabinets and wood-framed mirrors, and at reasonable prices.

The highest grade of materials and workmanship go into these goods—polished plate glass mirrors, nicked brass hardware, steel or glass shelves, and the whole, inside and out, finished in beautiful baked white enamel, guaranteed to be everlasting.

Look for this mark:



and make sure you are getting the genuine Hess. Sold by dealers everywhere. Illustrated booklet on request.

Sweet's Index, page 1470

HESS WARMING & VENTILATING CO.

1224 TACOMA BLDG., CHICAGO

Makers also of HESS WELDED STEEL FURNACES



The photo above shows the living room of a residence at Overbrook, Pa., floored with Ritter Appalachian Parquetry Oak Flooring—block pattern.
—Wm. Woodburn Potter, Architect.

Here is Beauty at a Saving

WHETHER in private residences, hotels, apartment buildings or churches, no matter how pretentious or modest the requirement, there is economy as well as unsurpassed elegance in the use of Ritter Appalachian Oak Flooring.

Ritter Flooring is accurately milled from Appalachian Oak—famed for its superior qualities. Characteristics of this oak are its fine, subdued grain, uniform color, and mild texture. Because of these qualities, as well as of the care exercised in its manufacture, it may be finished far more beautifully than ordinary oak flooring.

And here, too, is where the economy in the use of Ritter Flooring enters. For, because of these same qualities, it may be laid, nailed and finished in less time and with less effort—and as a result, at a great saving in the cost of labor. Quality considered, Ritter Appalachian Oak Flooring costs no more than any other.

As a protective measure, it is stored in steam-heated warerooms at the mills where it is kept in a perfectly dry condition until shipped. Ritter Appalachian Oak Flooring is branded for your protection and there is a grade for every purpose.

Our booklet giving technical information on the laying and finishing of flooring will be mailed to you upon request.

W. M. RITTER LUMBER COMPANY

America's Largest Producer of Hardwoods

GENERAL OFFICES—COLUMBUS, OHIO

Branch Offices—Pittsburgh, Philadelphia, New York, London and Liverpool

RITTER

APPALACHIAN OAK

FLOORING

DIXON'S SILICA GRAPHITE PAINT

ECONOMICAL

because it protects metal or wood surfaces for the longest time.

The pigment flake silica-graphite is inert and immune to attack by gases, acids, alkalies and climatic conditions.

It will not peel, crack or flake off because of the natural elasticity of this pigment. Made in FIRST QUALITY for over 50 years.

Write for Booklet 1-B

JOSEPH DIXON CRUCIBLE COMPANY

JERSEY CITY, N. J.



Please mention ARCHITECTURE in writing to manufacturers

*Why you'll find
Sedgwick outfits
most satisfactory*

No. 2

— Because you can get from us just the Hand Power Elevator or Dumbwaiter you need—*when you need it.*

Thirty years' experience in the design, manufacture and installation of Hand Power Elevators and Dumbwaiters for all purposes has shown us what types of Hand Power Elevators, Dumbwaiters and Gravity Lifts are best for standard conditions and requirements. We have these outfits in stock ready for immediate shipment.

If you require a special type of outfit, not carried in stock—we can make it up for you and ship within five days after receipt of your order.

SEDGWICK MACHINE WORKS

140 West 15th Street
New York, N. Y.


DURASTONE BRAND

LIMESTONE, CAEN STONE
TRAVERTINE INTERIOR
AND EXTERIOR FINISHES

KRIDER BUILDING MATERIAL CO., Inc.

422 East 3d St. New York
Grand St. & Metropolitan Ave. Brooklyn

PROMETHEUS




THE PLATEWARMER THAT CANNOT OVERHEAT

Write for our new circular
describing exclusive Prometheus
improvements.

TOWEL AND CLOTHES DRYERS

THE PROMETHEUS ELECTRIC CORP.
356 WEST 13th STREET NEW YORK




GRAND CENTRAL TERMINAL
NEW YORK CITY

A magnificent panel of Polished
Wire Glass



MISSISSIPPI WIRE GLASS CO.
220 Fifth Avenue
NEW YORK
St. Louis Chicago



Building Finance for the Architect

OUR job is the financing of community buildings, particularly modern hotels.

It has been our privilege during the past decade to finance 97 per cent of the modern community-built hotels of the country, due, largely, to the exceedingly low cost of raising funds the Hockenbury way.


It has been our pleasure to co-operate with the country's leading hotel architects in the financing of some of the foremost hotels.

You owe it to yourself, Mr. Architect, to keep apace with the rapid growth in community building. A few minutes spent with THE FINANCIALIST each month will keep you informed. Our subscription list is open to Architects—gratis!

Your name, please?

The HOCKENBURY SYSTEM, Inc.
• Penn-Harris Trust Bldg •
• HARRISBURG-PENNA •

Please mention ARCHITECTURE in writing to manufacturers



Sanymetal installed in the University of Pennsylvania Stadium, Philadelphia, Pa.

4000 Installations

THE substantial success of Sanymetal Toilet and Office Partitions is attested today by over 4000 installations, in practically every class of building, all over the country. Unexcelled metal craftsmanship, insistence on the best in materials and finish, close attention to details of sanitation—these qualities have set Sanymetal distinctly apart from ordinary metal partitions. And perfect adaptability to every space requirement of toilet rooms and offices has made it standard equipment in many architects' specifications.

Designed for toilets, urinals, showers, dressing-rooms, and toilet wainscot. Standard units adaptable to any layout. Made of Armco Ingot Iron. Water-shedding construction. Doors equipped with Sanymetal Gravity Roller Hinges. Write for new Catalog 5, with detail drawings.

Catalog 4 shows Sanymetal Office and Mill Partitions



THE SANYMETAL PRODUCTS CO.
985 E. 64th Street Cleveland, O.

Sanymetal
TRADE MARK U.S. REG.
Toilet and Office Partitions




Fig. 157

Note the construction of patent Interlocking Device used on Edwards Metal Shingles and Spanish Tile.



Fig. 367

Metal Spanish Tile for main part of roof.

Edwards "Queen Anne" Metal Shingles



Residence Senator Geo. S. Nixon, Reno, Nevada. Edwards Metal Spanish Tile used on this building

EDWARDS Metal Spanish Tile

It is wonderful what a remarkable transformation takes place when an "Edwards" Metal roof is properly applied to a house—all of the charm of the Old Spanish Terra Cotta Roofing Tile is preserved, even to the color.

The house takes on a new lease of life. It seems a better place to live in. It helps put the stamp of progressiveness and thrift on a community. An Edwards Metal or Tile Roof is a real commercial asset and will bring a better return in rent or sale.

Edwards Metal Roofings made in various styles, to have the appearance of wood shingles, tile, slate, or any other roofing effect, and none of these fine artistic effects will cost any more than a plain, commonplace roof.

All Edwards Metal Roofing is easy to lay—no big expense for skilled labor—storms and winds will not wrench it loose or make it a rattle-trap. It is lightning-proof and fire-proof—Reduces Insurance Rates.

When an Edwards Roof is laid, it is there to stay.

Send for our literature—it explains

The Edwards Mfg. Co.

324-374 Eggleston Ave., CINCINNATI, OHIO

The World's Largest Manufacturers of
Metal Roofing, Metal Ceilings, Metal Garages,
Portable Buildings, Rolling Steel Doors, etc.



Stewart's IRON FENCE STANDARD OF THE WORLD



Our distinctive designs harmonize with the lines of the building, whether it is a town house, suburban home, country estate, bungalow or other property.

Book of Designs "B" sent upon request


We also manufacture grilles, balconies, partition railings, folding gates, miscellaneous iron and wire work and chain-link wire fence.

Architects' Designs executed in strict accordance with their specifications

THE STEWART IRON WORKS COMPANY
INCORPORATED
CINCINNATI, OHIO, U.S.A.
"The World's Greatest Iron Fence Builders"

The Water Supply for SWIMMING POOLS

A new edition of Graver Bulletin No. 500 has been issued containing detail drawings of installations, detail drawings of equipment, and complete data on the design and construction of both indoor and outdoor swimming pools.



A copy of this bulletin, together with Architect's Specification Form covering this class of equipment, will be mailed on request.

GRAVER Corporation

(WM. GRAVER TANK WORKS FOUNDED 1857)

Steel Tanks and General Steel Plate Construction
Water Softening and Purifying Equipment

610 TODD AVE., EAST CHICAGO, IND.

HALICOMP



Durable, Sanitary and Distinctive

Halicomp—the floor that withstands the ravages of time and the tread of myriad feet.

Halicomp—the floor that can be used in kitchens, bathrooms, hospital rooms, halls and operating rooms and wherever sanitation is the first consideration.

Halicomp—the floor that is never confused with the ordinary magnesite floor—that has a distinction of appearance all its own.

Hallicomp is installed only by men in the Hachmeister-Lind organization who are experts. Let us give you specifications and quotation, or see Sweets Catalogue for details.



HACHMEISTER-LIND
PITTSBURGH

CHEMICAL COMPANY
PENNSYLVANIA

14 Reasons for your Specification of "The BEST Glass"

THE answer of the architect to the ever increasing demand for more light in the home, school and office building is a provision for more windows and better window glass. Here are fourteen reasons why our window glass is not only better glass, but "The Best Glass."

1. Our melting furnaces are the largest in the world and produce uniformly melted batch.
2. Our improved mechanical process of drawing and blowing gives our glass greater tensile strength and higher modulus of rupture than any other window glass, plate glass, or rolled glass.
3. Our latest improvements in our blowing machines enable us to produce absolutely perfect cylinders, which makes it possible to secure the best flattening ever obtained.
4. Our new method of flattening gives our glass a wonderfully even surface, preserving meanwhile the brilliant lustre of the drawing process.
5. Our glass has less wave than other glass, and consequently shows less distortion.
6. Our glass is uniformly flat; it contains no reverse curves.
7. Our glass is uniform in thickness.
8. Our glass is perfectly annealed and therefore does not break as easily as poorly annealed glass.
9. Our glass is washed and thoroughly cleaned in an acid bath, which prevents discoloration and permits ready detection of defects.
10. Our glass cuts perfectly on both sides.
11. Our glass is graded to the highest standard of quality.
12. Our grading is the recognized standard for the United States, and is higher than the foreign standards.
13. Our glass does not break in shipment, on account of the uniformity of flatness, well made boxes, great care in packing, and skillful loading.
14. Our entire process is conducted on scientific principles.




Our elliptical trade-mark together with the grade markings stenciled on every box of the genuine guarantee the quality. Specify "The Best Glass" and be assured of strength, evenness and beauty.

AMERICAN WINDOW GLASS CO.
GENERAL OFFICES: PITTSBURGH, PA. *The BEST Glass* BRANCHES: IN PRINCIPAL CITIES

Please mention ARCHITECTURE in writing to manufacturers

The **FA** Line of Standardized Panelboards



Type R

Safety type small building panelboard for two and three wire requirements, furnished with or without main switch.

Cut shows fuses.
Fuses not furnished.

For Residences, Apartments, Stores

The Triumph Safety Type R Residence Panelboard is the last word in modern, safety type, panelboard engineering. It can be used with equal facility in residences, apartment buildings and stores. It is absolutely safe and can be located at the center of distribution. It is a factory

Type T-P

Plug fuse type connection, 30A tumbler switch controlled branches; safety, with one door opening.

Type T-C

Cartridge fuse type connection, 30A tumbler switch controlled branches; safety with door-in-door front.

Type P

Plug fuse type branches. An extremely narrow panelboard safety type. Also made in two row construction and called Type 2P.

product of standardized unit construction, that costs less—installed—than the old-fashioned porcelain-block, fuse-plug assembly.

Types T-P, T-C, P and 2P are other members of this better designed line of standardized, unit constructed, safety type panelboards.

Write for bulletins giving full information on the Triumph Standardized Safety Type Panelboards.

Frank Adam

ELECTRIC COMPANY
ST. LOUIS

District Offices:

Detroit, New York, Dallas,
Minneapolis, Kansas City,
Cincinnati,
New Orleans, Chicago,
San Francisco, Los Angeles,
Seattle, Philadelphia, Pittsburgh.

Manufacturers of

Major System of Theater Lighting Control; Triumph Line of Safety Type, Standardized Panelboards and Cabinets; knife switches; safety switches; hanger outlets; reversible-cover floor boxes; A. C. and D. C. Distribution Switchboards.

Interesting Wall Sconce in antique iron and gold finish.

CASSIDY COMPANY
INCORPORATED
Designers and Manufacturers of Lighting Fixtures Since 1867
101 PARK AVENUE AT FORTIETH STREET
NEW YORK CITY


ROOF AND
aid. It is not
every so often
on or breaking.
ook L, also our
um Pad
of of his famous
nd.

Architecture, and many other high-grade mag-
booklets are printed with **O., INC.**


Doubletone Inks 72 Reade St.
(REG. TRADE MARK)

Made only by the **Sigmund Allman Co.**
Main Office: Park Ave. and 146th St. New

Please mention ARCHITECTURE in writing to manufacturers



Style A for Exposed Piping Style D Mixes Steam and Cold Water



Recent Installations
 Evanston Golf Club, Carsey Health Club, Postl's Health Club, Big Oaks Golf Club, Union League Club, Chicago Cub's Ball Park.

The Powers Shower Mixer
—a great improvement!

MAKES the shower bath safe and enjoyable by completely eliminating those unexpected "shots" of cold and hot water common to the shower bath equipped with the ordinary mixer.

How It Works

Sudden "shots" of hot or cold water in the shower bath are caused by pressure changes in hot and cold water lines when adjoining showers or other plumbing fixtures are used. In a Powers Shower Mixer there is a simple all-metal pressure balancing valve which instantly equalizes the pressure of hot and cold water before they enter the mixing chamber, so that regardless of pressure changes, a Powers Mixer always holds the temperature of the water where you want it.

Made of brass with nickel plated dial and handle in four styles for exposed and concealed piping. *Send for Bulletin No. 154, which gives detailed information.*




Style B
For Concealed Piping

THE POWERS REGULATOR COMPANY
 2787 Greenview Avenue CHICAGO
Offices in 31 principal cities

THE POWERS REGULATOR COMPANY
Over 30 Years of Specialization
in the Manufacture of Apparatus to Automatically Control Temperature

Introducing~~



For Westinghouse Panel Board Catalogue 42-A, write to our nearest district office or to East Pittsburgh, Pennsylvania.

—the most complete reference catalogue on Panel Boards.


This interesting and attractive book gives a very instructive detailed description of all types of panel boards. It makes careful analyses of all applications.

For architects, engineers and contractors, the Westinghouse Panel Board Catalogue 42-A is an ideal reference book.

Westinghouse Electric & Manufacturing Company
East Pittsburgh Pennsylvania

Westinghouse

Please mention ARCHITECTURE in writing to manufacturers



Speeding Up Production!

Machinery has been the greatest factor contributory to the economical production of Indiana Limestone. Even the minor operations have not been overlooked in this development. An important example of this is a machine called the "Header."


Prior to the introduction of this machine, a piece of moulded work on which a head was to be returned, was first placed on a "Planer" and the long side moulded, then lifted to a banker and the return moulding cut by hand. This method is now obsolete. Today the Header both planes and moulds the return heads, and does away with unnecessary service of the Traveling Crane and Stone Cutter. This modern, efficient method of producing Indiana Limestone is just another reason why such a tremendous quantity is being used today for moderate-cost commercial structures.

Our handsomely illustrated booklet on bank building will be sent free upon request.

Indiana Limestone Quarrymen's Association, Box 771, Bedford, Indiana
Service Bureaus in New York and Chicago



Please mention ARCHITECTURE in writing to manufacturers



Experience

SEEMINGLY, it's worth considering the fact that as builders of greenhouses we have accumulated over a half century of experience.

The iron-framed house originated with Mr. Burnham. Its initial features were first used in the large Jay Gould group, which after two score or more years of constant use is still in remarkable condition.

NEW YORK
30 E. 42nd St.
BOSTON-11
Little Bldg.
PHILADELPHIA
Land Title Bldg.
CLEVELAND
407 Ulmer Bldg.

IRVINGTON
N. Y.

Lord & Burnham Co.

CHICAGO
Cont. Bank Bldg.

Builders of Greenhouses and Conservatories


EASTERN FACTORY
Irvington, N. Y.

WESTERN FACTORY
Des Plaines, Ill.

CANADIAN FACTORY
St. Catharines, Ont.

ST. LOUIS
704 E. Carrie Ave.
KANSAS CITY
Commerce Bldg.
BUFFALO
White Bldg.
DENVER
1247 So. Emerson St.
TORONTO
Harbor Commission
Bldg.

Please mention ARCHITECTURE in writing to manufacturers



Walker and Gillette, Architects, use Stedman in the outer office of a famous engineer

Many Architects have Solved the Flooring Problem

WHEN the best brains of the country turned some twenty years ago to pioneer in the rubber industry, all but one went to making rubber tires. J. H. Stedman, alone, had the greater vision of an even more splendid field. He alone foresaw the perfect floor covering of the future—and wall covering—made of rubber.

Go into one of the great clubs, banks, offices, hotels, hospitals—the Union League Club of New York, the First National Bank of Detroit; the office of McKim, Mead and White, New York; the Jefferson Hotel of St. Louis, the Lying-In Hospital of Boston — and see Stedman's vision realized.

Stedman Naturized Flooring is real rubber, reinforced with millions of minute web-like cotton fibres and integral permanent colorings, vulcanized in great heat under terrific hydraulic pressure.

Impressive as marble itself, Naturized Flooring yields to your foot softly and pleasantly as a carpet of pine needles. Noiseless, resilient—it will not dent, crack or wear out. Soft and firm to the foot it prevents slipping. Sanitary, with an impervious surface. Won't stain, easily cleaned—it requires no care. Simple to install. And the first cost—from 75c to \$2.00 a square foot—is your only cost!

To facilitate architectural specification, we are advertising this flooring directly to home owners, hotel operators, bankers, hospital managements, school-boards, and superintendents. Let us send you complete data and samples.

STEDMAN PRODUCTS COMPANY

Manufacturers of Reinforced Rubber Flooring, Sanitary Base, Wainscoting, Walls, Rugs, Table Tops, Shower Bath Mats, and other reinforced rubber surfacings

SOUTH BRAINTREE, MASSACHUSETTS

Agencies in all principal cities

DIRECT BRANCHES

101 Park Avenue
NEW YORK


4488 Cass Avenue
DETROIT

15 E. Van Buren Street
CHICAGO

462 Hippodrome Annex
CLEVELAND

In marble, granite and tapestry effects—in tiles, square and rectangular, in long runners—browns, reds, grays, black—in a classic floor, or in cozy warm mixtures in Nature's own colorings.

STEDMAN NATURIZED FLOORING



GRAY PAISLEY



R. B.



BLACK PAISLEY



RED PAISLEY



B. W.



O. S.

Please mention ARCHITECTURE in writing to manufacturers



On request a complete folio of these
Granite Studies will be reserved for you.

Please mention ARCHITECTURE in writing to manufacturers



"In the corner stands our piano—it is a beautiful Duo-Art Grand—a Steinway"

HARK! SOMEONE IS PLAYING

It is Paderewski. He is playing the Military Polonaise of Chopin. We thrill at the vivid portrayal and, as we listen, there is borne to us by the music, a tale of the deathless devotion of the player and the composer for their country, their beloved Poland.

The music ceases.

There is a pause, and now, as delicate as old lace, as quaint and beautiful as a coat of brocade, his own Minuet. How crisp his touch, how glorious his tone—his touch and his tone, none other.

And now he is gone and another takes his place at the piano. It is Josef Hofmann. He is playing a Liszt Rhapsodie. How perfect his art. How faithfully it is mirrored by this Duo-Art medium. Truly it is a masterful performance.

We have but to choose whom we would hear. Now it is de Pachmann or perhaps Siloti, who has sat at Liszt's side and learned his art from the

great immortal. Now it is Friedman with his marvelous color and technique; or the great Frenchman, Cortot; Gabrilowitsch, the poet; the ever-charming Percy Grainger; the scholarly Harold Bauer; the delightful Ganz.

The catalogue of Duo-Art Music embraces a large and comprehensive list of the Classics interpreted by the world's greatest Pianists.

There are also a large number of selections from the Grand and Light Operas and the Popular Classics. There are many song rolls including the old English, Scotch and Irish ballads. Plantation Melodies and Folk Songs of different countries. The Song rolls have the words printed on the rolls.

Popular Music from the current successes is published monthly. A very large assortment of Dance Music is available and new selections are added monthly. The Dance Music is recorded by pianists from the leading Broadway Dance Orchestras and is ideal for dancing.

Representatives in all leading cities

The AEOLIAN COMPANY

NEW YORK

LONDON

PARIS

MADRID


SYDNEY

MELBOURNE


Makers of the celebrated Aeolian-Vocalion

Please mention ARCHITECTURE in writing to manufacturers

FERROCRAFT GRILLES



Ferrocraft grille No. 108



Ferrocraft grille No. 170


Ferrocraft Grilles For Churches

AMONG the 500 standard Ferrocraft Grille designs, patterns of which are carefully preserved in our vaults, are numerous ones either especially designed for, or adaptable to, churchly uses.

These three shown are selected from our design book, containing 500 or more.

Every Ferrocraft Grille is painstakingly hand tooled by Ferrocrafters who have a love for their work.

Do not for a moment, confuse such grilles with the foundry products of the ornamental iron class.



Ferrocraft grille No. 109

TUTTLE & BAILEY MFG CO.

Established 1846

2 West 45th Street, New York



METAL GRILLES

Representatives in Principal Cities


36 Portland Street
BOSTON

1123-29 West 37th St.
CHICAGO

Please mention ARCHITECTURE in writing to manufacturers

DRAFTING ROOM DETAILS FOR TILEWORK

ASSOCIATED TILE MANUFACTURERS



PLASTER
 $\frac{3}{4}$ " DULL GL. MOSAIC
 OLD BLUE
 $4\frac{1}{4} \times 4\frac{1}{4}$ BR GL. WHITE
 6x3 ARCHITRAVE
 A-5310 D. GL. GRAY

$\frac{3}{4}$ " DULL GL. MOSAIC
 OLD BLUE
 $4\frac{1}{4} \times 4\frac{1}{4}$ BR GL. WHITE
 CAP A-4150
 DULL GL. GRAY
 $4\frac{1}{4} \times 4\frac{1}{4}$ BR. GL. WHITE
 TOWEL BAR
 DULL GL. GRAY

SILL A-7500
 BR. GL. WHITE
 $4\frac{1}{4} \times 4\frac{1}{4}$ BR. GL. WHITE
 $\frac{3}{4}$ " DULL GL. OLD BLUE
 6x3 BR. GL. WHITE
 $\frac{3}{4}$ " DULL GL. OLD BLUE
 6x6 BASE A-3620
 DULL GL. GRAY

3x3 DULL GL. BLUE
 $\frac{3}{4}$ " UNGLAZED WHITE
 $\frac{3}{4}$ " DULL GL. MOSAIC
 LT. GRAYISH GREEN

GRADES: White Glazed Tiles "Standard" grade; all others "Selected" grade. Grade certificate to be furnished by contractor for all tiles.
 Colors will be selected by architect from samples to be submitted by contractor.
 Joints to be standard width in natural gray Portland cement.

This design is intended for a bathroom or kitchen. It has good variety in size, color and texture. The sizes and mouldings have been chosen for the scale of an average residence room. The slight variation in colors, characteristic of dull glazed tiles and faience give additional "texture" and in the floor take the place of a geometric pattern. The color designations are arbitrary; the numbers of trim and mouldings apply to standardized shapes obtainable from any producer.

The object of this page is to furnish by example informative data on some of the products of the Tile industry. Detailed information on methods of application and specification provisions may be found in publication K-300 "Basic Specification for Tilework." Kinds, sizes, grades, etc., are listed in publication K-200 "Basic Information on Tiles."

ASSOCIATED TILE MANUFACTURERS
 BEAVER FALLS — PENNSYLVANIA

If not in your files request a copy of publication K-300 "Basic Specification for Tilework."

Please mention ARCHITECTURE in writing to manufacturers

AMERICAN BRIDGE COMPANY

EMPIRE BUILDING—71 BROADWAY NEW YORK

*Manufacturers of Steel Structures of all classes
particularly BRIDGES AND BUILDINGS*

SALES OFFICES:

NEW YORK, N. Y.	71 Broadway	Denver, Colo.	First Nat. Bank Building
Philadelphia, Pa.	Widener Building	Salt Lake City, Utah	Walker Bank Building
Boston, Mass.	120 Franklin St.	Duluth, Minn.	Wolvin Building
Baltimore, Md.	Continental Building	Minneapolis, Minn.	7th Ave. & 2nd St., S.E.
PITTSBURGH, PA.	Frick Building		
Cincinnati, Ohio	Union Trust Building		
Cleveland, Ohio	Guardian Building		
Detroit, Mich.	Beecher Ave. & M. C. R. R.		
CHICAGO, ILL.	208 So. La Salle St.		
St. Louis, Mo.	Liberty Cent. Trust Building		

Pacific Coast Representative:

U. S. Steel Products Co., Pacific Coast Dept.

San Francisco, Cal.	Rialto Building
Portland, Ore.	Selling Building
Seattle, Wash.	4th Ave. So., Cor. Conn. St.

Export Representative: United States Steel Products Co., 30 Church St., N. Y.



CLOISTER BRICK

A BRICK that will bring out the utmost beauty of your designs. Its soft, even texture, like silk velvet, gives to the finished brick wall the coveted charm of simplicity and of quiet dignity.


The four shades of red and brown in which Cloister Brick are made befit its distinctive texture. They are rich—glowing. They give life and character to your structure.

Cloister Brick are shale. They are side cut. They are impervious. They are without glaze—and they are inexpensive.

You will want our booklet, "The Cloister Brick." Write Dept. 410

WESTERN BRICK COMPANY
DANVILLE ILLINOIS

Capacity Over One Hundred Million Annually



INTERNATIONAL CASEMENTS

JAMESTOWN, NEW YORK
+ SALES OFFICES +

NEW YORK CITY: 101 Park Avenue
BOSTON MASS: 49 Federal Street
ST. LOUIS. MO: Chemical Building
CHICAGO. ILL: 58 E. Washington St.
SAN FRANCISCO CAL: Hearst Building
+ AGENTS IN PRINCIPAL CITIES. +

Please mention ARCHITECTURE in writing to manufacturers



Harrisonburg, Va.,
home of
R. G. Alexander,
Chicago

Before and after
remodeling

A Renaissance

*effected by
the use of*

Koll's

Lock-Joint
Wood



Columns

HERE is an outstanding example of the effective use of the right Columns. In plans for remodeling or building a structure, where columns are specified, due consideration should be given to the adaptability of Koll's patent lock-joint wood Columns. They are accepted as standard where Columns of architectural correctness, built for permanence, are desired. Have all the facts about Koll's Columns before you. Write today for Catalogue 47-13.

HARTMANN-SANDERS CO.

Originators and Sole Manufacturers of
KOLL'S PATENT LOCK-JOINT COLUMNS
Manufacturers of

COLONIAL ENTRANCES, PILASTERS AND PORCH MATERIALS


Main Office and Factory
2155-87 Elston Ave.
Chicago

Eastern Office and Salesroom
6 East 39th St.
New York

Pacific Coast Factory, 421 Colyton St., Los Angeles

An Investigation

and comparison of Electric Self-Winding Master Regulators will show the most skeptical that the



Landis
Self-Winding Regulator
Movement



ELECTRIC Time and Program Clock System

uses the most economical, simplest, and most reliable regulator movement that is made today.

Some Users:

Board of Education, Philadelphia, Pa.
125 Installations
Board of Education, Baltimore, Md.
15 Installations
Board of Education, Butte, Montana
7 Installations
Board of Education, El Paso, Texas
5 Installations
and Thousands of others

Our Engineering Department

is at your service. Send us your preliminary plans, let us prepare and submit detailed specifications, conduit and wiring layout with complete data for your general electrical specifications.


*Let us send you our
new catalog*

Manufactured and Sold by

LANDIS ENGINEERING AND MFG. CO.

WAYNESBORO, PA., U. S. A.

Please mention ARCHITECTURE in writing to manufacturers



*A South Orange, N. J., Home
heated with a Thatcher Boiler*

THATCHER BOILERS

GIVE owners a little more than they usually expect of their heating plants, in comfort, convenience and fuel economy. When you specify Thatcher Boilers you can count on receiving an extra measure of good will from your clients.



THATCHER HEATERS & RANGES

THATCHER FURNACE COMPANY
Makers of GOOD Heaters and Ranges Since 1850

New York
133-135 West 35th St.

General Offices
Newark, N. J.
39-41 St. Francis St.

Chicago
341 Clark St.

AIR Engineering Service

The American Blower Company offers the cooperation of a competent Engineering department in the solution of any problem along the following lines:

HEATING
VENTILATING
AIR WASHING
FANS AND BLOWERS
EXHAUST FANS

American Blower service and mechanical equipment represents the development of forty successful years. Write for descriptive Bulletins.

AMERICAN BLOWER COMPANY, DETROIT
BRANCH OFFICES IN ALL PRINCIPAL CITIES
CANADIAN SIROCCO COMPANY, WINDSOR, ONT.
(330)

American Blower
SIROCCO
EXHAUSTERS - VENTILATING FANS - AIR WASHERS - BLOWERS - ENGINEERS
FOR HEATING, VENTILATING, DRYING,
AIR CONDITIONING, MECHANICAL DRAFT

REFRIGERATING

*Machinery & Equipment
for all Purposes*

MARKETS
HOTELS
ICE PLANTS
HOSPITALS
APARTMENT HOUSES

BAKER, SMITH & CO., INC.

Contractors

572 GREENWICH STREET

NEW YORK CITY

Offer you the service and extensive experience of their engineers

Communicate with us for estimates on your requirements

THE KEystone OF EVERY
ARCHITECT'S LIBRARY

A History of Architecture

FOR THE STUDENT, CRAFTSMAN, AND
AMATEUR

Being a Comparative View of the Historical Styles
from the Earliest Period

By BANISTER FLETCHER

Professor of Architecture in King's College, London, and

BANISTER F. FLETCHER

Instructor in the Architectural Studio, King's College, London

New Edition, enlarged

With 3,500 illustrations. \$12.00

This is something more than a history of architecture; it might well be called an encyclopædia of architecture.

In the illustrations, you will find the key to every style of architecture known.

If you had only *one* book, this one, you'd have a good reference library. It is a manual of condensed but adequate information.

Charles Scribner's Sons, New York

Please mention ARCHITECTURE in writing to manufacturers

Preoccupied!

NINE tenths of the elevator accidents are due to one cause. The passenger is preoccupied. He is not thinking about exercising reasonable precaution in getting on and off the elevator. He is in a hurry to get to the office, or perhaps to get started on an important errand.

Notice the number of passengers who get off at the wrong floor. They are thinking about something else—preoccupied!

You can't change this condition. You *can* see to it that it doesn't bring disaster. Equip your elevators with automatic locks, so that the careless passenger *cannot* injure himself and blame the management of the building.

M-C-K Automatic Locks not only protect the passenger absolutely, they do *not* slow up the elevator. They're easily best.

Write for booklet, giving all the facts
—and let us estimate your job.

ELEVATOR LOCKS CO.
General Office and Factory
PEORIA, ILLINOIS

BRANCH OFFICES:
WASHINGTON—1407 L Street N. W.
BALTIMORE—814 American Building
CLEVELAND—1940 East 6th Street
CHICAGO—22 West Monroe Street
NEW YORK—116 West 39th Street

Absolute Safety

M-C-K

at Elevator Doors



Oak floors are laid throughout "The Perfect House," Glen Ellyn, Ill., shown above, with the living room at the left, now being featured in motion picture houses throughout the United States, under the title, "The Great Idea."

Oak Floors throughout

—for permanence,
character, charm

As guests enter the home, they are welcomed by oak flooring in the hallway, reflecting in its bright polished surface the beauty and variety of figure that characterize oak. Hospitality extends into the living room, comfortable and "home-like" in its appointments, enhanced also by Nature's permanent floors of oak.

In the dining room, too, oak floors, finished to harmonize with the coloring of walls and hangings, convey a sense of well-being and enjoyment; in the bed rooms they possess that quiet dignity and charm that invite rest. The new finishes conform to room decoration.

All these advantages are lasting, for oak floors improve in mellowness and beauty with the years and are always modern.

The booklet shown below, with color plates of the new finishes, will be sent to architects upon request. Mail the coupon.

See our catalog in Sweet's, page 481,
Seventeenth Edition

OAK FLOORING BUREAU
1040 Ashland Block, Chicago

NATURE'S GIFT OF EVERLASTING BEAUTY


Please send me your free illustrated booklet,
"The Story of Oak Floors."

Name _____

Address _____



Please mention ARCHITECTURE in writing to manufacturers



Tudor Stone

THIS study in brick, stucco and Tudor Stone is interesting both for its excellent structural design and for its harmony of coloring. The picturesque roof of Vermont Tudor Stone slopes steeply down to the eaves at different levels above the ground, giving this house much of its individuality.

Further information regarding Tudor Stone will be gladly given on request to our Architects' Service Department.

Write for Booklet

Rising and Nelson-Slate Company

West Pawlet, Vermont

Architects' Service Department, 101 Park Avenue, New York
BOSTON PHILADELPHIA CHICAGO



Charm As Old As Tradition

BRING to the estate the picturesque utility and true old-time rusticity of the FITZ STEEL WATER WHEEL. No matter what size the stream, there is a FITZ WHEEL in suitable size, width and capacity to harness the power and to furnish electricity and pump water for all parts of the estate.

The Fitz Water Wheel Company

Hanover, Pa.

I-X-L Steel Overshoot Water Wheels, Mill Gearing,
Pulleys, Steel Flumes, Forebays, Burnham Turbines

BATCHELDER TILES



FOUNTAIN DESIGN No. 208

BATCHELDER-WILSON CO.
2633 ARTESIAN ST. LOS ANGELES




May we send you
"The Banking
House in Art
Metal"

FOR a third of a century Art Metal has co-operated with architects in faithfully executing their designs for bank interior equipment in bronze and steel. Our experience covers everything from the elaborate bronze doors, bank screens, etc., to the steel counter work, partitions, cages and office equipment. We are proud to have justified the confidence architects have placed in our organization.

Art Metal

JAMESTOWN, NEW YORK

Steel and Bronze Equipment for Banks
Steel Office Equipment, Safes and Files



SANITAS

MODERN
WALL COVERING



Marks a distinct advance in the type and quality of wall coverings

PRACTICALLY every disadvantage inherent in other kinds of wall coverings is overcome by Sanitas. It forms one of the most important advances in the type and quality of materials used for covering and decorating walls.

Sanitas is made on cloth, machine-painted with durable oil colors. It does not fade, crack, tear, peel or blister. Its oil-color surface, impervious to moisture, grease and stains, can be wiped clean with a damp cloth. On new walls it can be applied as soon as the plaster is dry; on old, cracked walls often Sanitas is the only practical covering. Ideal over wall-boards.

Sanitas comes in styles for every room in the house.

Enamel Finish plain colors and tile effects for kitchens, bathrooms, etc.

Flat Finish plain tints that can be hung as they come, stenciled, frescoed, stippled, or Tiffany blended.

Decorative Patterns, floral designs, tapestry, grass-cloth, leather and fabric effects.

Our Architects' Service Bureau will gladly send samples and suggestions, on request.

THE STANDARD TEXTILE PRODUCTS CO.

320 BROADWAY, NEW YORK

Dept. A.A.

Please mention ARCHITECTURE in writing to manufacturers

DAHLSTROM



Illustrating Dahlstrom Metal Corridor Doors in the Otter Tail County Court House, Fergus Falls, Minn. Architects: Buechmer & Orth, Shubert Bldg., St. Paul, Minn.

THE SUPERIOR DOOR

FOR twenty years the Dahlstrom Metallic Door Company has successfully supplied metal doors and trim for all types of modern buildings. These twenty years of good door building have proven the DAHLSTROM STANDARD CONSTRUCTION is correct.


Protection, appearance and durability, the triplets of this construction, have all been tried and proven successful in DAHLSTROM hollow metal doors and trim.

Exterior of Otter Tail County Court House,
Fergus Falls, Minn.


DAHLSTROM METALLIC DOOR CO.
495 BUFFALO STREET, JAMESTOWN, NEW YORK

NEW YORK CHICAGO DETROIT
25 Broadway 19 So. La Salle St. 1331 Dime Bank Bldg.

Local representatives in principal cities



Please mention ARCHITECTURE in writing to manufacturers



IN CARVED WOOD—

ALTARS · REREDOSSES

PULPITS · CHOIR STALLS

LECTERNS

ORGAN SCREENS · ROOD BEAMS

SANCTUARY AND

CHANCEL FURNITURE

PEWS


THE WOOD CARVING STUDIOS OF

American Seating Company

NEW YORK
610—119 W. 40th St.

CHICAGO
1093 Lytton Bldg.

PHILADELPHIA
707—250 S. Broad St.



FREER MEMORIAL, Washington, D. C.
Charles A. Platt, Architect
Meyers, Strong & Jones, Electrical Engineers

Frink Reflectors in the Freer Memorial

THERE has been much favorable comment on the lighting effects produced in the new Freer Memorial. We shall be glad to give architects planning galleries, the benefit of our experience, which covers over thirty years' planning on this type of work. May we emphasize the importance of taking up such plans before the work is too far advanced?

"Specify Frink Reflectors"

I. P. FRINK, INC.

24TH STREET AND 4TH AVENUE, NEW YORK

Chicago, Ill.
Monadnock Bldg.

St. Louis, Mo.
1415 Pine Street

Birmingham, Ala.
426 Jefferson Co.
Bank Bldg.

San Francisco, Cal.
77 O'Farrell Street

Detroit, Mich.
325 State Street

Buffalo, N. Y.
310 Mutual Life
Bldg.

Philadelphia, Pa.
Franklin Tr. Bldg.

Seattle, Wash.
609 Seaboard Bldg.

Atlanta, Ga.
1526 Candler Bldg.

Boston, Mass.
161 Summer Street


Louisville, Ky.
415 W. Main St.

Canada:
Associated with Robert Mitchell Co., Ltd.
64 Belair Avenue, Montreal

Cleveland, Ohio
992 The Arcade

Cincinnati, Ohio
601 Second Nat'l
Bank Bldg.

Please mention ARCHITECTURE in writing to manufacturers



THE NAME *Klieg Bros.* MEANS QUALITY

OUR ENTIRE FACTORY IS AT YOUR SERVICE FOR THE PRODUCTION OF

Act Announcers	Stereopticons	Foot Lights, Border Lights, Strip
Arc Lamp Spot Lights	Stereopticon Arc Lamps	Lights, Proscenium Lights
Nitrogen Type Spot Lights	Step Lights and Aisle Lights	Scenic and Stage Effects
Asbestos Covered Cable	Carbons, all types	Portable Plugging Boxes
Aisle and Step Lights	Dimmers	Projection Apparatus
Color Box or Boomerang	Dimmer Boxes, Portable	Parts for Arc Lamps
Color Frames	Effects	Pipe Clamps
Coloring for Lamps	Framing Shutters and Blinders	Stage Cable
Color Wheels, Hand and Auto-	Gauze for Scenes	Stage Connectors
matic	Gelatine, Mediums	Stage Pockets
Condensing Lenses	Iris Shutter	Shutters, all types
Connectors	Iris Dissolver	Wall Type Pockets and Plugs
Copper Terminals	Music Stands	

UNIVERSAL ELECTRIC STAGE LIGHTING CO., Inc., 321 West 50th St., New York

ENGRAVINGS IN "ARCHITECTURE" BY POWERS REPRODUCTION CORPORATION PHOTO-ENGRAVING SPECIALISTS

205 WEST 39TH ST.

NEW YORK CITY

TELEPHONE : PENNA. 0600



Tycos
temperature
instruments

Time tells with *Tycos*. The ability to stand up under constant duty makes it worth your while to specify *Tycos*.

Taylor Instrument Companies
Rochester, N.Y., U.S.A.

There's a *Tycos* and *Taylor* temperature instrument for every purpose

SAMSON SPOT SASH CORD



Trade Mark Reg. U. S. Pat. Off.

is made of extra quality cotton yarn, is carefully inspected, and is guaranteed to be free from all imperfections of braid or finish.



Samples and full information furnished on request.

SAMSON CORDAGE WORKS

BOSTON, MASS.

IF SERVICE IS DESIRED SPECIFY

The CALDWELL VERTICAL DOOR HOLDER



Made 1¼ in. and 4¼ in. drop. With the original vacuum rubber, reinforced to prevent frazzling and tearing.

MADE BY
CALDWELL MFG. CO.

3 JONES STREET

ROCHESTER, N. Y.

WORLD'S MOST COMPLETE LINE HEATING SPECIALTIES

YOUR attention is invited to the B. & B. Line of Heating Specialties, including the B. & B. Air Line System of Steam Circulation, Temperature Control System (All-Metal Thermostat, Pneumatic Valve), Multiflex Valve, Modulation Valve, Multiflex Trap, Vacu-Trap, Vacu-Stat, Blast Trap, Steam Damper Regulator and Hot Water Damper Regulator.


Write for Hand-Book "Modern Heating & Ventilating." Just off the press

Service and Sales Offices in 26 important cities

THE BISHOP & BABCOCK COMPANY

General Offices and Factories, CLEVELAND, OHIO

Please mention ARCHITECTURE in writing to manufacturers



KINNEAR
ROLLING DOORS
KINNEAR

Kinnear Motor Operated Steel Rolling Doors in Factory, American Insulation Co., Philadelphia, Pa.

Unfailing Satisfaction

Because of the perfect balance and alignment, the operation of KINNEAR Rolling Doors is always a satisfaction. They are always ready—always easy to open or close—giving an unfailing service that is invaluable to industrial establishments of all kinds.


They may be operated by hand, mechanically, or by motor. This makes them adaptable to buildings of all sizes. Kinnear Doors are really a part of a building—each door being built especially to fit in with the building plan.

Kinnear Fire Doors bearing the Underwriters Label are recognized by architects as the standard by which all other doors are judged. They are trustworthy under all conditions.

We maintain branches in the leading centers—thus securing for you the maximum efficiency at all times.

Our Engineering Department is at your service for consultation on special problems of installation. Write for illustrated booklet.

The Kinnear Manufacturing Company
660-670 Field Ave., Columbus, Ohio



Build sanitation and silence into your structures by insulating between walls and beneath floors with Viskote "A."

Viskote
SANITARY—SOUND—PROOF

RICHARDSON
Product

From the makers of Richardson Roofing (including Flex-a-tile Housetops), Viskalt Membrane Roofs, Wall Board and similar products.

© 1923, The Richardson Company

Protection that every building needs

How do you protect against noise and vermin the buildings you design? The requirements of modern hygiene, as you know, make such protection not merely an added refinement but a necessity.

Here is a very simple way to deaden sound and at the same time to provide a sanitary coating against vermin and spillage. Insulate between walls and beneath floors with Viskote "A."

This improved material is a loosely woven blanket-like felt, coated on both sides with a highly adhesive waterproof surfacing of Viskalt Compound.

Double protection

Such a germ-proof coating not only repels mice, fleas, moths and other vermin, but also prevents spillage from setting up unhealthy conditions. The heavy, cushioned fabric which forms the base of Viskote contains innumerable dead air cells which absorb and reflect sound to a remarkable degree. Moreover, Viskote, because of its tough coating is not subject to fatigue, and therefore, does not crumble and break up.

You can readily see the distinct advantages of Viskote—sanitation and silence—especially for public buildings such as schools, hospitals, and libraries, as well as

homes. And once installed it lasts as long as the foundation.

A new use for Viskote

This unique product has now been specially prepared as Viskote "B," to meet a new use—as a cushion to be laid under linoleum and other floor covering.

After being softened on both sides with Viskote Primer, it adheres firmly both to the floor and to the floor covering, thus forming a waterproof, sanitary cushion which adds long life to the linoleum and insulates against heat, cold and dampness.


Moreover, it meets fully the recommendations of the foremost manufacturers of linoleums and floor coverings, who strongly urge the use of a felt cushion cemented both to the linoleum and to the floor.

Viskote is made by a firm backed by over fifty years of manufacturing experience. You will find it distinctly helpful to know the other construction products of this company. For complete specifications, just write the Construction Materials Division, Dept. 31-1.

The RICHARDSON COMPANY

Lockland (Cincinnati), Ohio
Melrose Park (Chicago), Ill. New Orleans, La.

Please mention ARCHITECTURE in writing to manufacturers

SONNEBORN PRODUCTS**Architects Specify Cemcoat**

*When they see its Glossy, Washable,
Durable, Light-Reflecting Finish*

Write for this free Sample Board—Seeing is Believing.

In our main laboratory where chemical fumes are usually present, there are four panels each painted with a different well-known mill white including

Cemcoat

The Industrial Enamel Paint

For over a year these panels have been subjected to fumes, washing and bright sun light.

The Cemcoat panel *alone* has resisted the yellowing effect of time. Its surface *only* has maintained its full glossy, light-reflecting power. Its super refined, pure linseed oil, its carefully ground pigments and our chemists' skill in compounding have clearly won superiority for Cemcoat.

So we are able to say to all architects:

Cemcoat stays white, resists washing and lasts longer. Exterior and Interior Cemcoat are unsurpassed.

All tints and colors: gloss, eggshell and flat.

OTHER SONNEBORN PRODUCTS:

LAPIDOLITH—the liquid chemical which makes concrete floors dustproof and wearproof. Write for reference near you.

HYDROCID No. 648—which renders concrete foundation walls and footings waterproof and dampproof.

HYDROCID No. 633—which makes the inner surface of exposed walls dampproof.

HYDROCID, COLORLESS—a transparent liquid compound for waterproofing exposed exterior masonry walls, copings, parapet walls, etc.

HYDROCID INTEGRAL—for waterproofing mass concrete, stucco and mortars. It is incorporated in the mix, in powder and paste form.

LIGNOPHOL—the modern wood preservative, gives new life to old or new wooden floors.

STORMTIGHT—a liquid roof coating for all kinds of worn or new roofs. Stops and prevents leaks and lasts for years.

FERMO—accelerates the setting of concrete to such an extent that it effects considerable saving in time and money, even in warm weather. In cold weather it saves the concrete from freezing.

L. SONNEBORN SONS, INC.

116 Fifth Ave., Dept. 9

New York

(SONNEBORN)

THE CUTLER MAIL CHUTE

*manufactured and installed to
sustain a reputation for good
work and service enjoyed by
us for nearly forty years.*

*Specify Model F
Standard equipment
for Cutler quality
at least cost.*

CUTLER MAIL CHUTE CO.
OFFICES AND FACTORY
ROCHESTER, N. Y.

NO MORE
Sticking
Rattling
Dust
Draft



SAVES
Nerves
Housework
Doctor Bills
Fuel

VICTOR PARTING BEADS

Should be part of every double-hung window-frame. They prevent sash from sticking and rattling despite all swellings, warping and shrinking. Many of the foremost Architects specify Victor Parting Beads regularly. Any new building fully equipped with Victor Parting Beads costs less to build—and less to maintain.


THE VICTOR PARTING BEAD CO.
READING, PA.

*For Permanent
Walls and Ceilings*

Bostwick

TRUSS-LOOP
METAL LATH

THE BOSTWICK STEEL LATH CO.
NILES, OHIO



Pfaudler Glass Lined Water-Cooling Tank, Hotel Statler, Buffalo, N. Y.

PFAUDLER WATER-COOLING TANKS

—for residences —for hotels —for office buildings

THIS is another Pfaudler product which has become very popular—a cooling tank for ice-water storage, in drinking-water systems. Some of the typical installations are:

Dommerich Residence, Greenwich, Conn.
Trowbridge Residence, Noroton, Conn.
Wagner Residence, Greenwich, Conn.
Everett Building, New York City
Bulletin Building, Philadelphia

Bulletin Building Annex, Philadelphia
Maryland Casualty Building, Baltimore
Church Home and Infirmary, Baltimore
Reed & Prince Mfg. Co., Worcester, Mass.
Hotel Statler, Buffalo, N. Y.

Absolutely non-contaminating, this equipment is a basic part of any up-to-date water-drinking system.



THE PFAUDLER CO.

Makers of Glass Lined Steel Laundry Chutes

ROCHESTER, N. Y.



Mail the coupon
for data.

Gentlemen:
Tell me about your
water-cooling tank.

Name

Address

A 10-23

.....1923

THE PFAUDLER CO.
Rochester, N. Y.

Please mention ARCHITECTURE in writing to manufacturers

Safeguard your clients' property from fire and lightning—and add *security* to lasting service. Be particular to specify Keystone Copper Steel



BLACK AND GALVANIZED

SHEETS


and Roofing Tin Plates

Keystone Copper Steel makes better and safer roofs and more lasting sheet metal work. This alloy assures greatest wear and *rust resistance* for roofing, siding, spouting, gutters, eaves trough and similar uses. Look for the Keystone added to regular brands.

APOLLO-KEYSTONE Galvanized Sheets will give increased wear and permanence to the sheet metal work on your buildings. Demand Keystone quality for superior rust-resistance.

KEYSTONE COPPER STEEL Roofing Tin Plates make clean, safe, attractive and satisfactory roofs. Supplied in grades up to 40 pounds coating—specially adapted to residences and public buildings. Metal roofs may be painted to harmonize with the color scheme of the building—an important feature which is often overlooked. Keystone quality products are sold by leading metal merchants, and are used by first-class roofers and sheet metal workers. Send for our booklet, "Copper—Its Effect Upon Steel for Roofing Tin."

AMERICAN SHEET AND TIN PLATE COMPANY, Pittsburgh, Pa., U. S. A.



ORIGINATORS OF SASH CHAINS

BLACKSTONE HOTEL
one of Chicago's high class buildings, is equipped with our chain.

Catalog A-1 sent on request

THE SMITH & EGGE MFG. CO.
BRIDGEPORT, CONN.

The quality of Ripolin Enamel Paint has won recognition all over Europe and America. It first commanded favor in many residences; then in our finest hospitals, hotels and clubs. During the more recent years, however, it has been used wherever a really fine, yet economical enamel result has been desired. Specification data on request.

THE RIPOLIN COMPANY, CLEVELAND, OHIO

RIPOLIN

THE ORIGINAL HOLLAND ENAMEL PAINT

Please mention ARCHITECTURE in writing to manufacturers



HOTEL LAFAYETTE
LEXINGTON, Kentucky
C. P. & E. J. Weber, Architects

Smokeless and Economical Hotel Heating with Utica-Imperial SUPER-SMOKELESS Boilers

UPER-SMOKELESS heating of large buildings is highly economical and satisfactory because of the smokeless operation and adaptability to available fuel during coal shortages. Fore-architects and engineers specify SUPER-SMOKELESS for important buildings where low fuel costs and compliance with rigid smoke ordinances are essential. Soft coal is the fuel, but fuel oil is proving very successful.

Patented design of SUPER-SMOKELESS Boilers provides clean air at the heart of the fire, thus converting the heavy combustible gases into intensely hot, clean flames of great heating


capacity and entirely eliminating objectionable smoke and soot when burning soft coal.

Replacement of other types of boilers with the scientifically designed SUPER-SMOKELESS Boiler has repeatedly resulted in fifty per cent reduction in annual coal costs. Selected fuels are no longer necessary, care and attention is reduced to a minimum, and smokeless operation is a reality.

A complete descriptive catalog, together with a copy of the special Timmis Report, will be sent upon request to architects interested in efficient heating equipment for large buildings.

essly and Economically
ed by Three 16 Section
**R-SMOKELESS
AM BOILERS**

Installed by the
**W PLUMBING AND
EATING CO.**



**UTICA HEATER
COMPANY**

UTICA, NEW YORK

218-220 W. Kinzie Street, Chicago
707 Union Building, Cleveland
1843 Grand Cent. Term., New York

*Sales Offices in Principal
Jobbing Centers*

Please mention ARCHITECTURE in writing to manufacturers

THE MADVAL BIDET




The Bidet provides so much in the interests of health and personal cleanliness that it is rapidly becoming an essential fixture in the modern bathroom.

The fixture illustrated is the Madval Bidet, a Thomas Maddock vitreous china fixture that embodies all the latest refinements and sanitary advantages developed in the plumbing industry — a fixture that in every way is truly representative of the high quality that always has characterized Thomas Maddock fixtures.

ARCHITECT'S SPECIFICATION: White Vitreous China Flushing Rim Pedestal Bidet Pan; height, 15 inches, with Douche and Fixture Shelf. Fitted with N. P. Brass 1/4-inch Pop-up Waste

Fixture with China Knob, 1/4-inch O. D. Tailpiece; "Hot" and "Cold" Compression Supply Valves with China Cross-arm Handles and Escutcheons, and Transfer Valve with China Lever Handle and Escutcheon, permitting either "Hot" and "Cold" Supply to Flushing Rim or center Douche; Supply Pipes to floor.

Send for literature describing the use and construction of this fixture.



THOMAS MADDOCK'S SONS CO.
TRENTON, N. J.



Please mention ARCHITECTURE in writing to manufacturers


Complete Specifications for Architects

Covering Enclosed Type Motor Starters and Control Apparatus
for Hotels, Public Buildings, Theatres, Factories, Office Buildings

To provide greater uniformity—and reduce the cost of enclosed motor starters and controller for pumps, fans, and the scores of motor-driven machines used in office buildings, hotels, theatre buildings, etc., Cutler-Hammer engineers have developed and standardized a complete line of this class of apparatus.

The requirements of leading architects and engineers as well as those dictated by the National Electrical Code, Electric Power Club, and other safety codes have been incorporated.

Instead of building these as special equipment they are now a regular part of the C-H line, information in usable form for the architect being included in 40 pages of typed




Prominent architects have found this information of value and such buildings as the Union Trust, and Keith's Theatre in Cleveland, and the new Statler Hotel in Buffalo have recently been equipped with this class of controller.

The book of specifications is designated as Publication No. 2068, a copy of which will be forwarded to you for your specification writing department.

THE CUTLER-HAMMER MFG. CO.

Motor Control Department
Works: MILWAUKEE and NEW YORK
Offices and Agents in Principal Cities
Northern Electric Co., Ltd., Can.


*Get a Copy for
Your Specification
Writing Dept.*



ENCLOSED CONTROLLERS


BUILDING EQUIPMENT STYLE WITH CIRCUIT BREAKERS

Please mention ARCHITECTURE in writing to manufacturers



Sectional view of Fig. 106,
screwed. Jenkins Standard
Bronze Globe Valve.

Messrs. Schultze and Weaver, Architects, New York. Mr. Clyde R. Place, Consulting Engineer, New York. Thomas Haverty Co., Los Angeles, Heating and Plumbing Contractors.



LOS ANGELES BILTMORE

Valves for Hotels

GUEST satisfaction, and a maximum return from capital invested, two objectives in hotel management, are materially promoted by Jenkins Valves.

Jenkins Valves, widely used in fine hotels, are a sound investment for two reasons. First, functioning reliably in plumbing, heating, and fire protection, they contribute to the convenience, comfort, and safety of the guest; second, due to years and years of dependable usefulness in severe as well as average service, dividends are paid in economy of valve maintenance.

Hundreds of different types of Jenkins Valves are installed in the Los Angeles Biltmore as well as in numerous other first class hotels throughout the United States and elsewhere.

Specifications calling for *Jenkins throughout* provide true valve economy.



Fig. 715, Jenkins
Bronze Fire Line
Angle Valve.



Fig. 325, screwed,
Jenkins Iron Body
Gate Valve.



Fig. 370, screwed,
Jenkins Bronze
Gate Valve.



Fig. 294, screwed,
Jenkins Iron Body
Swing Check
Valve.

JENKINS BROS.

New York
Montreal

Boston

Philadelphia

Chicago
London

FACTORIES: Bridgeport, Conn. Elizabeth, N. J. Montreal, Canada



Always marked with the "Diamond"

Jenkins Valves


SINCE 1864

2927-J


Please mention ARCHITECTURE in writing to manufacturers

Why is tile soaked in water before it is used?


The reason tile and china must march hand-in-hand



*Combination
Soap Holder
and Safety Grip*



Tumbler Holder



Sponge Holder

AS EVERY tile contractor knows, tile must be soaked before it is installed in bathroom walls. This soaking is necessary in order to prevent undue absorption, by the porous tile, of the moisture contained in the cement. Otherwise, the cement would dry too quickly, destroying its holding properties, so that the tile would loosen from the wall. Another thing, after tile has been in service a few months notice the series of fine cracks in the thinly glazed surface.

Just so with tile built-in bathroom fixtures. They, too, are porous. The thinly glazed surface of the tile after a time becomes cracked and crazed. Through continuous daily use, these cracks admit soapy water or other liquids. Soon the tile fixtures become stained and unsightly to the eye and unsanitary.

Because of this quality, tile should only be used for covering walls, while, for fixtures, Fairfacts China Bathroom Fixtures should be used. They never crack, craze or stain. Fairfacts Fixtures are made of solid snow-white china which refuses to absorb the moisture and foreign matter. For dignity, grace of line and variety of design they are unmatched.

Write for Catalog F. Details and specifications also appear in Sweet's Catalog.

Fairfacts Fixtures are installed by tile contractors—the only trade that does this work and should be included in the tile contract. We do not sell the plumbing trade.

THE FAIRFACTS COMPANY, Inc.

Manufacturers

Dept. A

234-236 West 14th Street

New York City

Look for this



trademark

Fairfacts Fixtures


BUILT IN YOUR BATHROOM WALLS

Please mention ARCHITECTURE in writing to manufacturers

WEISTEEL

TRADE MARK
REGISTERED

Compartments for Banks and Monumental Buildings




WEISTEEL Compartments in design, finish, quality of materials and workmanship, harmonize with other select materials used in fine buildings.

All toilet rooms in Federal Reserve Banks in New Orleans and Nashville are equipped with WEISTEEL Compartments.

Federal Reserve Bank
Nashville, Tennessee
A. Ten Eyck Brown, Architect
Marr & Holman, Associate
Architects
Foster & Creighton, Contractors

1923 Edition Catalog No. II,
giving complete information,
details and specifications, will
be sent on request



HENRY WEIS MANUFACTURING CO.

New York, N. Y.
110 West 34th Street

Chicago, Ill.
105 West Monroe Street

ATCHISON, KANSAS

Boston, Mass.
8 Beacon Street

Los Angeles, Calif.
616 South Utah Street

Please mention ARCHITECTURE in writing to manufacturers

Mixing Valve Showers Where You Control Force as well as Temperature



THERE used to be an objection to the mixing valve type of shower because *then* only the temperature of the water was under control.

Now, with the Anyforce Head a slight turn of the handle gives any desired shower volume—enough to satisfy the fellow who likes it on full, or the gentle rain-like shower often preferred by women, older folks and the children.


The Anyforce Head is a feature of SPEAKMAN Mixometer Showers

The Anyforce Head is featured in our booklet "Once-Used Water." Several shower installations are also shown in this booklet. If you would like to have a copy, also a copy of our Catalog "H," please let us know.

SPEAKMAN COMPANY
WILMINGTON, DELAWARE


SPEAKMAN SHOWERS

Please mention ARCHITECTURE in writing to manufacturers



CONNECTICUT

AUTOMATIC SIGNAL SYSTEM *for Hospitals*



"Making Assurance Doubly Sure"

The safeguard receptacle here illustrated should add more than a single point in scoring the superiorities of the


CONNECTICUT AUTOMATIC HOSPITAL SYSTEM

First—because its design is such that if the plug is removed accidentally or otherwise, all duty station signals are thrown "on"—thus insuring warning of the slightest interruption of service to the patient.

Second—because this protection is not restricted to our regular four-contact lamp annunciator system, but is an equally important feature on any modification of it—even where our new five-contact system is the only one that will come within the appropriation.

The five-contact plug receptacle, cord and button, making possible a simplification of the wiring by having the same pilot light at the duty quarters common to both wards and private rooms, instead of individual pilot lamps for the private rooms and for each ward (which is sometimes done for circuit reasons due to lack of equipment with the fifth contact arrangement) will be the subject of our next advertisement.

Illustration and complete information on request



No. 3 of a series of pages illustrating and describing the superiorities of the Connecticut Nurse's Silent Call System.



CONNECTICUT
MERIDEN

TELEPHONE
& ELECTRIC
SIGNAL SYSTEMS DIVISION

COMPANY
CONNECTICUT



Please mention ARCHITECTURE in writing to manufacturers

SELECT FOR A LIFETIME

THE selection of plumbing fixtures for the residence or industrial building deserves serious consideration. How serious depends upon the kind you select. The proper kind will outlast a lifetime with reasonable care. The life of the other kind may be very, very limited.

The Trenton Potteries Company

All-Clay Plumbing Fixtures represent the best in plumbing. The glaze baked on "Tepeco" Fixtures cannot be baked on anything but clay because no other material will stand the intense heat necessary to produce a genuine glass surface.

That is why the surface of "Tepeco" All-Clay baths, lavatories, kitchen sinks, etc., is the hardest, most durable, sanitary, and easiest to clean. Gritty soaps cannot scratch their surface; medicine and common acid stains will not adhere. A permanent investment—a beautiful one. Catalogs on request.

THE TRENTON POTTERIES COMPANY

Trenton, New Jersey, U. S. A.

New York

Boston

San Francisco



Please mention ARCHITECTURE in writing to manufacturers



MILCOR Metallic Building Products provide a revolutionary system of interior construction for the modern building. Exposed corners are protected from blows that would shatter ordinary plaster construction, and cracking in the interior corners is eliminated by the expanded wings of MILCOR *Expansion* Corner Bead. Used in conjunction with MILCOR *Expansion* Metal Trim and Concealed Picture Molding all wood is eliminated, furnishing the ultimate in modern, sanitary interior finishing.


This New Expansion Corner Bead Gives Better Results at Less Expense

More than four million feet of MILCOR *Expansion* Corner Bead has been placed within the last twelve months in the better buildings in America. Architects and builders have been quick to realize the superiority of expanded metal construction applied to corner bead design—a feature found exclusively in this modern MILCOR product.

Instead of presenting a flat metal surface like old style beads the expanded mesh of this new product actually strengthens the corner by allowing the plaster to key through both itself and the lath to which it is applied. Further, tests show that the expanded structure quickly distributes the force of any impact allowing absorption of greater blows without chipping or cracking of the plaster.

This expanded design is also responsible for the economy of this better corner bead. The open mesh is a great time saver, offering a multitude of points where it can be wired, nailed or stapled in place. No clips are required and the slight additional first cost is repaid many times by the labor saving in its erection. Insist on *Expansion* Bead—no substitute *can* be as satisfactory. The name MILCOR is your protection.

Milwaukee Corrugating Company
Milwaukee • Kansas City • Minneapolis



MILCOR *Expansion* Corner Bead effects great savings in erection costs, the expanded metal wings providing a multitude of places for attaching by nails, wire or staples. The bead is drawn, not stamped, giving perfect alignment and greater strength. In addition to protecting any corner, it actually increases its strength, the expanded metal design allowing the plaster to key through both itself and the lath to which it is applied. Furnished galvanized, or in pure copper, or zinc. Full information as to the use of any MILCOR Products or where they may be obtained will be gladly supplied on request.

MILCOR

Metallic Building Products

Please mention ARCHITECTURE in writing to manufacturers