

# The AMERICAN ARCHITECT



INTERIOR OF SANTA MARIA DELLA SALUTE, VENICE

PUBLISHED WEDNESDAYS IN NEW YORK—FOUNDED 1876  
VOLUME CXV                      MAY 28, 1919                      NUMBER 2266

Entered as second class matter January 6, 1909, at the Post Office at New York, N. Y., under the Act of March 3, 1879. Publication office, 243 West Thirty-ninth Street, New York, N. Y. Subscription price in the United States and Possessions, \$10.



# RAYMOND



**This  
Concrete Pile Form  
will be left  
in the ground**

This is a section of the spirally reinforced steel shell in which every Raymond Concrete Pile is cast. Every Pile has its own shell. Every Pile is thus protected against distortion or weakening of the pile column by any unfavorable underground condition. You may inspect the shell interior after it has been driven.

**RAYMOND  
Concrete Pile Co.**


NEW YORK: 140 Cedar Street  
CHICAGO: 111 W. Monroe Street

*A Form for Every Pile—  
A Pile for Every Purpose*









BASILICA PALLADIANA, VICENZA, ITALY

The greatest work of Palladio and the finest secular building of the Renaissance period. The porticos surround an Italian Gothic town hall

THE AMERICAN ARCHITECT



# THE AMERICAN ARCHITECT

VOL. CXV

WEDNESDAY, MAY 28, 1919

NUMBER 2266

## A Review of The Post-War Committee's Activities at the Nashville Convention

By ROBERT D. KOHN, F. A. I. A.

IT would be quite impossible in a brief article to give any adequate impression of the discussions that took place on the items of the Post-War Committee's program at the recent convention of the Institute in Nashville. The transactions of the Institute, when published, will contain a fairly complete report, but it is worth while attempting to give the impressions of one member of the committee who is very deeply interested in the whole matter.

To begin with, the convention unquestionably went on record as approving the continuance of the work of the committee. This was shown by the vote recorded on the recommendation of the Board of Directors that the Institute be allowed to draw from its reserve fund if necessary in order to carry on this work, as well as certain other important work for the coming year. The vote required a two-thirds majority. While it secured that majority by a narrow margin, a vote of 82 to 40 was really most satisfactory because of the fact that many who voted against the appropriation did so because they thought that the expenses of the committee should be drawn from current funds and not because they disapproved the committee's work. A direct and clear vote on the issue as to whether or not the Post-War Committee was to continue its investigations would apparently have secured the almost unanimous vote of the convention.

The Post-War Committee held a meeting before the convention and one immediately afterwards. At these meetings consideration was given to many hundreds, indeed possibly close to a thousand, communications received from architects throughout the country in response to the questions contained in the program. A very large share of these replies came from men who were not connected with the Institute, thus indicating that the inquiry had aroused a very general interest on the part of the profession at large. The three sessions of the

convention particularly devoted to a discussion of the various items of the program were full of interest and in the opinion of many of those present brought out the most vital and lively discussions that have been heard for many years.

There was considerable delay in getting to the subjects assigned for the first evening session because a good part of the time allotted for the meeting was taken up by an admirable address delivered by Mr. John Bell Keeble, a distinguished attorney of Nashville. His professional message was inspiring and dealt principally with the distinction between the business attitude and the professional attitude toward life. His analysis of the social point of view in the practice of law and architecture was most welcome and highly appreciated.

Mr. Dunning's admirable introduction to the detailed discussion of the Post-War Committee program, followed by an address by Mr. Medary of Philadelphia, the chairman of the evening, set the pace at so high a standard that it was really difficult thereafter to get the modest delegates to express themselves freely. Before the evening was over, however, an enlightening debate had taken place on the possibilities of expansion of the architect's service, the self education that comes through his greater participation as a citizen in public work, and the methods by which he can make his importance in relation to the problems of building more quickly felt. There was no attempt on the part of the speakers to place the architect on a pedestal as a perfect being and to blame the public for all the ills of the profession. There was hardly a speaker who did not frankly say that the architect would have to make his own services more efficient and more complete if he wished to put himself right with the public.

Owing to the desire of the convention to give an earlier opportunity for the discussion of educational problems than had been provided by the program,



## THE AMERICAN ARCHITECT

the session originally arranged for the evening of the last day, and which was to be devoted to the subject of education and registration, was advanced to the afternoon of the second day. There were present not only the regular delegates to the convention but a large number of men connected with various universities and schools where departments of architecture are now already established. The report of the Committee on Education, signed by Mr. Ackerman, Mr. Medary and Mr. Dwight Perkins of Chicago, awakened great discussion, both for and against the principles maintained by the committee. The report attacked the problem in its fundamentals. It pointed out that the faults of our architectural schools are also the faults of our whole system of education. The common and secondary schools and our universities do little to develop independence of thought on the part of their pupils, and so the men who then study architecture have no adequate foundation to work on. Our schools of architecture, it was claimed, are bound by traditional methods of teaching and are out of touch with reality. They do little to give their students a sense of social responsibility and so their methods and their ideals are in need of radical change.

It was interesting to note the varying points of view expressed on the floor during the debate. There was no attempt to deny that the men going through our architectural institutions are inadequately trained. Some claimed, however, that it was impossible to teach men in any institution under any system so that they would be capable of practicing architecture efficiently when graduated. Some of the speakers claimed that the methods of teaching are right in principle, but need more thoroughness in application; that a longer period of instruction is essential; and that the men should be required to go through a number of years of practical training after graduation before being allowed to practice. In this connection the discussion on the value of the registration of architects was interesting. Mr. Waid clearly pointed out that when the standard of qualifications set for registration in the various States was placed sufficiently high, then registration would be an important element in the educational problem. Many who had rather grudgingly agreed to registration laws merely as a means to prevent the obviously inefficient from practicing now recognize that in some States registration has actually raised the educational standards of the profession.

Throughout the entire discussion of the problems of education there was displayed a very broad-minded willingness on the part of teachers to accept constructive suggestions for reform. They seemed

to realize the justice of many of the points made in the report on education, and so expressed themselves, saying that they welcomed this analysis of their problems. What they did urge, however, was that they might have the help of the members of the profession toward securing constructive reforms, not the least of which would be in the placing of architectural schools in a position where they would be independent of the schools of engineering, which in some cases still controlled their policy. Any tendency that the debate might have had to become acrimonious was prevented by an exceedingly amusing paper read by Mr. Magonigle, in which, among other things he listed the colossal number of subjects in which the architect is supposed to be proficient. On the whole the discussion was very well worth while, and indicated certain constructive lines of study which the Post-War Committee will now follow up.

The evening session of the second day was very well attended, and started off splendidly with the report of Mr. Russell of St. Louis on the recently organized National Board of Jurisdictional Awards of the Building Industry. This Board has been recently created to pass on all questions of trade jurisdiction in the building industries. It owes its existence in a great measure to the efforts of the American Institute of Architects, and indeed it is the first formal and definite act of participation on the part of the architectural profession in questions of adjustment between employers and employees in the building trades. The membership of the board includes representatives of the building trades department of the American Federation of Labor, the Associated General Contractors, the National Association of Builders, Executives of the Engineering Council, and the American Institute of Architects. The organization of the board seemed almost like a direct answer to that question in the Post-War Committee's program, which referred to the need for closer co-operation on the part of architects with the men who execute their work. Nothing was more stirring in Mr. Russell's report than the expression of his conviction borne of experience that the step taken by the architects in this matter was most welcome to the Federation of Labor, and secondly that there already were evidences that all the interests represented in the board would benefit by the co-operation thus established, particularly in the way of enlightenment and understanding.

Under the head of item K of the program, Standardization, Mr. Boyd presented an interesting paper in which he indicated the ways in which certain forms of construction might be standardized along the lines established by various Govern-



## THE AMERICAN ARCHITECT

ment departments during the war. An interesting letter on the same subject, written by Mr. C. B. J. Snyder of New York, in a great part confirmed the position taken by Mr. Boyd.

The major part of the evening was devoted to topics L and M of the program. The former raised the liveliest discussion as to the best and most desirable form of architectural societies. There seemed to be a very general agreement that the proposed action of the convention in encouraging the formation of State Associations had been justified. Illinois gave very interesting reports as to the effectiveness of the State organization—how it supplemented the work of the Chapter and supported it in every way and yet had developed an independent force of its own owing to the co-operation of great numbers of architects throughout the State, who for one reason or another were not directly associated with the Institute. There were interesting reports from Kansas and Pennsylvania, Ohio and New York. Delegates of the two latter States indicated that they are even now taking steps to reorganize their existing State Associations, making them independent of the Institute so as to take in on the basis of comparatively small membership dues all those architects who are qualified to practice, but who by reason of their distance from the principal cities or for financial reasons are not now connected with any architectural society. Ohio was apparently hesitating as to the advisability of this step, but delegates from New York reported that preliminary notices had already been sent out for a meeting to be held in Utica on the 7th day of June to form a new association.

Under the last topic, M, the subject of competitions was very thoroughly debated. Prof. Laird presented an interesting resumé of a statement on the subject which he had prepared for the Philadelphia Chapter. His opinion was on the whole favorable to competitions as being both the best means for selecting an architect and for getting the best architectural result. This stirred up a mighty discussion, some holding that results of competitions were rarely satisfactory either to those who participated or in the design of the structure resulting therefrom, some contending that they were a necessary evil, and others holding that they were an entirely unnecessary evil. There was no doubt that the members agreed that the principle of regulating competitions cannot be questioned; that is to say that competitions if held must conform to the code set by the Institute. One of the most interesting remarks made during the evening was that of Mr. Mauran of St. Louis, who told of a case in which his firm had been invited to compete for an important building and had declined on the ground

that the character of the building was such that a competition could hardly elicit satisfactory results because the problem needed intimate conferences between the owners and architect. In this particular case the owners had abandoned the idea of a competition and had awarded the work to Mr. Mauran's firm, whereupon they prepared quite a number of different schemes for the same building, developing, in other words, a series of sets of competition drawings themselves for their client's consideration. These different sets were then presented one after the other in the order of their development, and each in turn was declared by the client to be acceptable until the last in the order of development was acknowledged to be superior to any of the others. It was evident that in this particular case no competition could have produced a result so directly the effect of the conferences that had preceded the development of the plan.

Those who were most insistent on the value of competitions were perfectly ready to acknowledge that everything lay in the wisdom of the program and the wisdom of the jury, but the critics were quick to point out that if the program were properly written; that is to say that if the professional adviser had really studied the problem so as to include within its fundamental conditions the essentials to a satisfactory solution then the program itself would solve the program. On the whole, delegates from the eastern and central sections of the country were generally of the opinion that competitions are to be discouraged, but that in any case the standards must be maintained, insisting that the programs must be carefully drawn and the jurors carefully selected, while the delegates from the West and the South, with the exception of San Francisco, clung to the competition as their only hope against deplorable public architecture. These parts of the country hold that in the last few years the competition program of the Institute has greatly helped in clearing up the situation with regard to public work, and that for a great many years to come they will wish to continue the valuable educational influence which has come through its enforcement.

Quite aside from the three main sessions of the convention devoted to the Post-War program, the subjects covered by that program were constantly brought up in the course of other debates. While delegates from some of the big cities seemed to think there was nothing very important so far in evidence as the result of the committee's work, delegates from the rest of the country were unquestionably enthusiastic about the possibilities of this Post-War effort. The remark was common that the Institute had really thereby struck its gait and was



making itself of great value to the profession. Everyone wanted to know in what form the result of the investigation would be sent out, and offers of assistance and co-operation were received from innumerable sources.

On the whole the results of the discussions at Nashville were exceedingly helpful, and will un-

doubtedly help spur on the Post-War Committee to carry on its formidable task during the coming year with renewed energy. Its greatest hope must be that it may be able to help in the development of a public opinion within the profession as to the lines along which the practice of architecture ought to grow so as to become efficient in the public service.

## The Registration of Architects

Remarks by D. EVERETT WAID, *Treasurer, American Institute of Architects, before the Nashville Convention*

THIS subject is a matter of present importance for the reason that perhaps a dozen States now have registration bills under consideration, and double that number are likely to pass such laws in the near future. For the good of the public and the credit of the profession, it is the duty of every Institute member to be prepared to oppose every bill drawn on a wrong basis and to be ready to fight for certain fundamentals which, if not provided, would mean the defeat of every State law proposed.

Our chief danger lies in the fact that selfish self-protection is the impelling motive most certain to initiate registration or license laws. Architects chafe when they see incompetent, conscienceless persons design buildings and impose on the public and the qualified practitioner by calling themselves architects and walking away with the commissions.

The first impulse is to say "bar such people by means of a license law." Such a method of meeting competition is a mistake and in the end brings trouble. As members of the American Institute of Architects, we should have the vision to work on a higher plane; we should have the foresight and energy to take the lead and act first, and not wait until we have to correct the missteps of others.

Our primary motive and object should be to make ourselves competent rather than to condemn the incompetence of others. A registration law should be an instrument for educating architects, not for placing a ban on a poor carpenter or an enigneer who wishes to design a building. Druggists or practical nurses may advise a remedy for a cold; but they cannot call themselves doctors without first passing examinations which test their actual qualifications. A real estate man may give a sound opinion on a legal question or conduct his own legal operations, but he has no standing in court until he has acquired certain general and technical education and experience.

A professional man or an artist must excel in his particular line of work and be a real expert as compared with the laity or those in other professions, or he will bring discredit upon himself and the profession of which he pretends to be a qualified member.

Let us impress upon ourselves and every architect the fact that each State in the Union is going to have a registration law. That being the case, whether we feel any personal interest in registration laws or not (at any rate it should be an unselfish interest) let every member of the Institute stand for three things:

*First*—that every architect to win his title should have a general education equal to or a little better than that of the average well educated citizen, plus an adequate technical education.

*Second*—That present practitioners may continue to practice by legal right and that the Board of Examiners shall not be forced to give them certificates of competency unless they prove their qualifications.

*Third*—That all the States shall aim at some uniformity of standards and to that end all prospective legislation be submitted through *The Octagon* to the Institute Committee on Registration.

Since the last convention a new kind of legislation has been evolved. That is joint registration of architects and engineers. Three States have formulated bills of this kind: Ohio, Indiana and Michigan, and others are likely to follow, creating Boards of Examiners and Registration made up of members of both professions. In one State the bill provides for a board of examiners made up of one architect and two engineers. Think of the architectural standards of a State being placed in the hands of one architect, doubtless a political appointee, a mining engineer and an electrical engineer!

The American Institute of Architects has declared in favor of association with engineers on a basis



which will insure friendly co-operation and not competition. But this bill may be regarded as a grave mistake which threatens to place the artistic quality of architects' work, in the eyes of the public, on a lower plane than ever.

The Board of Directors appeals to all Chapters to send a copy of every registration bill to *The Octagon*. Prompt action may prevent ill-considered legislation which would hamper the best efforts of our profession for years to come.

## Notes from London

By SELWYN BRINTON, *Special Correspondent to THE AMERICAN ARCHITECT*

The housing question, to which I have alluded in my previous notes, now seems to be taking a definite shape under the pressure of the Government Housing Bill, whose main provisions I have already detailed. On all sides there are signs of movement. At Roehampton, near London, the Dover House Estate is being acquired at a cost of £20,000; but as this is a very desirable location on the high ground adjoining Putney Park it is suggested that this should not be developed exclusively as a working class estate.

At Brighton it is proposed to erect 800 houses on the Moulscombe Estate, and it has been found that the expenditure as contemplated works out at £900 each, instead of the estimated £700, representing a rental of £1.12.6 per week. As the prospective tenants are not expected to be able to pay more than 12/6 weekly, there will be a balance of £1 to be paid "from some source other than the rental"; and the Brighton Housing Committee assumes that the Government will "contribute an annual sum representing the difference between the rent actually obtainable and the amount of the outgoings, less the proportion of the amount produced by a one penny rate."

Apart from this, as this estate will not be available until after inquiry and arbitration, the Brighton authorities are constructing fifty houses


for the discharged soldiers, who are working at the new diamond cutting industry which has been started in that town; and Professor Adshead, F. R. I. B. A., is now preparing an estate and development plan for this last proposal.

These are only instances of what is going on all over the country. The recent statement of the Local Government Board reported that by the end of March 658 housing schemes had been submitted by 358 local authorities in England and Wales for the Board's approval, most of these schemes being in the initial stage of a site having been submitted for approval.

Housing is certainly a national necessity at this moment; but it is evident that the total expenditure is going to be enormous, and the class which is going to benefit most ought to take its fair share in meeting this. Take the Brighton (Moulscombe Estate) instance above mentioned. It is within the knowledge of the writer that in that district quite good residential

houses could be obtained recently at a rental value of less than £40 a year. The weekly rental of £1.12.6 amounts to about double this, and obviously for the class of houses required is simply preposterous. It amounts to plunder of an already overtaxed community; and not only what are called the professional classes, but the skilled technical workers and managers are rising in protest. At the recent In-

(From *The Builder*)



PROPOSED HALL, BISHOPS STORTFORD COLLEGE

H. C. IBBERTSON, ARCHITECT



## THE AMERICAN ARCHITECT

dustrial Conference a well-dressed man stepped on the platform to propose that "the National Industrial Council take into consideration the position of unions composed exclusively of the technical and administrative grades, and determine how such unions shall be represented." It is significant that in the recent annual meeting of the Association

should be abandoned at the earliest possible moment. "The underlying principle," it was remarked, "that seemed to obtain with the gentleman responsible for creating new ministries, departments and controls, was that of the spendthrift. They had been ready to adopt all sorts of wild and risky experiments; and the last consideration that entered




Fig. 5 A.




Fig. 8 A.




Fig. 6 A.




Fig. 10 A.




Fig. 7 A.




Fig. 11 A

The figure-numbers correspond to the numbers on the Plans on Page 741.

### THE ENGLISH FIVE-ROOM COTTAGE

of Chambers of Commerce at which one hundred Chambers were represented, the London and Luton Chambers joined in a unanimously adopted resolution that the House of Commons should resume control of public expenditure, and that the present unemployment donation, vicious in principle, and which is hindering the resumption of work,

into their heads was where the money was to come from. The unemployment donation scheme had been conceived in a hasty and reckless manner. It was demoralizing and degrading to pay men and women for doing nothing."

I have made it clear in my previous treatment of this subject that my criticism is directed against



(From The Architects and Builders Journal)

# THE FIVE-ROOMED COTTAGE Its planning analysed.

In the details of these typical plans, wherever possible, the Wash-house does not open into the Living Room.  
In order to avoid confusing the plans, cupboards of which there should be one in each bedroom are not shown.  
Floor areas have been calculated inclusive of chimney-breasts.




Fig. 1 Common Victorian Plan.




Fig. 2 Variation, when built in rows.




Fig. 3




Fig. 4 The shallowest convenient proportion.

Fig. 6 Cottages joined together endwise.




Fig. 5 The narrowest convenient proportion.




Fig. 7 Plan with staircase in front.

When built in rows, the wash-house reaches to the Fig. 8 Elongated Variant of the same plan. back and the E.C. is added, as in Figure 5.




Fig. 8 Elongated Variant of the same plan.




Fig. 9 Double-fronted Plan

This plan (Fig. 9) can be used for cottages built in rows, if the windows are re-arranged.

Fig. 10 Cottages joined together sideways. Dimensions as in Fig. 9.



## THE AMERICAN ARCHITECT

the methods, not the principle, of the housing scheme; and it will be of interest now to study the practical question of how—given the site and the difficult problem of funds—the actual house is to be planned.

The discussion which has been raging for months upon this interesting question seems to have centered around two special points. The one is what has been conveniently christened the "parlor question"; the other turns on the no less harassing problem of the worker's—and his family's—personal ablutions.

I myself incline to favor the parlor for two reasons. One is that I have found, among my workmen friends, a strong feeling to have some place set apart to receive the honored guest and to be a shrine for their household gods. That these household gods may take the form of wax flowers, china dogs or other objects not equally admired in the most cultured art circles, does not matter; their value is in the eyes of the possessor—and they are often very dear to him.

Mr. Goodhart Rendel, in his interesting contribution to *The Architect's Journal* on "Planning the Five-Roomed Cottage," has indeed scant mercy for such sentimental considerations, though he admits their existence. "This is not the place," he remarks, "to argue the vexed 'parlor question,' if indeed it be a question at all. From various causes a great many cottages are built—and will be built—without parlors, and it is with the plan of such as these that this article is concerned. . . . Having then reluctantly denied to our tenant a shrine for his domestic gods, we must furnish his actual needs: a room to live in, some sleeping-rooms and a washing place for his crocks and linen. Besides these, he must have a store for food, and a sanitary convenience. The living-room, if it is really to be the place where he lives, should be the cooking-room in winter, but not in summer; the washhouse should contain the stove for summer cooking. Without this provision, in hot weather the family will sit in the washhouse."

As regards aspect, the writer wishes his cottage living-room to face as near southeast as possible, and suggests ventilators, instead of a window, in the larder, if it faces south or west. The aspect of the washhouse is unimportant; that of the larder, and its proximity to the closet, is material, and in his Fig. 1, which is of the type known as the "Common Victorian Plan," we see it separated by the fuel store. We have now arrived at the bath question, which—almost as much as the parlor—has been a source of conflict, the trouble being whether it shall be upstairs, or downstairs in proximity to the washhouse. The English cottager, as

a rule, is stated to have his "tub" before the kitchen fire, when the family have gone to bed, but this does not apply to such work as miners, who must have a bath when they come in dirty, and for whom the best arrangement would be clearly downstairs.

A very real problem—which Mr. Goodhart Rendel scarcely touches—is the question of fuel economy; but he does suggest in this direction that the bath and copper should share a small apartment screened or walled off from the scullery, so that




Fig. 1 A.




Fig. 3 A.




Fig. 4 A.

The figure-numbers correspond to the numbers on the Plans.

### THE ENGLISH FIVE-ROOM COTTAGE




## THE AMERICAN ARCHITECT

the copper can heat the bath water at the same time. His plan will allow of three bedrooms and a fair-sized living-room, without the screened off room which has been elsewhere suggested; in the figures given he refers to the "Common Victorian Plan," shown in 1-5, that of Fig. 7, and still more the double-fronted plan of Fig. 9, which he considers the best, and which he notes can be rearranged for cottages built in a row.

It is interesting to compare this well-thought-out

small." Again, upon the "parlor question," his attitude is, if not hostile, at least unsympathetic. "There are many points both for and against. Beginning with the points against, the first is the great additional cost. Space, material and labor are expended on the parlor, which is often only used on state occasions. . . . This room is frequently shut up for weeks together, and has a characteristic odor about it that suggests intermittent life. It has a coldness as of death. But it

(From *The Architect's Journal*)



1.—PERSPECTIVE VIEW OF THE GRAND COUNCIL CHAMBER IN THE OLD PALACE, FLORENCE

(From an Engraving by Famin and Grandjean)

plan of the five-roomed cottage with Mr. C. F. A. Voysey's interesting article in *The Builder* of April 18 upon "The Artisan's Cottage." Upon two of the points which we have just noted his view is entirely different. "Every house," says Mr. Voysey, "should have its copper; but the idea of giving every artisan a fixed bath is extravagant, unnecessary, and often futile. He does not want to wash all over every day, so the labor of carrying up a can of hot water to a hip bath is comparatively


feeds the vanity of the tenant, and his head swells at the thought of his parlor gentility." But the writer admits that it often comes in very opportunely for the lodger, who is a most important factor in British lower-class life, and that even apart from its advantages as "a museum of photographs and wax flowers and a meeting-place for social affairs" it may be utilized for dressmaking or study, which must be all but hopeless in a living-room filled with clamorous children.



# THE AMERICAN ARCHITECT



DETAIL OF ONE OF THE SIDE ALTARS OF THE  
CHURCH OF SAN JUAN DE DUERO, VALLADO-  
LID, SPAIN



SANTA MARIA LA ANTIGUA, VALLADOLID,  
SPAIN

*(From The Architect)*



SECRETARIAT BUILDINGS, DELHI  
North and south side entrances, and detail of gateways to the side entrances.  
HERBERT BAKER, F.R.I.B.A., ARCHITECT




## THE AMERICAN ARCHITECT

I leave now the homelier theme of English cottage accommodation to turn to Imperial Delhi, that ancient capital of India, which is now being replaced in its high estate, which it possessed as early as 1193, when it became the capital of the Mahomedan Indian Empire, and was restored to that position under the Moghul Empire between 1638-58.

and Sir Edwin Lutyens, whom I met at Rome in 1911, is a designer of great imaginative grasp.

There has been a strong feeling in England, as well as India, that these designs should appropriately follow the characteristic lines of Indian architecture; and it will be seen that this feeling has not been overlooked in the proposed Government buildings.



SECRETARIAT BUILDINGS, DELHI. HERBERT BAKER, F.R.I.B.A., ARCHITECT

In a recent number of *The Architect*, which commemorates—from March 27, 1869—fifty years of that journal's successful career, the plans proposed by Sir Edwin Lutyens, A. R. A., and Mr. Herbert Baker, F. R. I. B. A., as principal architects and architectural advisers to the Government of India, are shown in an admirable set of illustrations. Mr. Baker is well known for his Government buildings at Pretoria and his monument to Cecil Rhodes;

Government House itself consists of a central block—about 255 ft. by 300 ft.—connected to two western and two eastern wings, beneath which are triple carriage ways. The principal approach from the east is by a great columned portico, 120 ft. wide, with steps broken by landings leading up to the principal floor; and the central feature is the great circular Durbar Hall, some 70 ft. in diameter, whose dome forms a center to the whole




## THE AMERICAN ARCHITECT

group. The Secretariat buildings form two H-shaped blocks, with wings at right angles to the sides of the H, facing each other and divided by the Processional Way; and it is satisfactory to note that much of the detail will lend itself to the wonderful inherited craftsmanship of the Indian de-

sign in much the same way that the administrators of India have bridged the gap between Eastern and Western ideals, in the effort to promote the happiness and prosperity of a vast area, which has been through centuries a battleground of conflicting races and creeds."

(From *The Architect*)



ANTWERP BRANCH, LONDON COUNTY, WESTMINSTER & PARIS BANK

MEWES & DAVIS, ARCHITECTS

signer. It has been remarked that a difficult problem—to design a building on general classical lines which would at the same time express the spirit of Indian design—has been successfully solved. "What Sir Edwin Lutyens has done is to bridge successfully the gap between Eastern and Western

A strong appeal has been made by Sir Sidney Colvin for public support to the acquisition by the Board of Education of the fine collection of casts and moulds, from Messrs. Brucciani, the well-known London "formatori," who are now in difficulties owing to war conditions. If this collection




## THE AMERICAN ARCHITECT

is acquired it will be used for purposes of art education by the Board, with the assistance of the Victoria and Albert Museum; and Sir Sidney says very truly that "It is well known that the provision of facsimile reproductions of sculpture and architectural detail is a prime necessity for practical teaching in art schools and historical and comparative study in museums of art," adding that "this necessity has never yet received from our Government the consideration which it urgently demands."

chosen. "La Antigua"—or to give its full title, "Santa Maria la Antigua"—at Valladolid, is one of the most ancient churches in Spain, and Mr. Street gives three pages to its beauties, describing in detail its finely groined interior. The "fine Western steeple," to which he also alludes, was, I regret to say the only part of the grand old building still upright when I recently visited Valladolid; and the work of "restoration" which was going forward alarmed me and was enough to make the author of

(From *The Architect's Journal*)



STREET DECORATIONS FOR PEACE: A FRENCH EXAMPLE OF THE EMPIRE PERIOD

I felt this very strongly when recently in Spain I came upon the admirable "Museo de Reproducciones Artísticas." Such a museum is, in fact, of priceless value both for the student of architecture and of sculpture. If it were to be undertaken in America it would surely be very efficiently carried through; and I hope to return to this again in a later letter.

Spain is indeed a country of surprises; she is often as astonishingly modern as she is overwhelmingly antiquated! No color magazine, for instance, in Europe in general quality can compare with *La Esfera*, and its architectural reproductions—from which I give two—are always extremely well

"Gothic Architecture" to turn in his grave. Soria I have not yet visited, though I had great accounts in Spain of its wonderful remains. The Church of San Juan de Duero, which was formerly a convent of the Templars, is without the city and picturesquely situated; the character of its architecture is Romanesque.

With peace in prospect the subject of war decorations is occupying the public mind; and it is interesting to note what has been recently achieved in this way by Messrs. Selfridge in Oxford Street and what was done in the old days of the Napoleonic Empire.

The Royal Academy is now taking the question




## THE AMERICAN ARCHITECT

of war memorials in hand, and is organizing two exhibitions, the first to be held at the Victoria and Albert Museum in June next, and to comprise selected examples of memorials executed in past and recent times by deceased and living artists. The second section will be held at the Royal Acad-

emy in October, and will consist of new designs for war memorials in any class of art or craft, with a view to the circumstances of the present war.

The 151st Exhibition of the Royal Academy promises, under present conditions, to be one of exceptional interest.

*(From The Architect's Journal)*



THE TAYLORIAN BUILDING AT OXFORD. C. R. COCKERELL, ARCHITECT

*From the drawing by Hanslip Fletcher*



## THE AMERICAN ARCHITECT

### THE AMERICAN ARCHITECT

Founded 1876

PUBLISHED EVERY WEDNESDAY BY

THE ARCHITECTURAL AND BUILDING  
PRESS, INC.

No. 243 West Thirty-ninth Street, New York

E. J. ROSENCRANS, PRESIDENT AND TREASURER

WILLARD C. HOWE, VICE-PRESIDENT

WILLIAM H. CROCKER, Editor

EDWARD F. HAMMEL, Engineering Editor

ARTHUR T. NORTH, Western Editor

Subscriptions in the United States and Possessions,  
Mexico and Cuba, TEN DOLLARS. Other Countries,

TWELVE DOLLARS.

SINGLE COPIES (Regular Issue) 25 CENTS

CHICAGO OFFICE, Mallery Building

PAGE A. ROBINSON, Western Manager

ST. LOUIS OFFICE, Wright Building

CLEVELAND OFFICE, Guardian Building

SAN FRANCISCO OFFICE, 320 Market Street

Owned by United Publishers Corporation—H. M. Swetland, President;  
Charles G. Phillips, Vice-President; W. H. Taylor, Treasurer;  
A. C. Pearson, Secretary. Entered as second-class matter January  
6, 1909, at the Post Office at New York, New York, under the Act of  
March 3, 1879.

VOL. CXV

MAY 28, 1919

No. 2266

### Mr. Kohn's Review

THE lucid review of the sessions of the Post-War Committee on Architectural Practice during the recent convention of the Institute at Nashville, prepared by Robert D. Kohn, a member of the committee, and presented in this issue, will repay very thoughtful reading.

The responses, numbering into thousands, received by the committee indicate how widespread is the interest in its work and prove conclusively that this interest is not confined to Institute membership, but that a very large share of these replies were from men who are not affiliated. This indicates the representative character of the committee and should insure the widest measure of support by architects everywhere in this country as well as by the many men whose work brings them closely in touch with the architectural profession.

Probably no movement thus far set afoot in the profession of architecture offers possibilities for so large a measure of fruitful accomplishment. In it there are to be found the elements of all of the possibilities for expansion of the service that architects may properly render—"the self-education that comes through participation as a citizen in public work and the methods by which architects can make

their importance in relation to the problems of building more quickly felt."

THE time has now arrived when the profession of architecture must unite in an effort for the stabilization of all the elements that affect the profession. Prejudices, small jealousies, narrow-minded points of view should all be brushed aside and the upbuilding process swiftly advanced by a strong and unanimous effort.

Whatever shortcomings there may have been attributed to the Institute, it is quite clear that the organization is now pledged to a policy that should enlist the warmest co-operation. The very favorable attitude of the convention toward the matter of State architectural associations indicates the democratic and constructive spirit that now rules. These organizations while at present limited to comparatively few States, are to be encouraged as a means of securing the affiliation of those architects who are qualified to practice, but who by reason of their distance from large cities are not now a part of the organized profession.

It is a source of satisfaction to learn that the development of State societies is so favorably regarded, and it is to be urged that no time be lost in the matter. There are wide fields of endeavor for both the Institute and State Societies, and their harmonious working toward the common good would accomplish many desirable ends.

IN no topic discussed during the committee's sessions was there a more widespread representation or a more unanimous opinion than in that of architectural education. Much good will come of the efforts that are now being put forward to place on a more practical basis the curriculum of our architectural schools. This effort will be, if carried forward under the control of the profession, one for more far-reaching good than any of the many that are now under consideration.

The period of architectural construction in its most practical form has now begun. To let it lag for want of a strong and concerted effort would be an unfortunate thing. We shall need, in order to push to completion the essentials of this Post-War Program, all of the effort of the Institute, of every State Society, of all the architectural clubs, and also every man who has the good of his profession at heart, whether he belongs to one of these organizations or not. And, if he does not, he certainly should, for it is a most selfish attitude supinely to await the efforts of others in these great problems of reconstruction. They are not for the benefit of just those who most strenuously promote them but for architects everywhere.



## What An "Open" Market Means to Building

**N**OW that there are to be no further attempts to stabilize commodity prices—the result of the conference recently held in New York City between the Industries Board and the steel industry which forced an "open" market having created an unmistakably better feeling—it is to be hoped that the Government's tinkering with business is at an end and that the progress of construction will be allowed to resume its normal cadence.

Just how firmly the restriction has been while the Industries Board and Railroad Administration were at deadlock is shown in practically every large municipality where all but the more daring speculators and those soundly financially backed were hesitant about proceeding with building projects. The Government's apparent disregard of the fundamental principles of economics in strangling the always present law of supply and demand and the substitution of a price fixing policy, did more than any other one thing to retard the needed impetus that should long ago have been given post-war construction.

Not until the Railroad Administration refused to order steel rails at the price fixed by the Industries Board was an effort made to put an end to such ill-advised procedure. The Railroad Administration's attitude in the matter has not received proper recognition, due possibly to the fact that its reasons for taking the stand it did were not made public. Industry consequently has just had to surmise that it was done to prevent possible violation of the Sherman Act.

In explanation of the retirement of the Industries Board it was stated that the board had for its object the resumption of construction and production through the stabilization of prices. The legal phases of the question as raised by the Attorney General's comment on the legality of price fixing failed to disturb the opinions of the Secretary of Commerce who referred to the opinion of the Attorney General as negligible. It was contended the results sought could have been obtained without violation of the Sherman act, as the plan was to ascertain and make public fair prices reached by agreement.

Subsequently another effort was made to fix the price of steel, but when the leading corporations proved to the Industries Board that no further reduction could be made without a reduction of wages, they won their fight for an "open" market. But in the meantime it has been business that has been held up, as usual.

In the past it has been very clearly demonstrated that American business men can always find a way to solve problems that may confront them no matter how difficult they may appear. There is no reason to believe that they could not have worked out the solution of reconstruction period business difficulties had they been given a free hand and assurance that there would have been no crossfire interference by Governmental departments. Recently the Administration has been getting a dose of its own medicine, but, of course, at the expense of business.

No better illustration of the futility of the Administration's efforts to tinker with business can be had than the recent Navy Department experience. Over a month ago the Navy Department requested bids on 20,000 tons of steel, and on opening the orders found that each of the fourteen companies had submitted the price fixed by the Industrial Board. Naturally, the bids were rejected as being non-competitive. Last week, on opening bids on another lot of plates, the same situation was found to exist. The bidders either referred the Navy Department to their bids of early April, or put in new offers amounting to practically the same thing.

As far as the Navy Department is concerned, action has been taken under authority conferred by war emergency legislation by placing an order, or what amounts to a requisition, for 14,000 tons of steel with the Carnegie Steel Company. Decision to requisition the steel was the result of a conference on how to meet the situation when it was found that the bids submitted were the same as the bids previously submitted, and which were based on prices agreed upon between the steel manufacturers and the now abandoned Industrial Board, which were rejected on the ground that they showed no indication of competition.

The present order, according to an announcement made by Acting Secretary of the Navy Roosevelt, was placed "at a tentative price subject to later adjustment," and that only one company bid on the entire order. Whether the steel company will get a higher price than that fixed by the Industrial Board, or whether, on account of the fact that it is put through as a war emergency requisition the price paid will be lower, remains to be seen. The price tendency so far seems to be upward.

The freeing of the price situation from Governmental muddling by the dissolution of the Industrial Board and the resultant "open" market for building materials has already brought about an unmistakably better feeling in the construction industry.



# Training School and Home for Young Girls, Brooklyn, N. Y.

LUDLOW & PEABODY, *Architects*


(For interior views and floor plans, see plate section)

THE problem of what to do with young girls who have come into the courts for petty crimes and immoral conduct is a difficult one. In order to meet this to some extent the Brooklyn Training School and Home for Young Girls was established to take care of such cases, so that instead

The Brooklyn Training School, as the secondary title indicates, has for its keynote the feeling of "home." These young girls, from the age of 12 to 18, are taken care of and educated by women of fine character and ability, and the strict discipline to be administered is not that of the jail.

The problem of the housing of such girls, therefore, is to provide practically a prison that is, in aspect and administration, a home. Iron bars and show of locks are, therefore, tabooed. Freedom from institutional lines and the use of color are essential.

The group consists of three buildings, two of which have already been constructed, and are shown by the accompanying photographs. One of these is a school building, which provides two large class rooms and an instructional laundry, the latter being used by the girls to do the work of the institution. The other building now constructed houses the head matron, a number of girls in small private rooms, and a little suite of dining room, living room, bedroom and bathroom, which is a typical apartment such as the girls may be called upon to take care of in their home life. Two or three at a time live in this apartment for a short period and are instructed in its care.



of the old-time method of sending these girls to the workhouse or jail they can be cared for in a manner that looks to constructive redemption rather than a period of incarceration which often confirms the culprit in her evil tendencies. Therefore, it is the practice now for certain of the judges of Brooklyn to send to the Brooklyn Training School such cases of this kind as come before their courts.

The large building which is to be erected later, to take the place of an old wooden structure which is now being used in its stead, will accommodate about fifty girls in private rooms, sleeping porch, detention ward, etc. It also houses the general dining room, recreation room, play room, solarium, and officers' room.

It is customary, on receiving new inmates, to



place them for two or three weeks in an entirely separate suite, called the "detention ward," where they are under surveillance during examination and a period of probation. In a little tower room in the fourth story, reached by a winding stairs, is a solitary room called the "thinking room," and is to this institution what the dungeon is to Sing Sing Prison; the difference is that this room is anything but a dungeon, the theory being that a flood of sunshine is better than darkness for the correction process.

These three buildings are connected by covered arcades so that access from one to the other is made convenient. They have red tile Spanish roofs and light buff pink stucco walls, with faded green windows and doors.

The court formed by the three buildings will be treated in simple garden fashion, so that the Italian effect of the whole group may be maintained.

To prevent the escape of the inmates, continual care is required, which is made easier by the ornamental grilles in the windows, which prevents a clear opening above or below either sash of more than 9 in. In addition to this, the annunciator in the officer's room on each floor connects with the door of each bedroom.

## Construction Field In South America

The requirements for construction materials in Chile, Peru and Ecuador are set forth in detail in a book of 200 pages just published by the Bureau of Foreign and Domestic Commerce, Department of Commerce. It appears that there is much construction and building work going on in Chile, where the Public Works Department has considerable work in hand. During 1917, thirty-five projects with a cost of over a million dollars were finished.

The author of the reports states that American manufactures are generally as good as those of Europe, and in some cases better. Some of the articles of American make that enjoy a preference in Chile are door locks, padlocks, hinges, iron and wire nails, tacks, lumber for construction and cabinet work, turpentine, varnishes, enamels and many other articles that are not imported in large quantities. The Chilean public is generally favorably impressed with American goods and considers them more up to date than the European articles.

During the past decade sanitation in Chile has made great progress. It is estimated that 15,000 fixtures, including enameled and porcelain bathtubs, water closets and lavatories are imported annually. There is also a steady demand for heating installations, hot water being the system most favored.

The time is ripe in Peru for the sale of construction materials, and there are possibilities of making some good contracts. The country has entered upon a period of prosperity. The government is progressive. The war has enriched the Peruvians who, a little uncertain how to invest their gains, are in many instances buying up lands and old houses and are preparing to rebuild with modern structures possessing all sanitary conveniences.

The financial condition of the Peruvian Government has been greatly improved, the income having increased more than 30 per cent, the result being that work has been commenced on several new public buildings, and will soon follow on others.

Impetus is being added to this activity by the fact that on July 28, 1921, the centennial of the independence of Peru will be celebrated, and it is proposed to have finished by that time the Judicial Palace, the Legislative Palace, the Archbishop's Palace, the model jail, the Prefecture, an orphan asylum and a hospital for women.

Some of the products that may be readily sold in Peru are yellow pine and Douglas fir, which will find a market in Peru so long as the native forests of the country remain undeveloped. The United States furnished the largest share of structural steel and Portland cement. In 1916 we furnished 89 per cent of the weight and 90 per cent of the value of window glass. England and Germany have led in supplying paints and paint materials. Paint materials coming from the United States have generally been higher in price than those from abroad.

## Demand For American Building Specialties

It is learned from a letter received by a prominent manufacturer in this country, from the American Commercial Attaché at Copenhagen, Denmark, that in the opinion of Professor Kampmann, a leading architect, there is a very large demand in Denmark for a number of modern American specialties.

Professor Kampmann is further of the opinion that it would be to the interest of American manufacturers to popularize their product in Denmark and has asked that samples, specifications and catalogs be forwarded to him. Professor Kampmann's address is Harsdorffsvej 3, Copenhagen, Denmark. For a wider distribution of commercial literature or advertising material it is suggested that the three most important architectural organizations in Copenhagen be addressed. These are: Akademisk Arkitektforening, Stormgade 12; Dansk Arkitektforening, Gyldenevesgade 3; Fri Arkitektforening, Strandgade 26; Copenhagen.



# Beaux-Arts Institute of Design

DIRECTOR OF THE INSTITUTE, LLOYD WARREN

ARCHITECTURE, WILLIAM F. LAMB

SCULPTURE, JOHN GREGORY

INTERIOR DECORATION AND INDUSTRIAL ART DESIGN, ERNEST F. TYLER

MURAL PAINTING, ARTHUR CRISP

## Official Notification of Awards— Judgment of March 4, 1919

### THE PUPIN PRIZE

The Gift of Prof. M. I. Pupin of Columbia  
University

Offered for the Ornamental Treatment of Some  
Scientific Appliance

FIRST PRIZE—\$50. SECOND PRIZE—\$25.

For conditions governing this Prize Competition,  
see Circular of Information, Article VIII—1 and 3.

### PROGRAM


The Committee on Architecture proposes as sub-  
ject of this Competition:

#### "A CAR FOR A FUNICULAR RAILROAD"

A funicular railroad is supposed to make an  
ascent 3000 feet, at an average grade of 30 degrees  
from the horizontal, to the top of a mountain. On  
account of the length of time necessary for the  
trip, and the views along the route, the car shall



PLACED FIRST, D. M. ALLISON, UNIV. OF ILLINOIS.  
PUPIN PRIZE  
A CAR FOR A FUNICULAR RAILWAY



PLACED SECOND, A. C. RUNZLER, UNIV. OF PENNA.  
PUPIN PRIZE  
A CAR FOR A FUNICULAR RAILWAY



be so designed as to be especially suitable for observation, but shall be comfortable, while providing place for as many people as possible. The arrangement shall be such that the platforms and seats will be level. The car shall be simple in design, but shall not lack a decorative appearance. In other respects the design is optional.

The car shall not exceed 20 feet in length by 6 feet in width, and shall be provided with a roof as a protection against the sun and rain.

**JURY OF AWARD:** F. A. Godley, T. Hastings, J. O. Post, F. H. Bosworth, Jr., R. H. Dana, Jr., R. M. Hood, W. S. Wagner, M. J. Schiavoni and L. Ayers.

Number of drawings submitted—33.

## AWARDS:

Placed First (Not qualified for Prize)—D. M. Allison, Univ. of Illinois, Urbana.

Placed Second—\$25—A. C. Runzler, Univ. of Pennsylvania, Phila.

Placed Third—E. Hayward, "T" Square Club, Phila.

Placed Fourth—S. M. Jokel, J. Huntington, Poly. Inst., Cleveland.

Placed Fifth—J. K. Smith, Univ. of Pennsylvania, Phila.

## Official Notification of Awards— Judgment of April 15, 1919

### Second Preliminary Competition for the Twelfth Paris Prize of the So- ciety of Beaux-Arts Architects

*For illustrative prize winning designs, see plate form.*

## PROGRAM

The Committee on Architecture proposes as subject of this Competition:

### "A TERMINAL RAILROAD STATION"

The station that is the subject of this problem, is supposed to be the terminal of one of our principal railroad lines in a large city. A level site, 600 feet square, bounded on one side by a broad avenue, on the two adjacent sides by important streets, and on the remaining side by the railroad

yard, is to be devoted to this purpose. The tracks, of which there are thirty, are approximately on the same level as the streets. The platforms for the arrival and departure of trains may be beyond the limits of the site described above, or included in it, at the student's option. There shall be ample provision on the site itself, however, either in the form of courts, or as may be otherwise arranged, for the arrival and departure of municipal street car lines, omnibus lines, and cabs.

The principal requirements of the station itself may be arranged in a single structure, or in several, as desired, and shall be as follows:

Concourses, ticket booths, baggage facilities (incoming and outgoing), parcel rooms, transfer companies, men's and women's waiting rooms with accessories, telegraph, telephones, a post office substation, information bureaus, lunch rooms and restaurants, newspaper and cigar stands, and the railroad executive offices.

All the above requirements should preferably be on one main level save the railroad executive offices, which may be on upper floors and need not be shown, although access to them must be indicated. If, however, any of the main requirements should be placed on different levels, their locations and dispositions shall be plainly indicated on the drawings called for.

**JURY OF AWARD:** R. H. Dana, Jr., W. Emerson, J. O. Post, R. M. Hood, L. F. Peck, H. Hornbostel, F. H. Bosworth, Jr., and L. Ayers.  
Number of drawings submitted—15.

## AWARDS:

Placed First and 2nd Medal—L. Fentnor, Atelier Wynkoop, N. Y. C.

Placed Second and 2nd Medal—F. M. Hodgdon, Atelier Rebori, Chicago.

Placed Third and 2nd Medal—E. E. Weihe, Atelier A. Brown, Jr., S. F. A. C., San Francisco.

Placed Fourth and 2nd Medal—D. McLachlan, Jr., Harvard Univ., Cambridge.

Placed Fifth and 2nd Medal—A. C. Bieber, Univ. of Pennsylvania, Phila.

Placed Sixth (1st Alternate) and 3rd Medal—R. H. Segal, Patrons G. & E. Blum, N. Y. C.

Placed Seventh (2nd Alternate) and 3rd Medal—W. F. McCaughey, Univ. of Illinois, Urbana.

**MENTION:**—R. W. Cheesman, Cor. H. I. Schenck, Dayton; W. H. Livingston and G. A. Anderson, Univ. of Pennsylvania, Phila.





PLATE 171

TRAINING SCHOOL AND HOME FOR YOUNG GIRLS, BROOKLYN, N. Y.

LUDLOW & PEABODY, ARCHITECTS










PLATE 172

TRAINING SCHOOL AND HOME FOR YOUNG GIRLS, BROOKLYN, N. Y.

LUDLOW & PEABODY, ARCHITECTS










PLATE 173

TRAINING SCHOOL AND HOME FOR YOUNG GIRLS, BROOKLYN, N. Y.

LUDLOW & PEABODY, ARCHITECTS












PLATE 174

GARAGE FOR EDWARD C. SCHAEFER, PREMIUM POINT, N. Y.  
REILEY & STEINBACK, ARCHITECTS









DETAILS AND PLANS

GARAGE FOR  
EDWARD C. SCHAEFER  
PREMIUM POINT, N. Y.

REILEY & STEINBACK,  
ARCHITECTS











PLATE 176

PLACED FIRST, SECOND MEDAL—L. FENTON, ATELIER WYNKOOP

A TERMINAL RAILROAD STATION

SECOND PRELIMINARY COMPETITION FOR THE TWELFTH PARIS PRIZE

STUDENT WORK—BEAUX ARTS INSTITUTE OF DESIGN



PLACED SECOND, SECOND MEDAL—F. M. HODGDON—ATELIER REBORI











PLATE 177

PLACED THIRD, SECOND MEDAL

E. E. WIEHE, ATELIER A. BROWN, JR., S.F.A.C.



PLACED FOURTH, SECOND MEDAL

D. McLACHLAN, JR., HARVARD UNIVERSITY

A TERMINAL RAILROAD STATION


SECOND PRELIMINARY COMPETITION FOR THE TWELFTH PARIS PRIZE

STUDENT WORK—BEAUX ARTS INSTITUTE OF DESIGN











PLACED FIFTH  
A. C. BIEBER, UNIV. OF PA.



PLACED SIXTH  
R. H. SEGAL, PATRONS G. & E. BLUM



A TERMINAL RAILROAD STATION

PLACED SEVENTH  
W. F. McCAUGHEY, UNIV. OF ILLINOIS

A TERMINAL RAILWAY STATION

SECOND PRELIMINARY COMPETITION FOR  
THE TWELFTH PARIS PRIZE

STUDENT WORK  
BEAUX ARTS INSTITUTE OF DESIGN







# Recent Legal Decisions

## DIFFERENCE IN MECHANICS' LIENS UNDER DIFFERENT STATUTES

In New York and other jurisdictions which follow what is sometimes called the "New York System," no one except the principal contractor acquires an absolute lien on the real estate upon which the improvement is made, and the rights of the subcontractor, laborer, and material-man are acquired by a kind of equitable subrogation secured by written or record notice to the owner of their unpaid claims, and the lien thus acquired imposes upon the owner the duty of retaining such funds as are in his hands belonging to the contractor at the time of such notice. In such jurisdictions the subcontractor, laborer, and material-man are limited in their recovery to the amount due from the owner to the contractor.

Other jurisdictions, however, like Indiana, have adopted what is known as the "Pennsylvania System," where the statute gives to the subcontractor, laborer and material-man an absolute lien for the material or labor furnished, in accordance with the provisions of the act and asserted and created in the manner provided therein, and a lien so acquired is not affected by the mere failure of the principal contractor to perform his contract or by the cancellation or rescission thereof, or by the removal of the work or payment of the principal contractor. But where, in a mechanics' lien suit, it is alleged by the defendant that the subcontractor was a partner of the principal contractor and had guaranteed that the improvement constructed would do the work required, it is a defense that the material furnished by the plaintiff had been removed as not complying with the guaranty.—*Coonse & Caylor Ice Co. v. Howe Stove Co. (Ind.)*, 121 N. E. 293.

## GENERAL CONTRACTOR'S RIGHT OF SUPERVISION

It is settled law that the general contractor has the right of general supervision in so far as it is necessary to insure full and proper performance by the subcontractors, and that it is only when he goes beyond the limits of that right and commits some affirmative act of negligence, as by taking some part in the performance of the work other than such general supervision as is necessary to insure its performance that he is chargeable. It may be difficult to say just what intrusion or participation in the work by a general contractor is enough to make him liable for its negligent performance, and it

would be unwise to attempt to lay down any precise rules upon the subject; but it is safe to say that the general contractor is not expected to be a mere interested onlooker, without the ability to complain and criticize, and thus indirectly to suggest; for if that were to be the measure of it, the so-called right of supervision would be a vain and empty thing. The New York Appellate Division holds that the fact that a general contractor took upon himself to have men bail water out of an excavation did not show such control of the construction of a building as to render him liable for negligence of the servants of a subcontractor working on stories above, resulting in injury to the roof of an adjoining building.—*Jacoby v. Browning*, 173 N. Y. Supp. 7.

## CONSTRUCTION OF CONTRACT FOR ARCHITECT'S SERVICES

In an action for a fee for designing and supervising the partial construction of a house on the defendant's land, two causes of action were set forth, one on written contract and the other on quantum meruit. Under the contract the architect agreed to render architectural services in connection with the building for a specified commission, and to arrange with the contractor to carry the work of construction forward to the point of completing the wooden frame and covering it with the rough boarding and outside trimmings before demanding any payment on account of his (the contractor's) contract. The architect further agreed to make no demand for payment on account of his own services until the owner had succeeded in negotiating a loan. The architect thereafter arranged with a contractor as agreed, furnished the necessary sketches, detail drawings, plans, etc., necessary for the construction of the house, and the owner then abandoned the work. The trial court found that the owner was liable for the architect's fee under a written contract; that the full fee would have been \$3,028, and that he had earned three-fifths of such sum, payable in case of abandonment, or \$1,816.80. This was affirmed on appeal, the California Supreme Court holding that the owner could not defeat recovery by abandoning the contract for failing to obtain a loan, for if the owner did not negotiate a loan the indebtedness became payable within a reasonable time.—*Rosenheim v. Howze (Cal.)*, 176 Pac. 456.





LOOKING NORTH ON PARK AVENUE

## The Park Avenue Improvement in New York

**A**FTER fifty years of patchwork improvement, including the opening, closing and relocation of various streets, the avenue which is known as Fourth Avenue below Thirty-fourth Street and Park Avenue above, in New York City, has been completed as an uninterrupted thoroughfare at a direct cost of \$1,220,000 to the city, \$1,131,150 to the New York Central Railroad Company, and \$150,000 to the New York Railways system.

The steel viaduct at Pershing Square, extending from Fortieth to Forty-second Street, is in some respects the most noteworthy portion of the improvement. It involved the setting up of six steel girders, each weighing from sixty to seventy-five tons, which act as the main supports of a high-level roadway beginning from the center of Park Avenue at Fortieth Street and terminating at the hitherto unused thoroughfare surrounding the Grand Central Terminal Building.

The width of this roadway, which is to be used entirely for passenger vehicles, is 36 feet. It connects at Fortieth Street with two vehicle levels 35 feet in width that are separated by a parked space in the center of the avenue immediately over the surface car tunnel. The width of the elevated stretch on the south side of the Grand Central Terminal Building is 45 feet.

This leads to a high-level street on the west side of the Terminal Building that is 35 feet in width and is really an upper story of Vanderbilt Avenue. On the east side of the Terminal there is also a high-level section varying from 40 to 60 feet in width, but for the present the public is excluded from this thoroughfare because it is legally a private right of way as a result of negotiations between the city and New York Central officials following a special act of legislature, passed in 1903, which provided for the closing of some streets in the terminal zone, and the relocation of others.






LOOKING NORTH ON PARK AVENUE FROM FORTIETH STREET

The other feature of the new thoroughfare is a ramp at Thirty-fourth Street, doing away with the stone wall and the long flight of stairs at this point. Before the construction of the ramp from Thirty-second Street to Thirty-fourth Street, pedestrians were forced to climb a long flight of stairs to get from the Thirty-fourth Street store district and the

cross town car lines. In place of the wall there is now a vehicular roadway 25 feet in width and a sidewalk for pedestrians 15 feet wide that connects lower Fourth Avenue, with the continuation of the street above, and with Thirty-fourth Street, and the connection is made at the grade.

The ramp has a grade of 3.6 per cent and inci-



LOOKING NORTH ON PARK AVENUE FROM THIRTY-THIRD STREET



dentally provides for opening Thirty-third Street at grade as a through thoroughfare by the elimination of the barrier that has existed for fifty years in the shape of a retaining wall that marked the beginning of the former tunnel at this point. To bring about the opening of Thirty-third Street across Fourth Avenue it was necessary to raise the grade of both the avenue and the street at that point about 6½ feet. This has resulted in increasing the grade of the tunnel cut for Fourth Avenue surface cars at the point between Thirty-third and

Thirty-fourth Streets to about 7 per cent. In the reconstruction work the west section of Fourth Avenue has been widened 3 feet, making the vehicle surface width for southbound 34 feet, so that where in the past there has been but 31 feet for vehicles moving in both directions, there is now a clear width of 24 feet for northbound vehicles and 34 feet for southbound traffic.

The new thoroughfare, it is estimated, will lessen traffic congestion 50 per cent on both Fifth Avenue and Madison Avenue.

## Current News

### Farms and Soldiers Again

In conference the other day with Secretary Lane of the Interior, both the republican and democratic leaders agreed to support a bill to provide land settlements for soldiers and sailors who served in the war. There is everything to commend this. So much is to be said in favor of helping the veterans to jobs, land and a home, that the question resolves itself into only how best this may be accomplished.

The whole country would reap the benefits from a plan which would make two blades of grass grow where but one grew before. The *New York Times* summarizes this by saying that there are millions of acres of arid land which can and should be irrigated for production, other millions of acres of swamp land that should be reclaimed for the same purpose, and still other millions of acres of cut-off land that should be cleared and plowed for sowing. Some of the land, if Secretary Lane is heeded, could be used for stock-raising. His plan is to put soldiers and sailors to work at current wages on a great reclamation scheme, and afterward sell them farms and implements to be paid for in installments.

In his last annual report, Secretary Lane, referring to this subject, pointed out that farms for returning veterans would solve many present difficulties.

During the period of reclamation the soldiers would have a job; the industrial labor market would be protected from oversupply; a large part of the best citizenship of the country would become attached to the soil; and great areas of land of no present value would be made productive for the benefit of all the people.

"Would it be unreasonable," said Secretary Lane, "to ask that we spend in the next two years on these veterans of the great war as much as it cost us to conduct that war for a single week? There is only one answer, and all will agree that there can be no surer insurance for the nation than to put its men upon the soil."

Community settlements on the order of farm villages are a feature of the Secretary's plan, for he realizes that without a social element to relieve the monotony of existence on the lands redeemed from wildernesses his plan would not be practicable. He has no intention of risking failure; therefore he would keep the soldier and sailor on the land in touch with society and its educational and recreational opportunities. "Canada," he says, "with less than 7,000,000 people is offering to each man 130

acres of land and \$2,500 with which to improve it. Surely the United States, which has escaped with so slight a comparative loss in life, would do no less."

At the meeting referred to, Representative Mondell, Republican floor leader, announced that he would soon introduce a bill appropriating \$500,000,000 to provide farms for soldiers and sailors, to be paid for by them in a period of years. Senator Smoot is to look after the bill in the Senate. As a beginning this will be promising, but it is of the first importance that the measure should become a law without the usual delays that attend social and economic legislation.

Returning soldiers and sailors cannot live long on prospects. Active interest must be shown in the plan proposed for their welfare, or it can get no further than the stage of discussion. If this happens, an opportunity valuable all around, will have been lost.

### Works of Art Lost to Russia

From Stockholm comes the news that seven hundred and fifty million dollars worth of Russian art treasures are in danger, and that if the Allies or Providence do not intervene, they will eventually be lost. The estimate of their value comes from Prince D. Golitzyn, an expert, who counts merely the contents of the Petrograd Hermitage and Museum of Alexander III; and of the Moscow Tretyakoff Gallery and the Historical and Rumantsieff Museums. Golitzyn takes no account of the uncounted millions worth of pictures, statues and books in the palaces of the Grand Dukes, and the great private families, the Yousouffs, Scheremetieffs and Stroganoffs.

An official "robbery museum," it is stated, has been created by the Bolsheviks in Petrograd, for loot.

The danger, he says, is not in Bolshevism itself. The responsible Bolsheviks though they rob art wholesale, destroy it only when it glorifies the Romanoffs or monarchism. The danger comes partly from the hungry mobs and the disorderly Red Guards; but most of all from the growing faction of anarchists, who have written on their banner that art is a luxury of capitalists; and that the best way to prevent capitalism reappearing is to destroy all the pictures, statues and imposing buildings, and to burn all libraries to the ground.



## Japanese Architecture

Writing in the *Asia Magazine*, a recent visitor to Tokyo asks the following questions:

Why have the Japanese abandoned their splendid heritage of eastern art? Why are they imitating the West? These are the first questions which spring to the lips of every sensitive European or American who comes to Tokyo. The call of the East has lured them a thousand leagues—to what? To the capital of the Tycoon? To the old Yedo of the color prints? To the diaphanous colors of Hearn's lovely pages? No!—to one of the ugliest cities of mixed architecture in the world. Old Japan lingers in by-streets, in temples, in tea rooms and gardens and in conservative art, but nowhere with evolving energy, as one is forced to admit, when chance throws old and new together for our comparison. To the traveler newcomer the contrast does not strike home, because there is enough of old tradition to satisfy his exotic needs. It is only when second-hand Europe in Asia begins to obtrude itself upon his attention that his indignation is aroused, and his resentment leads him to ask the answers to these questions.

Looking for oriental beauty, he finds all the ugly occidental trade-marks of materialism, and he turns and rends them because they are not up to date. The necessity for modern efficiency he reluctantly admits; but, being no psychologist, he cannot grasp the magnitude of this demand for the old exquisiteness of the extreme oriental people, whose whole energy has been spent during a short half-century in absorbing, at breakneck speed, western industrialism and material efficiency, in order to preserve independence. The west has taken at least four times as long in her own indigenous process and has effectively antagonized her art and action. It may well be that the traveler's protest is a cry of sympathetic pain and warning.

"But," exclaims the visitor, "what has art to do with industrialism?" Everything. In applied art directly and in pure fields indirectly. The Japanese are abandoning their old traditions of art because they are abandoning their old traditions of life. The two are inseparable; life feeds art, and art stimulates life. As well might one expect a cabbage to yield roses as to demand the old medieval flowers of Japanese art on the pavements of Tokyo.

## Rheims Cathedral, Past and Present

That Rheims Cathedral is more associated with the history, the patriotism and the art of France to a greater degree than perhaps any other similar structure may be gathered from the following account in the English architectural press.

Rheims Cathedral was built on the spot which tradition assigned to the baptism of Clovis—an event which gave to the Kings of France their titles of *Roi Tres Chrétien* and *Premier Fils de l'Eglise*. It early became the coronation church of the Capetian dynasty, and to it Charles VI was brought by Joan of Arc to receive his crown and to save his country. It was considered to be one of the most noble and most beautiful examples of medieval architecture in Europe.

Conflicting reports as to just what has happened to this noteworthy example of Gothic building, make an authoritative account of interest.

The western façade and portal are severely battered, the greater number of the pinnacles of the southern front

have been shot away, the roof has several gaping holes in it, the high altar is a formless mass of débris, and the choir as such has ceased to exist. The glass has entirely disappeared—some, indeed, has been preserved, but most has been totally destroyed. All that really remains is the core of the fabric—probably considerably shaken and weakened—and the remarkable series of statues within the west wall. Nothing in the way of restoration has yet been begun, and the public are shown the church by a guardian who tells them that it will take a generation to repair it.

## Pawtucket's Civic Theater

The disappearing saloon is creating problems which have been absorbing attention throughout this rapidly drying country. While the interesting work of the Pawtucket Civic Theater had its inception in an entirely different need, it might if adapted in other cities, also serve as an alternative for the saloon, particularly in cities where a large percentage of the residents are foreign born.

The Civic Theater movement in Pawtucket is an enterprise founded for the sole purpose of teaching Americanism to the foreigners in our midst. The common sense methods pursued, the sympathetic attitude of those who are conducting it toward those of foreign birth, commend it to the serious consideration of all who would have the melting pot melt a trifle more thoroughly than it has in the past.

## Survey Shows How Available Space Has Been Absorbed

The survey of housing conditions in thirty-four typical city blocks, which has been carried on by the New York State Reconstruction Commission with outside aid, reveals a percentage of vacancies which has continued to decrease since 1916. The vacancies now are at their lowest point and are found practically only in houses which are completely uninhabitable from the point of view of human things.

"At present there is a total of about 985,000 apartments in Greater New York," said the Tenement House Commissioner, Frank Mann. "There are altogether approximately 103,000 apartment houses including old law and new law tenements. These include all apartment houses. The relation between old law tenements and new law tenements is 75,000 old law and 28,000 new law, making a total of 103,000 houses.

"From January 1 until April 15, 1919, seventy-six plans were filed for tenement houses with an aggregate number of 120 buildings and 1,658 apartments. There is a shortage in the city today of about 100,000 apartments. The approximate normal increases in population, with immigration eliminated, as it is now, should be about 200,000.

"The vacancies in 1916 in tenement houses, both old law and new law together, was about 6.52 per cent; in 1919 it is 3.25 per cent, of which the vacancies in new law tenements are .6 per cent and in old law tenements 2.18 per cent.

"The vacancies which existed are on the lower east side—the old tenement houses some forty or fifty years old or more. They would house approximately 42,000 people. They are legally fit for human habitation, but that is all. The only remedy to this situation is the erection of new and better houses."



### Planning Model Cities

Cities looking for twentieth century results cannot expect to get them from nineteenth century methods. This is the substance of some comment in a daily paper of St. Paul. The writer of this comment calls attention to the situation in England. There, he says, new cities are planned for sites as yet unbroken, to provide localities for industries and homes for industrial workers. The great cities—London, Manchester, Sheffield—are no longer regarded desirable locations for industries. They are incapable of taking care of the pressing demands of housing, transportation and sanitation. They are too inelastic and unadaptable. Property is too expensive and the mistaken conservatism of proprietors is a bar to the improvements necessary for the development of a modern industrial community.

The same tendency may be noted in this country. Gary is the classical example, a city planned complete before a spadeful of earth was turned on the grounds where it was erected. But apart from paternalistic ventures of this sort, there are cities like Flint, Mich., and Janesville, Wis., both of which have had remarkable growth due to the automobile industries which have developed there, and both of which are laying plans for the maximum of municipal efficiency.

This is the course of procedure the benefits of which require no emphasis of statement.

### Paris Architect Estimates Rheims Construction to Cost a Billion Dollars

Architects of Paris, Rheims, and other French cities have been preparing plans for the reconstruction of Rheims, the total cost of which undertaking they have estimated at a billion dollars. Twenty complete plans have been submitted. The city of Rheims will select from each plan the features that seem most desirable, and will arrive at a final plan to be approved by the city council.

### Russian Housing Difficulties

In Russia, it is learned, housing accommodations fail to meet one-tenth the demand. Houses are so scarce that it is almost impossible to get a Trans-Siberian Railway passenger car, because they are used in all-important stations to house refugees and as Government offices.

### Simplicity of Beauty

Referring to the value of the civic association to every town or city, a writer in the Lansing (Mich.) daily press writes very tersely. A civic association, he says, may urge that industrial buildings can be just as useful if they are beautiful as if they are not, that their employees lose no efficiency because the shop has window boxes filled with green things or has its waste spaces kept in tended lawns.

It costs no more to erect a beautiful building than an ugly one, since beauty is a matter of line and color. Beauty can be produced with pine and carefully selected paint as easily as with marble. The limiting of workshops and railroad yards to certain districts may seem a hardship in

some cases, but the result in the appearance of the city, the sustained value of property and the class of persons attracted as residents will soon compensate.

### World Chamber of Commerce

The American Chamber of Commerce in London has put forward a plan for a consolidation of the various chambers of commerce throughout the world. Organizations in the United States are actively supporting the idea. The American Chamber of Commerce in London is in touch with Edward Filene of Boston, a director in the Chamber of Commerce of the United States. Mr. Filene is now in Paris, where he is working in the interest of such a procedure.

With such a combination of local and foreign chambers all working under uniform methods, it is believed that business men throughout the world will be provided with an international organization unsurpassed by anything at present available for the development of better business.

### Erect Building in 33 Hours

To have erected in 33 hours a building of 15,000 square feet floor space, including a theater, social rooms, two canteens, class rooms, kitchen, offices and five sleeping rooms, the whole being what in army parlance is known as a "hut", is an achievement of which the 101st Engineers of the 26th Division, American Expeditionary Force, may well be proud.

It is known as the "York Harbor Y. D." hut of the Yankee Division opened by the Young Men's Christian Association at Le Mans.

Foundations had to be leveled, French municipal authorities had to be dealt with for the site and for the location, of sewer, water and electrical connections; one car of material carrying the floor joints went astray and other timbers had to be cut at a local mill. Notwithstanding all these difficulties the hut, which is the largest one used by the American Expeditionary Force, was erected, New England stone fireplace and latticed doorways all complete, in a space of time that made the good people of Le Mans rub their eyes in amazement.

### Government Offers Business Data to Industry

The Council of National Defense announces its readiness to place at the disposal of business men the large fund of information now available in the quantity of data assembled and classified by its Reconstruction Research Division. This division, it is stated, may be called upon to procure such additional special information as will assist in the reorganization of industry and the resumption of trade, or in any way promote progress in reconstruction.

The division is well equipped for such service. It has access to every important report of foreign reconstruction, whether proposed or actually accomplished, that reaches this country. It also has available, what is thought the most reliable information to be obtained on foreign, commercial, industrial and financial conditions and prospects.

It is learned that this division has contact with all the war administration boards, and investigation commissions, as well with numerous sources of unpublished information,



dealing with price data, production estimates, wage data, labor supply reports, and the reported results of experiments in method of handling labor problems, on foreign production and other conditions abroad, including labor and immigration.

The division maintains its own clipping service, supplemented by commercial clipping bureaus, and has facilities for sifting practically everything in public print that has a bearing on any phase of reconstruction. This material is all classified, indexed, and ready for reference.

The material and staff now placed at the command of business are primarily intended for government use and will, of course, continue to function as the government clearing house of reconstruction information.

## San Francisco Struggles with Comfort Station Problem

Plans for the establishment of comfort stations throughout the city, in addition to those to be built by the city, are being discussed by the Board of Supervisors of San Francisco, Cal. A proposition has been advanced to make the permits granted automobile service stations contingent on the establishment and maintenance of such facilities.

The city engineer has recommended an appropriation of \$12,000 in the coming budget for the construction of convenience stations, but it is doubtful if work on any of these can be commenced before saloons go out of business, even if the application for funds is granted.

San Francisco is singularly lacking in public convenience stations, the city maintaining but one in the downtown district, outside of those in its City Hall and Hall of Justice. However, it has exceptional opportunities for the installation of stations, since it is the owner of all sidewalk area, an arrangement not true in many large cities.

Property owners have been making use of this free of charge for many years, and it has been suggested that they be called upon to pay a rental for this privilege, or to set aside basement room for comfort stations. Civic organizations are urging that some policy be decided upon at once and work commenced.

## Issue Call for Meeting to Form New State Association in New York

A call was issued this week to all qualified architects in New York State to attend a meeting to be held at Utica, N. Y., on June 7th, at which time a new organization, to be known as the New York State Association of Architects, will be formed. As was exclusively announced in the April 30th issue of THE AMERICAN ARCHITECT, all architects of New York State interested in the formation of this organization are requested to correspond with John B. Slee, acting secretary, at 154 Montague Street, Brooklyn. The purpose is to bring together those practising the profession of architecture in order that they may take a more active part in the working out of the important and timely issues that now have to be faced. Others on the committee of arrangements include Frederick L. Ackerman, William P. Bannister, James Riely Gordon, L. E. Jallade, Robert D. Kohn, Frank H. Quinby, Andrew J. Thomas, D. Everett Waid, all of New York City; A. L. Brockway, Syracuse; Edwin S. Gordon, Rochester; F. H. Gouge, Utica; Edward B. Green and H. Osgood Holland, Buffalo; Alexander Mackintosh, Brooklyn; Leon Stern, Rochester; Ornan H. Waltz, Ithaca, and Walter H. Whitlock, Binghamton.

## Personal

Architect Anton Dobman has moved his offices to 1003 Pabst Bldg., Milwaukee, Wis.

A. Raymond Ellis, architect, has opened offices at 36 Pearl Street, Hartford, Conn.

H. Childs Hodgens, architect, has opened an office at 1312 Walnut street, Philadelphia.

J. J. Kocher, architect, formerly of 7807 S. Loomis St., has moved to 806 W. 79th St., Chicago, Ill.

Fred A. Evans, architect, announces the removal of his office to 704 Book Building, Detroit, Mich.

R. E. Peden, architect, has opened offices at 945 New York Life Building, Kansas City, Missouri.

Chas. F. Buhrman, architect, R. F. D., Waynesboro, Pa., is about to open an office in Waynesboro for the practice of architecture.

F. W. L. Foehringer, architect, formerly 118 North La Salle street, has moved his office to his residence, 2677 Orchard street, Chicago.

Walter Frieling, architect, formerly in office of Hersch & Hersch, Altoona, Pa., has opened offices in room 20, Hutchinson Bldg., Altoona, Pa.

Albert C. Wirth, architect, has opened offices in the Banner Building at Greensboro, N. C. Mr. Wirth desires manufacturers' samples and catalogs.

Alfred Rapp, architect, has reopened offices at 215 West 26th street, Erie, Pa., to practice architecture and desires catalogues and manufacturers' samples.

Esselstyn, Murphy & Hanford, architects and engineers, have moved their offices from the New Telegraph Building, Detroit, Mich., to 810 Marquette Building.

John Hanifen, architect, of Ottawa, Ill., has opened an office in the Tribune Bldg., La Salle, Ill., with Strawn Aldrich Gay in charge, and desires samples and catalogues.

Ira G. Hedrick and W. W. Huff, consulting engineers, announce their association under the firm name of Hedrick & Huff, with offices at 506 Inter-State Building, Kansas City, Mo.

William Dewsnap, architect, formerly of 203 Broadway, New York, has removed his offices to 334 Fifth Ave., New York City. He would like to receive catalogs of building materials of size suitable for filing cases.

C. Howard Crane, architect, 2323 Dime Bank Building, Detroit, Mich., has opened an office at No. 6 Victoria Building, Windsor, Ont., and is preparing plans for a number of important theaters throughout Canada.

Alling S. De Forest, landscape architect, was the speaker at a recent luncheon of the Rochester, N. Y., Engineering Society. He spoke on the work done by the Government in town planning and in providing homes for workers.

Robert L. Fuller, of the firm of Fuller & Delano Co., architects, 44 Front Street, Worcester, Mass., has returned to the practice of architecture after spending several months as a representative of the United States Housing Corporation.

Mr. Phelps Wyman, landscape architect, 648 McKnight Building, Minneapolis, was elected to the board of trustees of the American Society of Landscape Architects at the recent annual election at New York. Mr. Wyman was, prior to last January, president of the Minneapolis chapter of the society. He has been employed in the town planning division of the United States Housing corporation.



# Late News from Architectural Fields

*Special Correspondence to THE AMERICAN ARCHITECT*

## Award of Prizes in Housing Competition

The American Housing Competition organized by the Journal of the American Institute of Architects, and conducted by it in conjunction with the Ladies Home Journal has now reached its conclusion in the award of two second prizes each of five hundred dollars, to Milo C. Hastings and Robert Anderson Pope, both of New York City. In making an award of two second prizes, the jury was governed by the fact that while both theses submitted offer a thorough analysis of the causes and cure for the housing problem that now exists in this country, the actual plans accompanying them did not fully provide for the application of the principles set forth in the theses.

The winning solutions will be offered broadcast as contributions which attack the problem fundamentally and relate it to our whole social and industrial organization.

## New York Society of Architects

The year book of the New York Society of Architects, revised and brought up to cover 1919, has been issued. This is a book of 200 pages, bound in flexible cloth and containing a vast amount of information that is of value and interest to architects not only in New York State, but generally throughout the country. It contains building codes, rules and regulations for plumbing and ventilating, a full report of the building zone resolution, and a complete list of the names of architects throughout New York State. The price of this work is five dollars and it may be secured by addressing the secretary of the Society in the United Engineering Societies Building, 29 West 39th Street, New York.

## Notify Institute of Wage Scale

WASHINGTON, D. C., May 23—The Builders' and Manufacturers' Exchange of Washington has notified the Washington Chapter, American Institute of Architecture, of the adoption of a price and wage scale for construction activities in the District of Columbia. The communication was read and approved at the regular meeting of the chapter Thursday night.

Appleton P. Clark, Jr., represented the Chapter on the central stabilization committee. The majority of the building trades union accepted the wage scale of November, 1918, as the basis for work. Builders have agreed to accept the pre-war percentage of profit until January, 1920.

## Architects Ask Government Aid

Fifty architects, formerly officers in the United States Army, have filed applications with the War Department for assistance in securing professional connections. The applications have been turned over to the U. S. Employment Service for placement.

## Annual Meeting, New York Society of Architects

The New York Society of Architects held its 13th Annual Convention on May 20th at the United Engineering Societies Building.

James Riely Gordon was again unanimously re-elected President, for the fourth consecutive term; Louis E. Jallade of New York was elected Vice-president; Edward W. Loth of Albany, Second Vice-president; Henry Holder of Brooklyn, Treasurer; Frederick C. Zobel of New York, Secretary; and Walter H. Volkenning of Brooklyn, Financial Secretary. Directors for three years, James Riely Gordon, Henry Holder, John Bergeson, Hugh Tallant, and Louis E. Jallade, and for one year, Nicholas Serracino and Frederick C. Zobel.

There were many interesting discussions. The consensus of opinion was that the present prices of labor and material will remain, and that this is the most advantageous time to build, in advance of the great amount of building which will undoubtedly be inaugurated before Fall. Many important steps are in contemplation this year, for the future welfare of the architectural profession. The society is heartily co-operating with other architectural societies and with real estate and building organizations allied with the profession. A number of applications for membership were received, and a number of new members were elected. In spite of the war this has been the Society's most prosperous year, it was stated.

## To Unify State Registration Laws

It has for some time been apparent that it would be desirable to bring about unification of the work being done by the various State Boards which are administering registration laws for architects. With this in view, an informal meeting was held at the time of the Institute Convention at Nashville by representatives of a number of registration boards. An informal association was organized which will seek to co-relate the experiences of the various States having such laws, enabling new boards to profit by that experience.

It is hoped that it will be possible to bring about a conduct of examinations as to make possible the exchange of credits between States, and thus facilitate the admission to practice in one State of architects who have already qualified in another. It is desirable that a special session be devoted to this subject at future Institute Conventions, for these State Boards, if properly constituted, will have the setting up of the standard of admission to the profession entirely in their hands.

The officers of the informal organization above referred to are Professor Emil Lorch, of the Michigan State Board, as Chairman, with Emery Stanford Hall, President of the Illinois State Board, acting as Secretary. All those interested in helping this work should address Mr. Hall at 332 South La Salle Street, Chicago, Illinois.



## Survey of Country's Economic Status Indicates Early Start of Construction Activity

IN a report just made showing the present status of economic conditions of vital importance to the country's welfare, John W. Platten, president of the United States Mortgage and Trust Company, states that the construction situation promises early improvement. Other indications are that the labor supply is at present adequate, and returning soldiers are being generally employed without unduly disturbing the labor market. Real estate conditions are found to be excellent and mortgage money is easy. Retail trade proves to be excellent. The Federal Reserve System is shown to be functioning in a highly satisfactory manner and the Federal Farm Loan System is gradually gaining in influence and popularity.

President Platten's report is in substance as follows:

Only in rare cases does there appear any shortage of labor. Indeed, it might easily be said that the contrary is true, due to returning troops and the closing down or curtailment of industries which were unusually active during the war. In view of these two important and far reaching factors it is evident that only the most intelligent effort and co-operation could have prevented an unsatisfactory situation. It is therefore most gratifying to find that employers, public officials and organizations generally have given the matter earnest and timely consideration with the result that up to the present time there is no serious disturbance.

It is true that there are sporadic outbreaks, a few strikes and some professional agitation, which, however, can no longer be classed as extraordinary or preventable even under the most favorable circumstances. Workers leaving the Government service are thus far being quite generally reinstated in their old positions, and this without in any large measure displacing the extra help taken on during the last two years.

From reports in hand, it appears that rents have increased almost universally, the percentage running from 10 per cent to 50 per cent, with occasional excessive advances in business space strategically located. The lack of new construction in the last two years, during which practically all available space came into demand, the flow of labor to industrial centers and the cost of labor and materials preventing needed new construction, have combined to force rents up to their present high levels, some of the non-industrial cities proving the only exceptions to this rule.

There are few large building operations in progress at the present time but there is considerable construction of dwellings, and a few business structures are under way. Building in a large sense, however, is not making any great headway, being unable thus far to adjust itself to the prevailing high prices of labor and material.

Organized labor is making vigorous efforts to maintain the present wage scales but the indications are that lower levels in some cases are bound to come. Reductions in a few lines indicate that material prices may possibly be on the point of a downward movement, but any immediate plans based on such development would doubtless be somewhat premature. However, these conditions considered in the light of the great need for new construction, give reasonable grounds for expecting a building campaign of good proportions at a reasonably early date.

One fact which stands out clearly in the Real Estate situation is the insistent demand for dwellings. This has literally forced a limited amount of home and apartment house building and vastly increased the rental demand for all available space of this nature.

In the wheat growing area the Government guaranteed price for the 1919 crop has resulted in a good demand

for wheat land. There is considerable activity in farm land generally, and more or less activity in small acreage plots. Oil and fruit lands are also in favor. Mortgage conditions are easy, with plenty of money available and rates declining.

Retail trade is in a healthy, flourishing condition, marked by only a few instances of depression and caution as to overstocking. The splendid possibilities for trade expansion opened up by the war are being met by a responsive appreciation of the part of business men, manufacturers, trade organizations and public officials. Particular attention is being given to exports, the improvement of waterfront facilities and the location of new industries. Significant, too, are the plans for bringing under cultivation largely increased areas through irrigation and other methods.

The Federal Reserve System is so well established and its beneficial operation so clearly demonstrated that it is now taken as a matter of course. By taking care of the war financing, the extension of credit, building of confidence and stabilizing conditions throughout the United States, it fills a place possibly higher than was anticipated by its most optimistic supporters.

The Federal Farm Loan System has proven of immense benefit in sections where opportunity has been given to show its worth. It continues to stimulate production by providing funds in large volume for long terms and at low interest rates. The one disappointing but perhaps natural feature is that it does not yet appear to be fully understood in some quarters, with the result that the benefits which it might confer are far from being fully realized. The indications, however, are that it is only a matter of a comparatively short time before it will be more generally known and utilized.

The following digest shows the trend of business and fluctuation of residential rents in the last two years, new building, labor and material prices and mortgage money in various sections of the country:

In the South—From reports received, rent increases are universal, ranging from 10 per cent to as high as 50 per cent. New building generally limited to dwellings and betterments, although a few large operations are under way. Good season in prospect. Labor and materials show little changes as yet, but generally appear to be weakening, although opposite tendency exists in one or two cities. Residential property is in big demand, with occasional instances of activity in business buildings and oil and farm land. Renting space very well filled. Mortgage money noticeably easy, with rates reacting accordingly.

In the Central West—Rents have generally increased but not to an excessive degree. The range is from 10 to 25 per cent, the larger increases usually applying to business space. A few large building operations are under way, but new construction is largely held up by present high prices of labor. There is some tendency toward reductions, but not to a degree warranting any early relief. The real estate market is strong in some lines, particularly renting, as the recent lack of new construction leaves practically no surplus space on hand. There is an insistent demand for dwellings and some call for farms and vacant property. Mortgage money is plentiful, as a rule, with rates easing off.

In the Southwest—Rents are generally higher, 10 to 25 per cent. There is some home building in response to urgent demands, but construction work generally is waiting more favorable prices. Labor is naturally anxious to maintain the present high wage scales, but with the general readjustment, some concessions are likely. Building materials show some reduction. The real estate market



## THE AMERICAN ARCHITECT

shows a brisk demand for dwellings with considerable activity in farm lands. The rental situation is good and some leases are being made on oil lands. There is an ample supply of mortgage money throughout the Southwest with the natural result of decreasing interest rates.

In the Inter-Mountain section—Rents are 10 to 50 per cent higher except in Spokane, which was deserted by its floating population when the neighboring industrial centers went on a war wage basis. There is considerable home building and planning, and a few larger operations but other projects are held up. These show a downward tendency. There is a good demand for homes, also some

sales of small suburban plots. Around Spokane, wheat and fruit land command good market. Mortgage funds are ample with rates tending downward.

On the Pacific Coast—Rents are uniformly higher, ranging from 10 to 50 per cent, with some choice retail space showing excessive advance. In response to a strong demand for homes there is a limited amount of construction. Materials show a tendency to lower levels. The real estate market shows a steady demand for moderate priced homes for occupancy by purchasers and wheat land is looked on with favor. Mortgage money is plentiful, with rates tending to ease off.

### "Open" Building Material Market Forces Prices Upward

WITH the return to an "open" building material market, forced by the recent abandonment of the Industries Board as a result of its conference with the steel industry, there has come a decided trend upward in commodity values. When it was learned that there was to be no further attempt by the Government to stabilize prices, architects and builders manifested keen interest as to just what the effect would be, and in what direction quotations would fluctuate.

There is no question but that construction activity is fast resuming its normal cadence, but weekly price tables also show that with the improved demand there has come an upward price movement and that the low level has been reached. The question now is how long can prices hold at present levels. Brick and lumber are now leading in the upward movement, due to the scarcity of labor and exceptionally high wage scale. The industry deems it most unfortunate that at this time building costs should be advanced.

It was clearly shown that while the Industries Board and the Railroad Administration were at deadlock over prices in practically every municipality only the more daring speculators and those soundly financially backed proceeded with building projects. The strangling of the fundamental laws of economics and substitution of price fixing, without any question, retarded the impetus that long ago should have been given post-war construction. Only when leading steel corporations proved that no further reduction in prices would be made without a reduction in wages was the fight for an "open" market won. But in the meantime business had been severely handicapped.

Before its retirement the Industries Board released hardwood manufacturers and other commodity interests from their promises of co-operation in price adjustments. In explanation of the withdrawal of the board, it was said that it had for its object the resumption of construction and production through the stabilization of prices. The legal phases of the question as raised by the Attorney General's comment on the illegality of price fixing failed to disturb the opinions of Secretary of Commerce Redfield or Mr. Peck, who referred to the opinion of the Department of Justice as negligible. The results sought could have been obtained, chairman Peck contended, without violation of the Sherman Act, as the plan was to ascertain and make public fair prices reached by agreement. When the Railroad Administration refused to buy rails at a fixed price, it was because Director General Hines believed that it would cause a later inflation of values. From the upturn in prices the past two weeks this theory has been borne out, not only in structural steel, but in common brick, sand, gravel, grit, broken stone, cement, plaster, lead, oils, and particularly lumber, as well.

An interesting sidelight on the many different problems affecting the progress of construction is to be found in the fact that contractors in estimating costs on suburban home construction are submitting bids that are decidedly close. On a recent project it has been disclosed that two bids on a country home were for the same amount and that the third was for but \$170 less. When the cubage cost based on these bids was found to be fifty cents and that similar work was being done elsewhere at from thirty to thirty-five cents, suspicions were aroused that there was collusion among the contractors in that section, and that they were attempting to profiteer in their work, especially, as in this instance, when the architect was from another locality. If these suspicions are confirmed it would seem that contractors in certain sections are by these irregular methods offering a severe handicap to construction.

Investigation into the cost of manufacturing various materials by the Illinois Senate as a result of suspicion that combines of dealers were holding up the prices of the various commodities failed to produce evidence to substantiate these reports. Manufacturers in the cement, stone, brick and lumber industries were called in, their books gone over, and every possible effort made to account for the present cost of their products. It was clearly shown that with the present high cost of labor there can be no reduction in manufacturing costs at present.

Reports from THE AMERICAN ARCHITECT's correspondents this week indicate that the building wave which has been working its way from the West is fast reaching the East. Two of the leading New York architectural firms have fifty-two distinct operations on their boards at this time, for many of which plans and specifications are about completed. Others are in the preliminary stages of closing the contracts. All of which indicates that the building boom is surely launched, having adjusted itself to the prevailing prices of labor and material.

The increased volume of material leaving the supply yard, the big demand for draughtsmen in the architect's offices, as well as the increasing commodity prices, are but few evidences of increased activities in construction projects. It is the actual start of post-war building, first the remodeling of old structures and building of low cost homes, and now the issuance of permits and the breaking of grounds for apartments and factories, that is stimulating many lines of business and making readjustment from war to a peace basis possible.

(Continued on Page 772-A)



# Department of Architectural Engineering

## Research Investigation of Warm Air Furnaces for House Heating


AMONG the many elements that constitute the building industry, there are several that are capable of being classed as unknown quantities. This is true because exact and definite data concerning them has never been secured. Among these are included the warm-air furnace for house heating. It seems remarkable that such an important factor in the heating of dwellings should have been so long neglected in this regard, and possibly the rapid advances made in the art of steam and hot water heating have so shaped competition that the manufacturers of warm-air furnaces were forced to recognize the necessity of making a scientific investigation of their own product.

The National Warm Air Heating and Ventilating Association, at their 1918 convention, appropriated the sum of \$8,000 to be used for a scientific investigation of the warm-air furnace. It was decided to have this investigation made at the University of Illinois Engineering Experiment Station under the direction of A. C. Willard, Professor of Heating and Ventilating. During the first year's work, now drawing to a close, this sum has been expended with a like amount of money contributed by the University of Illinois. Professor Willard's staff, conducting this investigation, consists of A. P. Kratz, Research Assistant Professor; W.

E. Pratt, Research Associate Special Investigator; V. S. Day, Research Assistant, and F. G. Wahlen, Graduate Research Assistant. The National Warm Air Heating and Ventilating Association deposited the funds with the University authorities to be expended by them. The Association has an advisory committee which has charge of securing funds and co-operating with the investigators if required. The appointment of the staff and the conduct of the tests has been entirely under the control of the Director of the Engineering Experiment Station, and the results,


as are all of those emanating therefrom, will be entirely free from the influence of any personal or commercial interest. A progress report will be made to the 1919 convention of the Association to be held at Columbus, Ohio, on June 11. Allen W. Williams, Columbia Building, Columbus, Ohio, is Secretary of the Association.

A description of the apparatus used for test purposes is here given, and some of the difficulties encountered are described. A steel channel and angle iron frame was constructed, on which three heavy plank floors were placed. These floors or platforms represent three floors of a dwelling and are 8 ft. apart from top to top of floors. Steel frame stairs are used, giving easy access to all




General view of the furnace testing plant. The switchboard for the electric thermo-couples is located on the first floor above the furnace. At the left is a portion of the auxiliary fresh air inlet. The construction of the frame work supporting the various floors and the various vertical ducts are shown. Tests have been made with the galvanized iron jacket insulated with a 1½ in. hair felt covering.





Side view of the furnace showing the fresh air inlet and the Uehling CO<sub>2</sub> Recorder at the right. In the rear is the 10 in. tube forming a portion of the auxiliary fresh air inlet.

floors. This structure is erected in the Mechanical Experimental Laboratory. The installation consists of a No. 270 hot air furnace, made by Moore Brothers, Joliet, Illinois. This is a standard fur-



View of a portion of the auxiliary fresh air inlet apparatus. At the left is the exhaust fan attached to the 10 in. pipe connected to the auxiliary inlet shown at the left of the general view of the test plant. The apparatus for regulating the fan and damper is shown. At the table can be seen the Pitot tube for measuring the volume of air passing through the inlet. Readings are taken at various points in the diameter of the 10 in. tube. With velocity conditions at the auxiliary inlet identical with those at the furnace inlet the volume of air passing into the inlets is thus determined.


nace with an ordinary solid cast iron fire pot and galvanized iron jacket. There are four 12-in. round horizontal ducts for the first floor, two 9-in. and two 8-in. for the second floor and two 9-in. for the third floor. These horizontal ducts are covered with an asbestos paper. The first floor ducts are connected to a boot leading to the base board registers, as shown in the illustration. The other horizontal ducts connect with vertical flues after passing through the boots at the basement

ceiling level. The vertical flues are placed between two studs with plaster board nailed to the edges, thus enclosing the flues. The passage of air between the flue and the stud and plaster board closure is prevented. Single and double-wall vertical tin flues are installed to the second and third stories, and the variation in performance is noted. Electric thermo-couples are installed in each of the ten registers, six in the base of two vertical flues leading to each floor, one in the smoke pipe and one in the fresh air inlet. These eighteen thermo-couples are connected with a switchboard located on the first floor, where the temperature readings are taken.

A thermometer is placed in the horizontal duct at the left of the front of the furnace and is

under constant observation in order to maintain a constant firebox temperature. The fluctuation of temperature is very small, and the average is well maintained. As yet only anthracite coal is used, and the firing, burning and weighing of the residual ash conforms to a standard procedure.

Temperatures are not taken in the jacket, owing to the radiant heat dispelled from the furnace, but it is expected that a method of measuring the air temperature at that point will shortly be developed.




View of the furnace fresh air inlet at the left and the auxiliary fresh air inlet at the right. The anemometer readings are being taken at 24 points on the face of the inlet to the furnace. Identical velocity conditions are established in the auxiliary inlet by means of an induction fan shown in another illustration.

The velocity of the air passing through the registers is measured by a special type of anemometer. This anemometer is attached to a square steel bar of sufficient length to permit of its being



## THE AMERICAN ARCHITECT



Auxiliary apparatus in small research laboratory. At the left is an electric heater placed in the end of the pipe which leads to an electric driven fan. The air is drawn through the heater and passed into a 5 in. tube which expands at the right end into a horizontal furnace duct which passes through a boot into and through a register. The same temperature and velocity conditions are established at the register as may be found at each register in the test plant. When these conditions are established readings are taken from the Pitot tube apparatus connected with the 5 in. pipe and the volume of air passing through the register is determined. By means of this apparatus the volume of air passing through all of the registers is measured. This is found to be slightly in excess of the air passing through the inlet and probably the result of infiltration through openings in the furnace jacket.

placed in three positions across the length of the register. Two steel bars are attached to the sides of the registers, in which are cut three notches in which the bar slides. By this means nine readings are taken on each register face and in identically the same position. The average of their readings gives the velocity of the air travel through the register. On the fresh air inlet, 17 x 47 in. in size, six horizontal readings are taken on each of four positions in the height of the inlet, giving twenty-four readings on the face of the inlet during a period of two minutes. This method of securing the average velocity is shown in the illustration of the fresh air inlet.


By these means the temperature of the air at the inlet, at the base of the vertical ducts and at the registers is found, as well as the velocity of the air at the inlet and the register faces.

To check the volume of the air passing through the furnace, a comparative inlet and register measurement is taken on an auxiliary apparatus. At the left of the furnace installation shown in the illustration is shown an auxiliary inlet connecting with a 10-in. tube. This tube in turn terminates in an exhaust fan, shown in the illustration. By means of this fan the same anemometer readings are established as occur in the furnace inlet. As shown, a Pitot tube is inserted and readings are taken at several points

in the diameter of the 10-in. tube, and thus the volume of air entering the furnace inlet is found. The apparatus for controlling the speed of the fan and the damper is also shown.

In a small research laboratory is installed a device for the purpose of checking the volume of air passing through the registers. At the inlet end of this, at the left in the illustration, is placed an electric heater attached to a duct leading to a fan. Leading from this fan, to the right, is a 5-in. tube which expands into a horizontal duct which enters a boot above which is installed a register. By manipulating the furnace and fan identical temperature and velocity conditions are established as were found at the registers in the furnace installation. A Pitot tube is inserted in the 5-in. tube, by which the volume of the air passing through the register is determined. It is found that the volume of air passing through the registers is slightly greater than that passing through the inlet. This is probably due to infiltration into the jacket.

An auxiliary plant is also used to work out problems on horizontal and vertical ducts. In this work the horizontal ducts will be of various lengths and inclinations. The vertical flues will be of different sections, round and rectangular, and the effect of any particular departure in design and installation from a typical standard is determined. The air is heated by a steam coil to any desired temperature and the water of condensation is measured. Temperature and velocity readings at the register are taken in the same manner as in the installation before described. The effect of various types of



Auxiliary plant for problems on vertical and horizontal ducts, different sizes and shapes of ducts will be tested with different inclinations and lengths of the horizontal duct, insulated and not insulated. The air is heated by steam coils in the large air chamber at the right. The glass encased Wahlen Draft Gauge is shown suspended from the duct with which the draft is measured at various points in the diameter of the duct. An enlarged view of the gauge is shown in the lower left-hand corner. Temperature readings are taken at the base of the vertical duct, at the register and in the duct near the hot air chamber. Velocity measurements are taken at the register with an anemometer.



insulation will be measured. It was found that the draft in the duct was so slight that no known gauge would measure it. It was given to Mr. Wahlen to design and construct one, and he has succeeded in constructing the Wahlen gauge, which indicates 1/10000 in. head in alcohol, which is comparative to 1/12000 in. head in water. This instrument is shown in the glass enclosed cage in the illustration, and readings are taken at various points in the diameter of the pipe. This instrument is so delicate that the passing of the hand in front of the orifice causes it to register a variation in air conditions.

This description will indicate the vast amount of labor and time required to make the installation of the main testing plant, the installation of the auxiliary plants and the designing and making of the delicate instruments required for this particular work. At the same time certain conversion charts were prepared, from which the various instrument readings are quickly converted into final form.

The program aims to establish (1) a reasonable basis for rating furnace performance, (2) to compare the performance of several standard types of furnaces, and (3) to determine what are reason-

able velocities in pipes. The tests made at this time are to establish the capacity of a furnace to heat a given number of pounds of air from one given temperature to another temperature during a given period of time. The field of investigation is very great, and in order to complete it two more years of work may be required. New and important problems are continually arising which must be solved. Much data used in the design of warm air furnace heating plants has been found to be incorrect and conditions that have never been contemplated have been discovered. It will only be by means of such an investigation as this that the actual facts concerning warm air furnaces and their use can be known. It is of the utmost importance to that portion of the building industry devoted to the construction of dwellings mainly, and some other types of buildings, that this work be carried on to completion. When completed, and the various furnaces are standardized as to their performance and this data is available for installation design, the architect can proceed with some assurance of success in the use of warm air furnaces. This will certainly be a most welcome change from the conditions that now obtain.

## Reinforced Concrete Building Stands Extreme Overload


**R**EINFORCED concrete structures have often been loaded far in excess of their designed safe carrying capacity, both for the purpose of testing the efficiency of certain types of design and for other experimental purposes. The University of Illinois, in Bulletin No. 106, records the results of one such test conducted on a flat slab type of reinforced concrete building about to be demolished.

While overloading also occurs to a greater or lesser extent in structures under actual service conditions, it is seldom that a building is called upon to sustain an overload as great as that which was recently placed upon the second floor of a reinforced concrete building in Long Island City, N. Y.

The structure in question was erected about three years ago, and is one of a group of several similar buildings. It is four stories high without cellar, built over marshy ground upon a

concrete pile foundation, with floors designed to support a live load of 200 pounds per square foot. The section in which the overloading occurred is 80 ft. wide by 218 ft. long, divided transversely into three bays, the outer bays being each 26 ft. 4 in. wide, and the center bay 27 ft. 4 in. wide. In a longitudinal direction the columns, which are circular in section, are spaced 18 ft. on centers. The floor construction is of the girder, beam and slab type with troweled floor finish. The girders are 14 in. by 26 in., in section, and have a clear span of approximately 16 ft.; the beams are 8 in. by

22 in. in section, spaced 6 ft. on centers, the beams in the outer bays having a clear span of 25 ft. 2 in. and those in the center bay of 26 ft. 2 in. Beams and girders are reinforced with heavy twisted steel rods (about 1 in. square) some of which are bent up at the ends. The slab is 4 inches thick and reinforced



General view of building.



## THE AMERICAN ARCHITECT




Interior view of second story showing heavy overload of tin. The work of removal has just been commenced.

by light round corrugated bars spaced about 4 inches on centers. Gravel concrete was used throughout, probably of a 1:2:4 mix.

It seems that the owners of the building had not occupied it for some time, but had leased it to a concern who in turn sub-leased the first and second stories to a warehouse man. This sub-lessee began using the two lower stories early in the year for the storage of sheet tin prior to its being shipped to Japan. This material is boxed in individual cases, each having outer dimensions of approximately 18½ in. by 14 in. by 4 in. deep, and of 122 lbs. gross weight, or 68 lbs. per sq. ft. when laid flat. From this it will be seen that the allowable safe load of 200 lbs. per sq. ft. would have been exceeded by 3 lbs. had the boxes been piled but one foot (or three cases) high. From the illustration showing the second story after partial


removal of the cases it will be seen that the tin was stacked nearly uniformly over the entire floor to a height of 15 cases (or 5 ft.), with a total resultant live load of 1020 lbs. per sq. ft., *over five times the designated safe load*. In some places the cases were stacked 20 high, thus loading the floor to 1360 lbs. per sq. ft. The equivalent average uniform load over the entire floor, allowing for the two longitudinal aisles near the columns, was between 900 and 1000 lbs. per sq. ft., as nearly as can be determined, but in many panels the loading was much higher than this figure. That these heavily loaded sections of the floor did not col-




Boxing beam forms around reinforcing rods left in place.

lapse is a remarkable testimonial to the efficiency of this type of construction.

The sub-lessee had several carloads of sheet tin on a siding, and apparently it was his intention to add this to the already overloaded floor. However, when the loading had reached the stage described, warning cracks in the beams and girders began to appear. The night watchman became alarmed by a series of rumblings or creakings, apparently due to the partial rupture of the concrete as the



Condition of outer bay after concrete had been removed. Note beam reinforcing rods left in place; also that cases of sheet tin stacked in center panel are located over girders.



View looking down on first floor. False work for supporting forms already in place.



## THE AMERICAN ARCHITECT

deflection increased and the cracks opened. These seemed so ominous that this individual spent the rest of the evening in the fresh air outside the building and reported approaching trouble in the morning. The matter shortly thereafter came to the attention of the Bureau of Buildings, and Superintendent Moore took prompt steps to relieve the dangerous situation. An "unsafe" building survey was immediately held, and under the powers vested in him by law and acting under a court order, based on the findings of the board of survey, the Superintendent of Buildings caused the removal of the material and the shoring up of the weakened second floor construction. An examination of the floor after the load had been removed indicated a continuity of action in the structure from wall to wall transversely, cracks having appeared on the upper surface on each side of, and parallel to, the two lines of longitudinal girders at approximately the point of inflection, this action thus reducing the bending moment at the center of the beams to  $\frac{WL}{12}$  or possibly to  $\frac{WL}{20}$ . That real "T" beam action did occur between beams and slab is evident from the fact that in some cases the cracks extended through the slab and into the beam proper or stem of the "T." Polygonal cracks also

appeared in the upper part of the slab roughly concentric around the columns.

The elastic limit of the construction (if such a property exists for concrete) was evidently exceeded, and at the present time the work of reconstruction is in progress as shown in the illustrations. The concrete slab and beams in one of the outside bays have been removed leaving the heavy reinforcing rods of the beams exposed, but firmly embedded in the wall and interior longitudinal girders at the ends. The slab reinforcing rods were removed, straightened, and reused. Wood forms were constructed around the beam reinforcing rods that had been left in place, and the new concrete beams and slab poured. This process will be repeated in the center and other outside bay, thus replacing the entire second floor construction without any great difficulty.

This experience would seem to refute the statement so often made that a damaged reinforced concrete structure is practically unrepairable and must be demolished.

Reconstruction work of a somewhat similar nature, it will be recalled, was satisfactorily completed in the Edison factory buildings at Orange, N. J., a few years ago after those buildings had been seriously damaged by fire.



New slab being placed. Reinforcing rods showing are those taken out of demolished floor slab, straightened and re-used.



# Present Status of Industrial Lighting Codes\*

## Part II

By G. H. STICKNEY

### GLARE LIMIT SPECIFICATION

THE establishment of proper limits for glare is probably more important than even the matter of intensity. While the provision of sufficient light is fundamental, it is also better understood and has a more obvious relation to production. It seems to be generally agreed that more employees suffer from glare than from insufficient light. Certain lighting conditions are readily recognized as glaring, while others are equally recognized as free from objectionable glare. But when it comes to drawing a definite limit between danger and safety, our present inability to measure or accurately define objectionable glare makes it necessary to utilize a qualitative rather than a quantitative specification.

The I. E. S., Pennsylvania and New Jersey codes simply require that lamps be "suitably shaded to minimize glare," with an explanatory note that glare from lamps or unduly bright surfaces produces eye-strain and increases accident hazard. This is supplemented by the requirement (under "Distribution of Light on Work") that "sharp contrasts" of intensity on the work be avoided.

The New York code requires that "exposed bare lamps, located less than 20 ft. above the floor, shall be provided with shades, reflectors, diffusing glassware or other accessories, to eliminate or minimize glare." Sharp contrasts of intensity on the work must also be avoided.

The Wisconsin code goes a little farther and says,

Lamps suspended at elevations above eye level less than one-quarter their distance from any position at which work is performed, must be shaded in such manner that the intensity of the brightest square inch of visible light source shall not exceed seventy-five candle power.

Exception: Lamps suspended at greater elevations than twenty feet above the floor, are not subject to this requirement.

Note: (a) Glare from lamps or unduly bright surfaces produces eye-strain and increases the accident hazard.

The brightness limit specified in this order is an absolute maximum. Very much lower brightness limits are necessary in many interiors illuminated by overhead lamps, if the illumination is to be satisfactory. In some cases the maximum brightness should not exceed that of the sky (1.5 to 3.0 candlepower per square inch).

Note: (b) When the principal work is done on polished surfaces, such as polished metal, celluloid, varnished wood, etc., it is desirable (but not mandatory at present) to limit the brightness of the lamps in all downward directions to the amount specified in this order.

For local lighting the Wisconsin code establishes the limit of 3 candle power per square inch, whenever visible from any working position. This lower

limit is selected "because the eyes are more sensitive to strong light received from below."

There is a difference of opinion among illuminating engineers as to the proper values of candle power per square inch to be applied to this specification, while some think a better principle of specification can be determined. It has been suggested that glare be specified in terms of contrast of brightness, perhaps expressed in ratios. Some experimental work has been done along this line and at least two experimenters have made up experimental instruments for measuring ratios of brightness. It is recognized that there is a considerable range in the permissible contrast for different processes for different directions, especially of elevation, and for different intensities<sup>10</sup>.

It therefore seems likely that sometime in the future the codes will have some sort of glare classification corresponding to the intensity classification. But advance in such a direction cannot be made until further investigation and development has provided a reliable basis.

Considerable space has been devoted to the engineering limitations of the present glare specifications, with the view of interesting experimenters and engineers in the solution of the problem. On the other hand, the present specifications must not be regarded in any way as a failure. They are practical, working specifications which will do much to improve lighting conditions. They provide the means of eliminating practically all conditions which constitute a serious menace, and while the lack of a defined limit may in some cases be taken advantage of by either the manufacturers or the inspectors, such instances are likely to be quite exceptional. In reality the present specification is more definite than many existing legal requirements in force regarding matters other than engineering.

### DISTRIBUTION OF LIGHT

The New Jersey code reads: "Lamps shall be installed in regard to height, spacing, reflectors or other accessories, so as to secure a good distribution of light on the work, avoiding objectionable shadows and sharp contrasts of intensity."

The distribution of light is partly taken care of in the intensity and glare limit specifications. That is, the requirement that intensity shall not fall below a certain minimum, coupled with economic considerations, tends to avoid a wide variation in intensity, while the latter also requires the elimina-

\*Continued from issue of May 14, 1919.



tion of dense shadows on the work. As worded in most codes these rules do not call for the elimination of bright striations of light, or, in brightly lighted rooms, of shadows which may interfere with vision, but still have an intensity above the minimum limit.

The distribution of light rule covers these omissions by calling attention to the relation of lamp equipment and location to light distribution. The lighting effects referred to, if objectionable, are so obvious that they are readily recognized when attention is called to them. Therefore, the rule seems likely to accomplish its purpose without much difficulty.

In the Wisconsin code a further requirement is made that the local lighting shall be supplemented by a moderate intensity of overhead lighting, except when reflection from light colored surfaces produces a general illumination. This renders more definite a feature than is implied by the general requirement of the rule.

#### EMERGENCY LIGHTING

Panics, which have occurred in crowded rooms when the lighting has failed at the time of a fire, explosion or other emergency, have emphasized the necessity of avoiding any probability of darkness at such a time. There is, however, a wide variation in the actual needs of different workrooms. For example, where a large number of women workers occupy an upper floor surrounded by dangerous conditions, inflammable materials, etc., continuity of lighting is exceedingly important. But where a small number of employees are scattered over a large ground floor area, with convenient exits and without dangerous conditions, safety can be assured without an elaborate provision for continuity of lighting. Moreover, such provision as would be necessary in the first instance, might be prohibitively expensive for the second.

It has, therefore, seemed necessary to make only a general provision in the code, with the expectation that rulings would be made to cover specific cases, or that the detailed requirements would be supplied later by those having suitable experience. It is more a problem of safety engineering than of illuminating engineering.

The general requirement of the rule, common to most of the codes is: "Emergency lamps shall be provided in all work space aisles, stairways, passageways and exits. Such lamps shall be so arranged as to insure their reliable operation when through accident or other cause the regular lighting is extinguished." In some States the rule has been expanded to include instructions for insuring reliable operation—separate mains or sources of energy being required.

For example, the New Jersey code requires—

Emergency lighting systems, including all supply and branch lines, shall be entirely independent of the regular lighting system and shall be lighted concurrently with the regular lighting system and remain lighted throughout the period of the day during which artificial light is required and used.

Emergency lighting systems shall be supplied from a source independent of the regular lighting system wherever possible. This source of supply and controlling equipment shall be such as to insure the reliable operation of the emergency lighting system when through accident or other cause the regular lighting system is extinguished. Where a separate source of supply cannot be obtained for the emergency lighting the feed for emergency lights must be taken from a point on the street side of all service equipment. Where source of supply for the regular lighting system is an isolated plant within the premises an auxiliary service of sufficient capacity to supply all emergency lights must be installed from some outside source, or suitable storage battery; or separate generating unit may be considered the equivalent of such service.

It is apparent that the question of insuring the source of supply is one which is open to considerable discussion, involving, as it does, the reliability of the generating station and various classes of supply lines. Not only do the characteristics of service received from electric central stations and isolated plants have to be considered, but in some cases gas service and other illuminants.

It is evident that conditions of reliability vary considerably in different instances and that leeway must be allowed according to the merits of the particular cases. Where central station service is employed, it has usually been assumed that independent wiring to the street main provides a sufficient safeguard.

There is a tendency in some quarters to require the emergency lighting to be in operation whenever the regular lighting is in use. This comes from the apprehension of deterioration of unused equipment as well as the anticipation of failure to put the emergency lighting into operation instantaneously. In many cases simultaneous operation may involve an excessive expense. The provision of an automatic system, with reasonably frequent inspection and tests, should provide ample protection.

Where the system is not electric the automatic control may present more of a problem.

Most of the codes do not specify what intensity of lighting shall be provided. In New York State the emergency lighting is provided for in the law, while the code specifies one-quarter foot-candle as the intensity to be provided. This value, which might be implied from the intensity table, is being considered for inclusion in other State codes. It seems to be the reasonable value to require for exits, stairs, hallways and passageways, and also for the main aisles of large workrooms. It might, however, involve an unnecessarily high investment in lines and equipment, to provide such an intensity in all work space aisles.

(To be concluded)





Stained with Cabot's Stucco Stains  
Harland A. Perkins, Architect, Boston

## A Four-Year Record of Cabot's Stucco Stains

Gentlemen:

Wakefield, Mass., November 11, 1911.  
Last spring I used over two hundred gallons of your Waterproof Cement Stains on Miss Boit's new house at Wakefield. This was a job I was very particular to have right, and I am glad to say your material has proved entirely satisfactory in every way.

JAMES F. SHERRITT.

Four Years Later:

In September, 1915, an examination of the Boit residence by an expert decorator showed that the Cabot's Cement Stains had worn so well and grown so soft and beautiful with age that he advised against re-coloring the stucco when the other parts of the house were painted. This is typical of the results obtained. These Stains tint stucco surfaces in soft, rich colorings that grow more charming under the action of the weather.

CATALOG SENT ON REQUEST

**SAMUEL CABOT, INC., Manfg. Chemists, Boston, Mass.**  
1133 Broadway, NEW YORK 24 West Kinzie St., CHICAGO

Cabot's Quilt, Waterproof Cement and Brick Stains, Conserve Wood Preservative, Damp-proofing, Water-proofing

5-5

"A product without a peer"

## APOLLO-KEYSTONE COPPER STEEL Galvanized Sheets



Highest in quality and rust resistance. Unequaled for Culverts, Flumes, Tanks, Roofing, Siding, Spouting, and all exposed sheet metal work.


We manufacture Sheet and Tin Mill Products of every description—Black and Galvanized Sheets, Corrugated and Formed Products, Roofing Tin Plates, Etc.  
AMERICAN SHEET AND TIN PLATE COMPANY, Pittsburgh, Pa.

## APPALACHIAN TENNESSEE MARBLE

has gone into the making of many of the country's finest banks and public buildings

*A variety of colors and markings  
to suit each individual requirement*

**APPALACHIAN MARBLE CO.**  
KNOXVILLE TENNESSEE



**Johnson  
"All-Metal"  
Thermostat**  
Size 4 3/4 x 2 x 1




**The Most Artistic  
and at the same time the  
most inconspicuous ther-  
mostat on the market.**

*It is a part of the Johnson  
system of heat regulation*

**Johnson Service Co.**  
Milwaukee

## THE STANLEY WORKS

The oldest and largest manufacturers of wrought steel hardware in the world.



"8 GARAGES" is a booklet built around the illustrations, descriptions and plans of eight typical private garages. Your copy is waiting for you to ask for it. Gratis.

**THE STANLEY WORKS**  
New Britain, Conn., U. S. A.

New York Chicago  
100 Lafayette Street 73 East Lake Street

"Use Ball Bearing Butts for Permanence"



## Building Material Market Prices

(Continued from Page 764)

A digest of weekly reports showing the status of economic conditions vital to construction show that the labor supply is at present adequate and that returning soldiers are being generally employed without unduly disturbing the labor market. Real estate conditions are found to be excellent and mortgage money is easy. It appears that rents have almost universally increased from 10 to 50 per cent, with occasional excessive advances in business space strategically located, forced by the lack of construction in the past two years and the flow of labor to industrial centers.

Organized labor is making vigorous efforts to maintain the present wage scale but indications are that lower levels in some cases are bound to come. It is true that there are sporadic outbreaks, a few strikes and some professional agitation, which, however, can no longer be classed as extraordinary or preventable even under the most favorable circumstances. Workers leaving the Government service are thus far being quite generally reinstated in their old positions, and this without in any large measure displacing extra help taken on the last two years.

In the real estate situation the insistent demand for dwellings has literally forced a limited amount of home and apartment house building and vastly increased the rental demand for all available space. But whether labor or material costs hold at the present level or not the great need for new construction has forced the present building campaign, which before many weeks will develop into one of big proportions.

(From our Special Correspondent)

CHICAGO, ILL., May 26.—Commercial construction is about to start in this city. Inquiry among the architects shows that while many are busy designing low cost homes, more are at work on plans for stores, factories, warehouses,

and other commercial work. The permits issued daily also indicate that early June will see considerable speculative building under way, mostly apartment buildings.

The demand for all building materials continues to show steady gains as the season advances. Manufacturers say that while the dealers are not buying in exceptionally heavy volume individually, the demand is more widely spread and is coming from practically all consuming territories. It is evident from the size of orders that dealers are not any too anxious to replenish stocks heavily at present prices. They are buying to meet the present demand.

Lumber is advancing in price, with stocks exceptionally scarce at the mills, and dealers and wholesalers are experiencing difficulty in finding items suitable to fill their requirements. Oak and maple flooring is in better demand, with prices exceptionally strong. Further advances have been made on yellow pine and fir from the mill to the consumer. Brick, cement, lime, sand and gravel are all holding firm in price. The same is true of metal goods, including pipe, fittings and all plumbing and steam heating supplies.

Competition continues strong among the dealers in all lines of material. Contractors are taking advantage of this condition in the buying. But in consequence of curtailed production regulating the supply, any price cutting at this time is not of sufficient moment to have the effect of causing a break in any of the material markets.

"We believe it to be our duty as public officials to advise the public not to delay building projects in the hope that prices will come down materially. We do not believe they will," was a part of the report of the committee recently appointed by the Illinois legislature to investigate building material prices. Its members started out in the belief that prices of building materials in Illinois were too high, but after holding a hearing in Chicago, before which representatives of the various building industries testified, they were "driven to the inevitable logical conclusion that existing prices would not decline materially and that these prices express a new and substantially a permanent level upon which present and future business must be conducted. Reconstruction can only be accomplished in its real sense by every citizen subscribing to the doctrine 'Buy now, build now.'"

(Price quotations now current on building materials and supplies as quoted by dealers and jobbers for delivery in New York and Chicago follow. The quotations set forth are placed before readers of THE AMERICAN ARCHITECT to afford an accurate review of market conditions rather than for use as a basis for actual purchase. They will not only provide knowledge of the exact state of the market as to items quoted, but will also present a basis to judge conditions as affecting co-relating materials. Items marked (\*) indicate an advance over last week, while those marked (†) record a decline. Other prices did not fluctuate during the week.)

## BRICK

|                                                                           | New York | Chicago |
|---------------------------------------------------------------------------|----------|---------|
| Face brick (delivered on job):                                            |          |         |
| Common (Delivered at job in Borough of Manhattan only), per thousand..... | \$17.85  | \$12.00 |
| Rough red .....                                                           | 37.00    | ....    |
| Smooth red .....                                                          | 37.00    | ....    |
| Rough buff .....                                                          | 42.50    | ....    |
| Smooth buff .....                                                         | 42.50    | ....    |
| Rough gray .....                                                          | 45.50    | ....    |
| Smooth gray .....                                                         | 45.50    | ....    |
| Colonials .....                                                           | 25.00    | ....    |

## BROKEN STONE

|                        |        |        |
|------------------------|--------|--------|
| (Delivered on job):    |        |        |
| 1½ in. per cu. yd..... | \$3.25 | \$2.35 |
| ¾ in. per cu. yd.....  | 3.25   | 2.35   |

## BURNED CLAY

|                              |        |        |
|------------------------------|--------|--------|
| (Delivered on job)           |        |        |
| Block partition:             |        |        |
| 3 in., per sq. ft.....       | .18    | .10    |
| 4 in., per sq. ft.....       | .20    | .11    |
| Chimney tops:                |        |        |
| 12 x 12 for 8 x 8 flues..... | \$3.50 | \$2.25 |
| Flue lining:                 |        |        |
| 4 ft. x 8 ft., per ft.....   | .18    | .12    |
| 4 x 12, per ft.....          | .22    | .16    |
| 8 x 8, per ft.....           | .22    | .16    |
| 8 x 12, per ft.....          | .27    | .20    |

|                                                                                | New York | Chicago |
|--------------------------------------------------------------------------------|----------|---------|
| 12 x 12, per ft.....                                                           | .35      | .28     |
| 8 x 18, per ft.....                                                            | .40      | .32     |
| 12 x 18, per ft.....                                                           | .49      | .42     |
| 18 x 18, per ft.....                                                           | .67      | .55     |
| Wall coping (double slant):                                                    |          |         |
| 9 ft., per ft.....                                                             | .24      | .14     |
| 12 ft., per ft.....                                                            | .27      | .18     |
| 18 ft., per ft.....                                                            | .36      | .30     |
| Wall coping (single slant):                                                    |          |         |
| 9 ft., per ft.....                                                             | .26      | .17     |
| 12 ft., per ft.....                                                            | .30      | .22     |
| 18 ft., per ft.....                                                            | .42      | .35     |
| (Corners and angles four times the price of one foot of coping the same size.) |          |         |

## Hollow Tile

|                                                  |         |         |
|--------------------------------------------------|---------|---------|
| (Delivered at job, in New York below 72nd St.)   |         |         |
| 2 x 8 x 12 partitions, per 1,000 sq. ft.....     | \$70.15 | ....    |
| 3 x 12 x 12 partitions, per 1,000 sq. ft.....    | 102.00  | \$67.90 |
| 4 x 12 x 12 partitions, per 1,000 sq. ft.....    | 114.75  | 72.50   |
| 6 x 12 x 12 partitions, per 1,000 sq. ft.....    | 153.00  | 99.60   |
| 8 x 12 x 12 partitions, per 1,000 sq. ft.....    | ....    | 135.80  |
| 10 x 12 x 12 partitions, per 1,000 sq. ft.....   | ....    | 167.50  |
| 12 x 12 x 12 partitions, per 1,000 sq. ft.....   | ....    | 194.60  |
| 2 x 12 x 12 split furring, per 1,000 sq. ft..... | 63.75   | ....    |

## CEMENT

|                                                                |        |        |
|----------------------------------------------------------------|--------|--------|
| Per bbl. in 15 cent bags (Rebate 60c. per bbl. for bags) ..... | \$3.25 | \$2.80 |
|----------------------------------------------------------------|--------|--------|

## COPPER SHEETS

|                                                            |       |  |
|------------------------------------------------------------|-------|--|
| At the mill, hot rolled, 16 oz. base-price, per lb...22½c. | 22½c. |  |
| (From jobber's warehouse add 2 to 3 cents.                 |       |  |
| Cold rolled add 1c. per lb. to hot rolled.)                |       |  |

## CORNER BEAD

|                |     |     |
|----------------|-----|-----|
| Per foot ..... | .05 | .05 |
|----------------|-----|-----|

## FIBRE

|                  |     |     |
|------------------|-----|-----|
| Per bushel ..... | .30 | .30 |
|------------------|-----|-----|





Photo Copyright, De'roit Pub. Co.

## From battleship to skyscraper--- "85% Magnesia" Conserves the Nation's Coal

THE battleship's mighty efficiency is measured by her ability to exploit every pound of coal without waste. Consequently, all boilers and steam pipes must be insulated with the most effective Heat-Insulation obtainable.

For this purpose the U. S. Navy has, since 1888, specified "85% Magnesia" coverings on all its ships, —to defend their steam and conserve their coal. The U. S. Shipping Board followed suit.

For many years, our best-built mercantile ships and tugs have also used "85% Magnesia" for the same end.

Our American locomotives are protected by "85% Magnesia," to conserve steam and coal. Our most progressive power-plants, big and small, are already insulated with "85% Magnesia," on boilers and pipes—to get greatest power from least fuel.

THE skyline of New York, colossal and graceful, is equalled by no other city in the world. By day, a monument of commercial supremacy. By night, a blaze of glory.

But,—facing every wind, bare to every wintry blizzard, how are these towering skyscrapers kept warm? You, who perhaps can scarcely keep three floors warm, find those topmost office suites comfortable. Why?

The Answer is:—*Nine-tenths of all of New York's largest buildings insulate their heating systems with "85% Magnesia" covering.*

Hundreds of miles of steam pipes, cutting through party walls, running under city streets, are thus protected. Thousands of tons of coal burned—but waste is eliminated.

Every available particle of heat is delivered where it is needed. Other-

wise, winter life in these giant structures would be impossible.

That same "85% Magnesia" insulation is used in the best made public buildings, institutions, hotels, apartment-houses, and in many thousands of residences, to exploit heat on least fuel.

*You are vitally concerned in the saving of coal. "85% Magnesia" is the supreme Heat-Insulation and Coal Saver.*

### Definite Proofs

For two years the Mellon Institute of Industrial Research has conducted experiments to prove the definite degree of its efficiency under varying conditions of temperature and pressure. A Table of the Monthly Coal Savings in Dollars and Cents by use of "85% Magnesia" has been prepared by this Institute, and the Magnesia Association will mail it to you for the asking. Also the illuminating booklet, "Let '85% Magnesia' Defend Your Steam." If you are an engineer or architect, ask us for the Specification for the scientific application of "85% Magnesia," compiled and endorsed by the above Institute.

Copyright 1919, M. A. of A.

—Permission to reprint by application.

MAGNESIA ASSOCIATION  
of AMERICA



721 Bulletin Building  
Philadelphia, Penna.

EXECUTIVE COMMITTEE, Wm. A. Macan, *Chairman*  
George D. Crabbs, The Philip Carey Co., Cincinnati, Ohio J. R. Swift, The Franklin Manufacturing Co., Franklin, Penna.  
Alvin M. Ehret, Ehret Magnesia Manufacturing Co., Valley Forge, Pa. Richard V. Mattison, Jr., Keasbey & Mattison Co., Ambler, Penna.



# Late Quotations in Building Material Markets

Continued from page 772-A

| GALVANIZED SHEETS             |          |         |
|-------------------------------|----------|---------|
|                               | New York | Chicago |
| Nos. 18 and 20 gauge, per lb. | \$6.12   | \$6.12  |
| No. 26                        | 6.42     | 6.42    |
| No. 27                        | 6.57     | 6.57    |

| GLASS                                            |     |     |
|--------------------------------------------------|-----|-----|
| (Discounts from manufacturer's price lists)      |     |     |
| Single strength, A quality, first three brackets | 77% | 77% |
| Single strength, B quality                       | 77% | 77% |
| Double strength, A quality                       | 79% | 79% |
| Double strength, B quality                       | 81% | 81% |
| Plate—up to 5 sq. ft.                            | 82% | 82% |
| Plate—over 5 sq. ft.                             | 84% | 84% |
| Plate—up to 10 sq. ft.                           | 83% | 83% |
| Plate—over 10 sq. ft.                            | 82% | 82% |

| GRAVEL                                             |        |        |
|----------------------------------------------------|--------|--------|
| 1 1/4 in. (Borough of Manhattan only), per cu. yd. | \$2.75 | \$2.35 |
| 3/4 in. (Borough of Manhattan only), per cu. yd.   | 2.75   | 2.35   |

| GYPSUM                                             |          |          |
|----------------------------------------------------|----------|----------|
| Delivered at job, Boroughs of Manhattan and Bronx. |          |          |
| 27 x 28 x 1                                        | 35c.     | 35c.     |
| 27 x 48 x 1/2                                      | 30c.     | 30c.     |
| 32 x 36 x 1/4                                      | 21c.     | 25c.     |
| 32 x 36 x 3/8                                      | 21c.     | 26c.     |
| 32 x 36 x 1/2                                      | 23 1/2c. | 23 1/2c. |

| Plaster Blocks:                                    |          |          |
|----------------------------------------------------|----------|----------|
| Delivered at job, Boroughs of Manhattan and Bronx. |          |          |
| 2 in. solid, per sq. ft.                           | 7 1/2c.  | 7 1/2c.  |
| 3 in. solid, 12 x 30, per sq. ft.                  | 10 1/2c. | 10 1/2c. |
| 3 in. hollow                                       | 10 1/2c. | 10c.     |
| 4 in. hollow                                       | 12 1/2c. | 11c.     |
| 6 in. hollow                                       | 17 1/2c. | 17 1/2c. |

| LATH                            |         |         |
|---------------------------------|---------|---------|
| Eastern spruce, per thousand    | \$6.70* | \$6.70* |
| No. 1 white pine, per thousand  | 6.50    | 6.50    |
| No. 1 hemlock, per thousand     | 6.00    | 6.00    |
| No. 1 yellow pine, per thousand | 6.25*   | 5.25    |

| LEAD                  |            |            |
|-----------------------|------------|------------|
| American pig, per lb. | 5 1/2 to 6 | 5 1/2 to 6 |
| Bar, per lb.          | 7 1/2 to 8 | 6 to 6 1/2 |

| LIME                               |        |        |
|------------------------------------|--------|--------|
| Common, 300 lb. bbls., per bbl.    | \$2.50 | \$1.40 |
| Finishing, 300 lb. bbls., per bbl. | 3.70   | 3.70   |
| Hydrated, in paper bags, per ton   | 17.25  | 17.00  |

| LUMBER                                         |          |         |
|------------------------------------------------|----------|---------|
| (Retail prices per M, F.O.B.)                  |          |         |
| Yellow pine, 2 x 4                             | \$53.50* | \$47.00 |
| Yellow pine, 2 x 6                             | 50.00*   | 45.00   |
| Yellow pine, 4 x 4                             | 60.50*   | 52.00   |
| Yellow pine, 8 x 8                             | 69.50*   | 52.00   |
| Yellow pine, 12 x 12                           | 57.00*   | 57.00   |
| Yellow pine, No. 1 boards, 1 x 6               | 60.25*   | 53.00   |
| Yellow pine, No. 1 boards, 1 x 12              | 62.50*   | 56.00   |
| Yellow pine, B and better flooring (plain)     | 62.50*   | 57.00   |
| Yellow pine, 8 and better flooring (quartered) | 74.50*   | 70.00   |
| Douglas fir, 6 x 6 to 12 x 12                  | 62.50    | 63.00   |
| Douglas fir, 12 x 14 to 14 x 14                | 64.00    | 64.00   |
| Norway pine, 2 x 4                             | 60.00    | 50.00   |
| Norway pine, 2 x 12                            | 65.00    | 57.00   |
| Hemlock, 2 x 4                                 | 47.50    | 46.00   |
| Hemlock, 2 x 12                                | 51.00    | 48.00   |
| Oak flooring, 13/16 quartered white            | 144.50*  | 122.00  |
| Oak flooring, 13/16 quartered red              | 136.00*  | 115.00  |
| Oak flooring, 13/16 plain white                | 94.50*   | 82.00   |
| Oak flooring, 13/16 plain red                  | 94.50*   | 82.00   |
| Maple flooring, 13/16 clear                    | 86.00*   | 72.00   |
| Maple flooring, 13/16 select                   | 82.00*   | 69.00   |
| Maple flooring, 13/16 No. 1 fancy              | 74.50*   | 58.00   |
| Mahogany, 1" F. A. S.                          | 300.00   | 300.00  |
| Quartered oak, 1" F. A. S.                     | 180.00   | 135.00  |
| Plain oak, 1" F. A. S.                         | 120.00   | 100.00  |
| Red gum, 1" F. A. S.                           | 87.00    | 70.00   |
| Sap gum, 1" F. A. S.                           | 56.00    | 60.00   |
| Chestnut, 1" F. A. S.                          | 87.50    | 75.00   |
| Poplar, 1" F. A. S.                            | 130.00   | 100.00  |
| Birch, 1" F. A. S.                             | 70.00    | 65.00   |
| Spruce, random 2"                              | 52.00    | 50.00   |
| Spruce, wide                                   | 62.50    | 60.00   |

| METAL LATH                     |      |      |
|--------------------------------|------|------|
| Under 100 sq. yd., per sq. yd. | 40c. | 40c. |

| MORTAR COLORS      |     |     |
|--------------------|-----|-----|
| Red, per lb.       | .05 | .05 |
| Brown, per lb.     | .05 | .05 |
| Chocolate, per lb. | .05 | .05 |
| Black, per lb.     | .05 | .05 |

| OILS                               |        |        |
|------------------------------------|--------|--------|
| Linseed, city, raw                 | \$1.90 | \$1.90 |
| Linseed, boiled, advance, per gal. | .01    | .01    |
| Out of town, American seed at      | 1.90   | 1.90   |

| PAINTS                                             |                  |                  |
|----------------------------------------------------|------------------|------------------|
| Leads:                                             |                  |                  |
| American white, in oil, kegs; lots over 100 lbs.   | 14c.             | 14c.             |
| White, in oil, 25-lb. tin pails; add to keg price. | 1/4c.            | 1/4c.            |
| Red, bbl., 1/2 bbl. and kegs; lots over 100 lbs.   | 14 1/2c.         | 14 1/2c.         |
| Dry Colors:                                        |                  |                  |
| Red Venetian, American, per 100 lbs.               | \$2.75 to \$5.00 | \$2.00 to \$5.00 |

| Metallic Paints: |                    |                  |
|------------------|--------------------|------------------|
| Brown, per ton   | \$24.00 to \$32.00 | New York Chicago |
| Red, per ton     | 24.00 to 30.00     | 24.00 to 32.00   |

| PIPE              |          |          |
|-------------------|----------|----------|
| 6 in. and heavier | \$52.10† | \$51.80† |
| 4 in.             | 55.70†   | 54.80†   |
| 3 in.             | 62.70†   | 61.80†   |

(and \$1 additional for Class A and gas pipe.)  
(Discounts to jobbers for carload lots on the Pittsburgh basing card; freight rates from Pittsburgh to New York, and also from Pittsburgh to Chicago, in carloads, per 100 lbs., are 27c.)

| Wrought:                |                   |          |
|-------------------------|-------------------|----------|
| Steel:                  |                   |          |
| Black, 1/8 to 3 in.     | 50 1/2%           | 57 1/2%  |
| Galv., 1/8 to 3 in.     | 24 to 44%*        | 41 %     |
| Iron:                   |                   |          |
| Black, 1/8 to 1 1/2 in. | 29 1/2 to 39 %    | 39 1/2%  |
| Galv., 1/8 to 1 1/2 in. | 2 1/2 to 23 1/2 % | 23 1/2 % |

| Steel:                |         |         |
|-----------------------|---------|---------|
| Butt Weld             |         |         |
| Black, 2 1/2 to 6 in. | 53 1/2% | 53 1/2% |
| Galv., 1/8 to 3 in.   | 41 %    | 41 %    |
| Iron:                 |         |         |
| Black, 2 1/2 to 6 in. | 34 1/2% | 34 1/2% |
| Galv., 2 1/2 to 6 in. | 21 1/2% | 21 %    |

| PLASTER                                   |         |         |
|-------------------------------------------|---------|---------|
| Neat wall cement in 15 cent bags, per ton | \$20.30 | \$18.50 |
| Finishing plaster                         | 24.00   | 21.00   |

| PUTTY                               |        |        |
|-------------------------------------|--------|--------|
| In bladders, per 100 lb.            | \$6.25 | \$6.25 |
| In 1-lb. to 5-lb. tins, per 100 lb. | 6.75   | 6.75   |

**RADIATION**  
(A further discount, effective April 4, of 15% on direct radiators, 12 1/2% on wall radiators, and 10% on steam and hot water boilers is announced. This approximates a drop of 36% on radiators and 33% on boilers from prices in effect before the 1st of January, 1919.)  
Chicago reports a 57% discount on standard heights.

| REGISTERS                                                                                                    |     |     |
|--------------------------------------------------------------------------------------------------------------|-----|-----|
| Cast iron semi-steel or steel, in black or white japan or electro plate and small faces and borders          | 40% | 40% |
| Wall frames                                                                                                  | 40% | 40% |
| Large faced, 14 x 14 in. and larger                                                                          | 60% | 60% |
| Base board registers                                                                                         | 40% | 40% |
| Base board intakes                                                                                           | 40% | 40% |
| White enameled goods                                                                                         | 15% | 15% |
| Solid brass or bronze goods, except grilles                                                                  | net | net |
| Grilles in black and white japan or electroplate in cast iron, plain lattice design—smaller than 14 x 14 in. | 40% | 40% |
| —Less than 14 x 14 in.                                                                                       | 60% | 60% |

| REINFORCING BARS            |         |         |
|-----------------------------|---------|---------|
| High carbon steel from mill | \$48.50 | \$49.50 |
| Medium steel from mill      | 48.50   | 49.50   |

| ROOFING MATERIAL                                                                           |                    |         |
|--------------------------------------------------------------------------------------------|--------------------|---------|
| Tarred Paper:                                                                              |                    |         |
| 1-Ply, per ton, per roll, 108 sq. ft.                                                      | \$63.00 to \$65.00 | \$65.00 |
| 2-Ply                                                                                      | 95c.               | 95c.    |
| 3-Ply                                                                                      | 1.23 to 1.30       | 1.30    |
| Rosin sized sheathing                                                                      | per ton 60.00      | 60.00   |
| Corrugated roofing, galvanized, 2 1/2 in. corrugation, over flat sheets, 30c. per 100 lbs. |                    |         |

| SAND                 |        |        |
|----------------------|--------|--------|
| Mason, per cu. yd.   | \$1.80 | \$2.25 |
| Torpedo, per cu. yd. | 1.80   | 2.35   |

| SHINGLES                                      |         |        |
|-----------------------------------------------|---------|--------|
| Red cedar, 5 to 2, clear, per thousand        | \$8.50* | \$6.50 |
| White cedar, extra star, A star, per thousand | 7.40*   | 5.50   |

| SLATE ROOFING                    |                  |                    |
|----------------------------------|------------------|--------------------|
| F.O.B. cars,                     |                  |                    |
| Pennsylvania:                    | Quarry Station   | F.O.B. Chicago     |
| Best Bangor                      | \$7.75 to \$9.00 | \$10.20 to \$11.45 |
| No. 1 Bangor Ribbon              | 6.75 to 7.25     | 9.20 to 9.70       |
| Pen Argyl                        | 7.25 to 8.00     | 9.70 to 10.45      |
| Peach Bottom                     | 10.00 to 12.50   | 12.45 to 14.45     |
| No. 1 Chapman                    | 7.25 to 8.25     | 8.70 to 9.95       |
| Vermont:                         |                  |                    |
| No. 1 Sea Green                  | 3.50 to 6.75     | 5.95 to 9.20       |
| Unfading Green                   | 5.50 to 9.25     | 8.30 to 11.05      |
| Red                              | 12.00 to 20.00   | 14.80 to 22.80     |
| Maine:                           |                  |                    |
| Brownsville, U'f'g Black, No. 1. | 11.00 to 12.00   | 14.10 to 15.10     |
| Slaters felt, 30 lb. roll        | 1.75             | .....              |
| Slaters felt, 40 lb. roll        | 2.25             | .....              |

| SPIRITS TURPENTINE |         |         |
|--------------------|---------|---------|
| Per bbl.           | .66 1/2 | .66 1/2 |


| STONE SCREENINGS  |        |        |
|-------------------|--------|--------|
| Lime, per cu. yd. | \$2.35 | \$2.35 |

| STRUCTURAL STEEL                        |        |        |
|-----------------------------------------|--------|--------|
| Beams and channel, 3 to 15 in., per lb. | 2.45c. | 3.47c. |
| Beams and channel, over 15 in., per lb. | 2.45c. | 3.57c. |
| Angles, 3 to 6 in.                      | 2.45c. | 3.47c. |
| Zeas and tees                           | 2.45c. | 3.47c. |
| Steel bars, half extras, from mill      | 2.35c. | 3.47c. |


| STUCCO                           |       |         |
|----------------------------------|-------|---------|
| In cloth, per ton (white, mixed) | ..... | \$21.50 |



# A Permanent Solution of the Door-Bell Question



*The Wayne Bell Ringing Transformer*  
Household size. Finished  
in olive green enamel.



**A** DETAIL of refinement in the electrical installation well worthy of the architect's attention is the Wayne Bell Ringing Transformer.

The household size, about the size of a baseball and weighing about a pound, replaces dry batteries for bell ringing. It is connected to the standard alternating current lighting circuit and has ample capacity for door-bells and residential signal systems.

There are also larger sizes for annunciator systems in clubs, hotels, large apartment houses, fire stations, factories and mines.

These miniature transformers are inexpensive, easy to install, consume an infinitesimal amount of current, and last indefinitely. Wayne Bell Ringing Transformers end door-bell troubles for all time and do away with battery renewals. They represent an improvement which, wherever installed, gives additional value to the property. They are approved by the Underwriters' Laboratories.

*The name General Electric Company on an electrical device is a guarantee of quality backed by over a quarter-century's experience in the generation, transmission, distribution and application of electricity.*

**Wayne Bell Ringing Transformers**  
*can be furnished by any reputable electrical contractor*

**General Electric**  
General Office **Company** Schenectady, N.Y.



# BUILDING NEWS

*To be of value this matter must be printed in the number immediately following its receipt, which makes it impossible for us to verify it. Our sources of information are believed to be reliable, but we cannot guarantee the correctness of all items. Persons in charge of proposed work are requested to send us information concerning it as early as possible; also corrections of any errors discovered.*

## ALABAMA

ALBANY, ALA.—Southern Cotton Oil Co., First National Bank Building, Montgomery, plans to increase capacity of mixing plant and build gin. \$50,000.

BIRMINGHAM, ALA.—Board of Education, Jefferson County, will build one story brick and stone addition for Shades Cahaba High School. D. O. Whildin, Title Building, Architect. \$50,000.

## ARIZONA

MESA, ARIZ.—High School Trustees plan election May 10 to vote on \$100,000 bonds to build additions to high school. H. E. Matthews, principal.

PHOENIX, ARIZ.—Phoenix Wholesale Meat & Produce Co., Fifteenth Avenue and River Street, Triholet Packing Co., Thomas Road, and Toyrea Packing Co., Bisbee, are organizing company and plan to build packing plant here to include refrigeration and ice manufacturing plant. \$500,000.

## ARKANSAS

JONESBORO, ARK.—V. C. Kays, president State Agricultural School, will construct a brick engineering building and brick Y. M. C. A. building.

LITTLE ROCK, ARK.—G. I. Dill Tractor Mfg. Co., Harrisburg, has acquired 10-acre site here and plans to build large reinforced-concrete fireproof factory. G. I. Dill, president.

## CALIFORNIA

ANAHEIM, CAL.—School Trustees having plans prepared by T. C. Kistner, Architect, American National Bank Building, San Diego, building two schools, one on Central School site; other on site to be purchased on east side of town.

COVINA, CAL.—Covina Citrus Association plans to build concrete and timber packing pre-cooling plant. W. W. Bennett, manager. \$125,000.

COVINA, CAL.—School Trustees having plans prepared by J. C. Austin, Architect, 1120 Baker-Detwiler Building, Los Angeles, for two schools, one to consist of four classrooms and auditorium; other eighteen classrooms and manual training building. \$150,000.

EL CENTRO, CAL.—Imperial Valley Milk Producers Association purchased site and plans to build 150 x 300 ft. plant on Main Street. \$150,000.

EL CENTRO, CAL.—Board of Supervisors, Imperial County, plan to build courthouse. \$250,000.

FRESNO, CAL.—H. A. Sells & Co., 829 J Street, let contract for building one story, 80 x 150 ft., reinforced concrete garage and shop on J and Monterey Streets to A. Mattei, I and Los Angeles Streets. \$30,000.

FT. BOWLING, CAL.—Commissioners of Indian Affairs, Washington, D. C., will construct a schoolhouse here.

IMPERIAL, CAL.—City will vote on \$90,000 bonds to build school. D. C. Gale, school trustee.

LOS ANGELES, CAL.—Board of Education proposes the construction of a new school building on the Nevins School site, 1569 E. Thirty-second Street. John P. Austin, Architect. \$115,000.

MODESTO, CAL.—Modesto Gas Co. plans to build gas generating unit, 300,000 cu. ft. steel gas holder, install two purifiers and extend gas mains to new sections of city. \$65,000.

NORWALK, CAL.—State Board Control, Sacramento, appropriated \$150,000 bonds to construct new building at hospital here. W. F. McClure, State Engineer.

SAN FRANCISCO, CAL.—Anderson & Ringrose were lowest bidders for constructing the Park-Presidio School at \$87,600.

SAN FERNANDO, CAL.—San Fernando Lemon Association let contract for two story, 100 x 199 ft., reinforced concrete, hollow tile and frame packing house on Brand Blvd., to Hamm & Shepherd, 205 Central Building, Pasadena. \$30,000.

SANTA MONICA, CAL.—Board of Education will vote on \$30,000 bonds to build concrete amphitheater on high school grounds and \$75,000 for brick addition to Washington and John Adams schools. Allison & Allison, 1405 Hibernian Building, Los Angeles, Architects.

TULARE, CAL.—City voted \$60,000 bonds to build auditorium and city hall. F. W. Eldridge, clerk.

TULARE, CAL.—City voted \$90,000 to build two schools. F. W. Eldridge, clerk.

VENTURA, CAL.—State Board of Control, Sacramento, appropriated \$90,000 bonds to construct building at girls' reform school here. W. F. McClure, State Engineer.

WHITTIER, CAL.—State Board of Control, Sacramento, appropriated \$64,000 bonds to construct building at boys' reform school here. W. F. McClure, State Engineer.

## CONNECTICUT

BRIDGEPORT, CONN.—R. Poladian, 172 Wade Street, will build two story, 60 x 80 ft., brick and timber factory. \$25,000.

BRIDGEPORT, CONN.—F. H. Beckwith, Architect, 10 Post Office Arcade, has plans for building five story, 75 x 86 ft. brick and terra cotta hotel on Golden Hill Street. \$100,000.

BRISTOL, CONN.—Barnes-Wallace Co., 30 Main Street, proposes building one story, 60 x 100 ft. fireproof addition to factory. \$25,000.

HAMDEN, CONN. (New Haven P. O.)—Yale Tire & Rubber Co., care of J. E. Hubinger, president, 827 Main Street, New Haven, recently organized, plans to build factory and power house on Dixwell Avenue here. \$100,000.

HARTFORD, CONN.—E. M. Stone, Architect, 327 Trumbull Street, will build seven story fireproof garage and one story salesroom on Ann Street for C. P. Cooley, 36 Pearl Street. \$90,000.

NEW HAVEN, CONN.—H. W. Walker, 421 Housatonic Avenue, Bridgeport, proposes building one-story, 72 x 113 ft., brick and concrete warehouse, on James and River Streets, here. Sullivan & McKeon, 843 Dixwell Avenue, have contract. \$30,000.

SOUTH MANCHESTER, CONN.—Cheney Bros., Hartford Road, let contract for three story, 50 x 80 ft., reinforced-concrete storehouse, on Elm Terrace, to Abertshaw Construction Co., 27 School Street, Boston, Mass. \$40,000.

SOUTH MANCHESTER, CONN.—G. E. Keith Furniture Co., 829 Main Street, purchased site on Main and Bissell Streets, and plans to construct one and three story, 50 x 280 ft., furniture and business building with storehouse in rear.

WATERBURY, CONN.—M. Joseloff, 17 Brown Place, soon receives bids for building three story, 50 x 132 ft. fireproof warehouse and grocery on South Leonard Street. F. A. Webster, Waterville, Architect. \$75,000.

## DELAWARE

WILMINGTON, DEL.—Wilmington Free Institute will build two story, 90 x 200 ft., steel and brick library. Boring & Tilton, 52 Vanderbilt Avenue, New York City, Architects. \$400,000.

## DISTRICT OF COLUMBIA

WASHINGTON, D. C.—Holmes & Winslow, Architects, 110 West Fortieth Street, New York City, are designing one story, 25 x 139 ft., brick and steel bank on Fifteenth and I Streets, for Liberty Savings Bank, 1410 New York Avenue, N. W. \$100,000.

## FLORIDA

DAYTONA, FLA.—City Commissioners soon receive bids for brick and stone hall. S. H. Cove and J. Espedahl, Daytona, Architects. \$50,000.

KEY WEST, FLA.—Norberg-Thompson are receiving bids for cold storage and distilling plant. \$60,000.

## ILLINOIS

CHICAGO, ILL.—Hydrox Co., 3543 Normal Avenue, let contracts for building three story, reinforced-concrete ice and ice cream factory, on Lake Park Avenue and Twenty-fourth Street, to Midland Eng. & Constr. Co., 332 South Michigan Avenue. \$225,000.

EAST ST. LOUIS, ILL.—Illinois State Bank, Missouri Avenue, plans to build 25 x 120 ft. addition. Cost to exceed \$50,000.

GRANITE CITY, ILL.—M. Carney, Architect, Wright Building, East St. Louis, has plans for building one and two story, 100 x 125 ft., brick and steel warehouse on Elm Street and Broadway for Southern Mfg. Co., 320 Elm Street, East St. Louis. \$50,000.

## INDIANA

EVANSVILLE, IND.—The M. J. Hoffman Construction Co. of this city was awarded contract for constructing an addition to the Haynes automobile plant. \$450,000.

INDIANAPOLIS, IND.—The following contracts were awarded by State Board of Agriculture: Thomas Monahan, Indianapolis, Ind., for the new manufacturers' building, at \$120,000; T. W. Stoolman, Champaign, Ill., for the new woman's building, at \$120,000.

INDIANAPOLIS, IND.—C. P. Conder and Elmer J. Culbertson, general contractors, 31 East Georgia Street, will construct a building at 1220 North Illinois Street. \$135,000.

## IOWA

AMES, IOWA.—State College soon receives bids for building four story library on campus, cost \$300,000; three story armory, \$200,000. Proudfoot, Bird & Rawson, 810 Hubbell Building, Des Moines, Architects.

SIOUX CITY, IOWA.—Burrell Engineering & Construction Co. of Chicago, Ill., has contract for constructing elevator for the Terminal Grain Co.

## KENTUCKY

LOUISVILLE, KY.—Louisville Cotton Seed Oil Co., 1318 McHenry Street, plans to rebuild plant recently destroyed by fire. Loss \$500,000.

## MARYLAND

ANNAPOLIS, MD.—Contract was awarded by the Government to Levering & Garrigues for the building of a steamship and navigation building at the Naval Academy at Annapolis.

BALTIMORE, MD.—Architects Flourney & Flourney, 1417 Johns Street, are preparing plans for eighteen residences at Guilford Terrace and University Avenue.

BALTIMORE, MD.—Architect E. L. Palmer, 513 North Charles Street, is preparing plans for a residence to cost \$30,000.

BALTIMORE, MD.—Architect W. O. Sparkin, 1402 Fidelity Building, is preparing plans for a laundry and dance hall at Havre de Grace to cost \$18,000.

BALTIMORE, MD.—Architect Fred E. Beall, 1335 North Gilmer Street, is preparing plans for thirty-four residences on Ashburton Street, between Riggs and Winchester Streets.

BALTIMORE, MD.—M. Filmore Carter, Helton and Mulberry Streets, is having plans drawn for four residences at 2200, 2202, 2204 and 2206 Rosedale Street.

BALTIMORE, MD.—Architect Clyde N. Friz, Munsey Building, is preparing plans for a church and Sunday school at St. Paul Street and North Avenue to cost \$100,000.

BALTIMORE, MD.—Hutzler Bros. Co., 212 North Howard Street, plans to build one and two story, 60 x 60 x 154 ft., reinforced concrete, steel and brick garage on Saratoga and State Streets. J. Pennington, 601 Professional Building, Architect. \$50,000.

BALTIMORE, MD.—Helwig & Leight, 1533 Gorsuch Avenue, let contract for building two story, 48 x 90 ft., concrete and brick addition to factory at 1529 Gorsuch Avenue to G. A. Gebb, 1347 Gorsuch Avenue. \$50,000.

BALTIMORE, MD.—H. S. Wampole Co., 761 Columbia Avenue, proposes building four story, 25 x 30 ft., concrete, steel and brick factory, on Barre and St. Peter Streets. \$35,000.

BALTIMORE, MD.—Hess Steel Corporation, Biddle Street and Loney Lane, let contract for constructing one story, 60 x 160 ft., shipping building and one story, 60 x 200 ft., annealing plant, concrete, steel and brick, on Biddle Street and Loney Lane, to Dietrich Bros., Pleasant and Davies Streets. \$150,000.

## MASSACHUSETTS

BOSTON, MASS.—Adams Pond Co., Dorchester, will build two story, 50 x 100 ft., reinforced concrete supply house on Commonwealth Street here. \$30,000.

BOSTON, MASS.—C. C. Whittemore plans to build two story, 32 x 135 ft. brick and concrete storage plant on Boylston and Ipswich Streets. \$30,000.

BROCKTON, MASS.—Donnelly Machine Co., 26 North Montello Street, let contract for building two story, 40 x 177 ft., brick addition to machine shop to D. E. Green, 56 Taber Avenue. \$35,000.

CAMBRIDGE, MASS. (Boston P. O.)—Cambridge Gas Co. let contract for building one story, 66 x 92 ft. brick and concrete garage and repair shop on Potter Street to W. A. Wentworth Co., 15 Exchange Street, Boston, Mass. \$50,000.



JONES & FURBRINGER, Architects.



*Artistic  
Lighting  
Fixtures  
for  
Apartment Houses  
and  
Investment Homes*

**A** DEFINITE DEPARTURE from all stereotyped forms characterizes our new series of electric lighting fixtures. We have adopted and are continuously developing original designs of conservative distinctiveness which lend themselves admirably to a wide variety of architectural creation. In this way, the builder of the apartment house or the investment home may be especially served.

We believe that our new fixtures are peculiarly successful in interpreting the thought of the architect. By the employment of efficiency methods we are enabled to produce them with truly remarkable results at a moderate cost and at a most opportune time.

We would esteem it a pleasure to show you these fixtures now on exhibition at our show rooms, or if we may hear from you to forward plates of these new designs.

We further call attention to the value of scientific lighting, and to the fact that for more than half a century Mitchell Vance Co., Inc., has studied the complexities of interior lighting. The services of our engineers in solving such problems are at your disposal or that of your clients.

**MITCHELL VANCE CO., INC.**  
Electric Lighting Fixtures

503-511 West 24th Street

New York City



FALL RIVER, MASS.—J. J. Burke plans to build two story, 50 x 150 ft. brick and reinforced concrete garage. Fallows & McLaughlin, 56 North Main Street, Architects. \$30,000.

GARDNER, MASS.—Central Oil & Gas Stove Co. proposes building one story, 50 x 120 ft. and three story, 40 x 50 ft. brick, steel and concrete additions to factory. \$40,000.

HOLYOKE, MASS.—Goetz Silk Mfg. Co., 642 South Sumner Street, proposes building brick and steel addition to plant. C. T. Main, 201 Devonshire Street, Boston, Engineer. \$60,000.

NEW BEDFORD, MASS.—Fairhaven Mills, 115 Coggeshall Street, let contract for building one story, 200 x 300 ft. brick and mill construction addition to mill to C. Ranger Construction Co., 20 Bond Street, Holyoke. \$125,000.

SPRINGFIELD, MASS.—National Equipment Co., 662 North Main Street, plans to build three story, 100 x 372 ft. and 35 x 162 ft. reinforced concrete addition to factory. \$200,000.

SPRINGFIELD, MASS.—Chaplin Realty Trucking Co., 296 Belmont Avenue, will build one-story, 48 x 112 ft., brick and concrete garage. \$25,000.

SWANSEA, MASS.—Swansea Dye Works will build two story, 50 x 100 ft. brick and steel addition to bleach house. \$25,000.

WARREN, MASS.—Warren Steam Pump Co. will build one story, 85 x 200 ft. factory, one story, 40 x 130 ft. boiler house, and one story, 40 x 130 ft. office addition, brick and concrete. \$75,000.

WORCESTER, MASS.—W. H. Sawyer Lumber Co., 66 Lincoln Street, let contract for building one-story brick lumber yard, to include office, shed and kilns, to J. Miles & Sons Co., 392 Main Street. \$50,000.

#### MICHIGAN

LANSING, MICH.—W. E. Wood Co. was awarded contract for the new State office building at \$815,293.

DETROIT, MICH.—North Woodward Methodist Episcopal congregation, care W. E. N. Hunter, Architect, 1306 Chamber Commerce, is having plans prepared for building two story, 180 x 250 ft., brick, steel and stone church, on Woodward Avenue. \$500,000.

PONTIAC, MICH.—City voted on \$1,000,000 bonds to build two sixteen room and one twenty-four room schools; also two additions to present high school.

#### MINNESOTA

BUHL, MINN.—Board of Education, St. Louis County, District No. 35, is having plans prepared by A. W. Kerr, Architect, 5 American Exchange Building, Virginia, for building three story, reinforced, concrete and brick high school, on Chestnut Street. \$250,000.

DULUTH, MINN.—Consolidated Elevator Co., 518 Lyceum Building, let contract for building, reinforced-concrete, grain elevator, on Fairfield Avenue and water front, to Barnett & Record Co., 415 Lyceum Building. \$250,000.

FERGUS FALLS, MINN.—State Board of Control, St. Paul, is having plans prepared by C. H. Johnson, Architect, 715 Capital Bank Building, St. Paul, of reinforced-concrete and brick dormitory here. \$50,000.

HASTINGS, MINN.—State Board of Control, St. Paul, proposes building one story, 45 x 140 ft., reinforced concrete and brick power plant here. C. H. Johnston, 715 Capital Bank Building, St. Paul, Architect. \$125,000.

HASTINGS, MINN.—State Board of Control, St. Paul, will build 50 x 120 ft. reinforced concrete and brick dormitory. C. H. Johnston, 715 Capital Bank Building, St. Paul, Architect. \$60,000.

LE SUEUR, MINN.—Minnesota Valley Canning Co. let contract for canning factory to J. B. Nelson & Co., 503 Belgrade Avenue, Mankato. \$25,000.

MINNEAPOLIS, MINN.—Minneapolis Steel & Machinery Co., Minnehaha Avenue and Twenty-ninth Street, plans to build two story, 70 x 100 ft., brick club on Twenty-seventh Avenue, S. \$70,000.

MINNEAPOLIS, MINN.—Board of Education will build 63 x 116 ft. reinforced concrete and brick addition to Francis E. Willard School on Queen Street and Sixteenth Avenue, N. Bureau of Buildings, Divisions, Design and Inspection of Business Superintendent's Department, Board of Education, Architects. \$90,000.

MINNEAPOLIS, MINN.—A. D. Walker, 807 Hennepin Avenue, and Pence Automobile Co., 800 Hennepin Avenue, will build twelve-story, granite and brick garage and office on Eighth Street and Hennepin Avenue. Long, Lamareaux & Long, Andrus Building, Architects. \$1,000,000.

MINNEAPOLIS, MINN.—Board of Education will build 61 x 92 ft. reinforced concrete and brick addition to George Bancroft School on Fourteenth Avenue, S., and Thirty-eighth Street. Bureau of Buildings, Divisions, Design and Inspection of Business Superintendent's Department, Board of Education, Architects. \$85,000.

ST. HILAIRE, MINN.—Board of Education plans to build two story, 57 x 90 ft., school. Dund & Dunham, 512 Essex Building, Minneapolis, Architects. \$50,000.

ST. PETER, MINN.—State Board of Control, St. Paul, will build two story dormitory, 45 x 140 ft., reinforced concrete and brick, here. C. H. Johnson, 715 Capital Bank Building, St. Paul, Architect. \$50,000.

WANAMINGO, MINN.—City is having plans prepared by Magney & Tusler, Architects, Builders' Exchange, Minneapolis, for two story, 58 x 93 ft., brick school. A. O. Berg, clerk. \$50,000.

WELLS, MINN.—City plans to build power plant, electrical distribution system and concrete reservoir. C. L. Pillsbury Co., 801 Metropolitan Life Building, Minneapolis, Engineers. \$40,000.

#### MISSOURI

JOPLIN, MO.—Christmas Dry Goods Co., Fifth and Main Streets, will build three-story, 104 x 120 ft., reinforced-concrete and brick warehouse, on Fourth Street and Virginia Avenue. C. Ludholtzer, 209 West Ninth Street, Architect. \$50,000.

OZARK, MO.—Christian Co. proposes soon building three story, 91 x 91 ft., concrete and brick court house. H. H. Hohenschild, Odd Fellows Building, St. Louis, Architect. \$100,000.

ST. LOUIS, MO.—Funston Bros. & Co., Second and Elm Streets, plan to build 8-story dyeing and dressing plant on river front. P. Fouke, care owner, engr. \$50,000.

ST. LOUIS, MO.—S. Hamburg, Jr., 2407 North Broadway, plans to build five story, 100 x 122 ft., reinforced concrete and steel service station and mercantile building on Leonard and Locust Streets. Cost will exceed \$50,000.

ST. LOUIS, MO.—W. H. McNicol & Bros., care of Weisels-Gerhart Real Estate Co., Eighth and Chestnut Streets, plan to build one story, 100 x 140 ft., garage and service station on McPherson Street, between Walton and Euclid Avenues. \$50,000 or more.

ST. LOUIS, MO.—Motor Garage & Realty Co., 46 Kingsbury Place, is having plans prepared for building three story, 250 x 250 ft., reinforced concrete, steel and brick garage on block bounded by Seventeenth, Eighteenth, Pine and Chestnut Streets. N. W. Ewing, president. \$300,000.

ST. LOUIS, MO.—E. A. Ganss, 9 North Seventh Street, plans to build six story hotel, 100 x 125 ft., on DeBaliere and Waterman Streets. Cost to exceed \$50,000.

ST. LOUIS, MO.—G. Wuest, Architect, Wainwright Building, has plans for building two story, 28 x 128 ft., reinforced-concrete, steel and brick, mercantile, at 208 North Seventh Street, for J. E. Kaime & Bros. Realty Co., De Menil Building. \$50,000.

ST. LOUIS, MO.—Essex Investment Co., Century Building, plans to build 80 x 100 ft. office, on Twelfth and Locust Streets. \$500,000.

#### NEW JERSEY

BAYONNE, N. J.—Board of Education plans to build school to replace P. S. No. 4. \$250,000.

BAYONNE, N. J.—Knights of Columbus, 669 Avenue C, plans to build three story brick clubhouse. \$200,000.

EAST ORANGE, N. J.—Board of Education is receiving competitive sketches for building school. \$150,000.

JERSEY CITY, N. J.—City will build schools Nos. 6, 23 and 37 in Greenville section. \$2,500,000.

JERSEY CITY, N. J.—Sons of Israel congregation plans to build synagogue on Grove Street. \$70,000.

LONG BRANCH, N. J.—Boring & Tilton, Architects, 52 Vanderbilt Avenue, New York City, are preparing plans for one story, 52 x 65 ft., brick and steel library for Long Branch Library. \$70,000.

NEW BRUNSWICK, N. J.—Flynn Brothers have contract for constructing a six room addition to the Washington School here at \$24,696.

PATERSON, N. J.—Sunburst Baking Co. is having plans prepared by The McCormick Co., Architects, Century Building, Pittsburgh, Pa., for building addition to bakery. \$30,000.

TRENTON, N. J.—Atlas Tire & Rubber Co. are having plans prepared by J. Hunt, Architect, 114 North Montgomery Street, for one story, 90 x 400 ft., brick and steel plant on Enterprise Avenue. \$225,000.

#### NEW YORK

ALBANY, N. Y.—Normanskill Farm Dairy Co., 120 South Swan Street, had plans prepared by R. Warden, Architect, for building four story brick factory at 126-128 Jay Street. C. P. Stevens, president. \$50,000.

BUFFALO, N. Y.—Wheat Ice Cream Co., 235 Elm Street, is having plans prepared by R. J. Reidpath & Son, Architects, Buffalo, for two story, 92 x 150 ft. reinforced concrete garage on Elm Street. \$50,000.

BROOKLYN, N. Y.—Maternity Hospital Society, 1666 Pitkin Avenue, is having revised plans prepared by Cohn Bros., Architects, 361 Stone Avenue, for building three story, 50 x 80 ft., brick and steel hospital, on Howard and Dumont Avenues. \$75,000.

BROOKLYN, N. Y.—Miller-Weiss Co., care Shampian & Shampian, Architects, 50 Court Street, will build one story, 75 x 100 ft., brick and steel theater, on Manhattan Avenue and Eagle Street. \$80,000.

BROOKLYN, N. Y.—A Rockmore, 50 Court Street, will build one story, 100 x 140 ft., brick and steel garage, on Forty-eighth Street, east of Second Avenue. \$35,000.

BROOKLYN, N. Y.—Rechnitz Bros., 44 Court Street, will build one story, 100 x 100 ft., brick and steel garage, on Coney Island Avenue, between Avenues H and I. \$25,000.

BROOKLYN, N. Y.—Realty Construction Co., 44 Court Street, will build one story, 92 x 200 ft., brick and steel garage, on Snyder and Flatbush Avenues. \$50,000.

BROOKLYN, N. Y.—T. S. Martin, 16 Court Street, will build one story, 130 x 235 ft., brick and steel garage, on St. Johns Place and Classon Avenue. \$75,000.

BROOKLYN, N. Y.—W. Bauer, care Shampian & Shampian, Architects, 50 Court Street, will build three story, 60 x 100 ft., brick and steel garage, on Vanderbilt and De Kalb Avenues. \$50,000.

BROOKLYN, N. Y.—L. Hirsch & Sons, care B. W. Dorfman, Architect, 26 Court Street, will build four story, 110 x 150 ft., brick, steel and concrete factory, on Thames and Porter Streets and Flushing Avenue. \$150,000.

BROOKLYN, N. Y.—M. A. Cantor, Architect, 373 Fulton Street, has planned building one story, 200 x 300 x 400 ft., brick and steel factory, on Rockaway and Church Avenues, for Hudson Bag Co., Inc., 77 Washington Avenue. \$150,000.

BROOKLYN, N. Y.—I. Birnbaum, 303 Oakland Avenue, is having plans prepared by G. Erda, Architect, 826 Manhattan Avenue, for building one story, 25 x 200 ft., brick and steel theater, on Manhattan and Norman Avenues. \$65,000.

HORNELL, N. Y.—Bethesda Hospital, North Hornell, plans to build Roosevelt Memorial Hospital here. Address L. S. Alger, Hornell. \$200,000.

MT. VERNON, N. Y.—Mr. Vernon Baptist congregation plans to build one story church. W. F. Tilton, chairman building committee. H. W. Jones, 739 Metropolitan Bank Bldg., Minneapolis, Minn., Architect. \$150,000.

NEW YORK, N. Y.—Baker, Carver & Morrell, 37-39 Water Street, soon receives bids for altering eight story brick and steel warehouse. Severence & Van Allen, 4 West Thirty-seventh Street, Architects. \$80,000.

NEW YORK, N. Y.—McCormick Co., Architects, 41 Park Row, is preparing plans for two story, 139 x 155 x 69 x 134 ft. brick and steel bakery on 165th Street and Park Avenue. \$100,000.

NEW YORK, N. Y.—New York Telephone Co., 15 Dey Street, had plans prepared by McKenzie, Voorhees & Gmelin, Architects, 1123 Broadway, for building four story, 103 x 115 ft., brick and steel exchange, on 167th Street and Grand View Place. \$391,000.

NEW YORK, N. Y.—League for Political Education, 15 West Forty-fourth Street, is having plans prepared by McKim, Mead & White, Architects, 101 Park Avenue, for five story, 100 x 125 ft., brick and steel institute on Forty-third Street and Broadway. \$150,000.

NEW YORK, N. Y.—R. T. Rane, Jr., Chicago, had plans prepared by Starett & Van Vleck, Architects, 8 West Fortieth Street, for building four story, reinforced concrete and steel farehouse at 1996-2010 Park Avenue, here. \$175,000.

NEW YORK, N. Y.—D. L. Elliman & Co., 15-17 East Forty-ninth Street, is having preliminary plans prepared by Cross & Cross, Architects, 681 Fifth Avenue, for ten story, 34 x 100 ft., brick and steel office on Forty-ninth Street, between Fifth and Madison Avenues. \$150,000.

NEW YORK, N. Y.—J. M. Felson, Architect, 1133 Broadway, is preparing plans for three story, 50 x 100 ft., brick and steel synagogue on 177th Street and Broadway for Temple Gate of Hope, 130 Wadsworth Avenue. \$50,000.

NEW YORK, N. Y.—B. S. Moss, 729 Seventh Avenue, had plans prepared by De Rosa & Pereira, Architects, 110 West Fortieth Street, for building two story theater, 125 x 150 ft., brick and steel, on Prospect Avenue and 161st Street. \$600,000.

NEW YORK, N. Y.—Beadleston Realty Co., care Wallis & Goodwillie, Architects, 56 West Forty-fifth Street, will build seven story brick and steel hotel, on East Fifty-eighth Street and Fifth Avenue. \$75,000.

NEW YORK, N. Y.—Park Realty Co., 151 West Forty-second Street, are having plans prepared by G. E. Blum, Architect, 503 Fifth Avenue, for building fourteen story hotel, 25 x 100 ft., brick and steel, on Fifth Avenue and Seventy-eighth Street. \$250,000.

OLEAN, N. Y.—United States Glue Co.



# The Consumer of Lumber Has a Right to Know Who Made It

The manufacturer who puts his name on his product issues a flat invitation to the consumer to hold the maker *responsible* for the quality of the article.

This means the manufacturer stakes his entire reputation on his goods.

It has been well said that the basic principle of barter and sale before the dawn of business ethics was: "Let the buyer beware."

Branding manufactured materials with the name of the maker turns this square around.

"Let the *maker* beware" is the new caution.

The Long-Bell Lumber Company believes consumers of lumber have a right to know who made the lumber they buy. On every piece of its 550 million feet yearly production of lumber, timbers and creosoted products will be found its trade-marked brand **Long-Bell**.

This brand on wood assures the consumer that he is obtaining the product of a concern that has more than forty years of lumber experience behind it; that by its strict adherence to high standards of workmanship and careful grading the result is a product as near perfect as men and machinery can make it; that lumber thus branded is made by the largest manufacturer of Southern Pine in the United States.

Look for this name  
on Lumber

## Long-Bell

THE MARK ON QUALITY LUMBER

Ask your dealer for  
**Long-Bell** Brand.

### The Long-Bell Lumber Company

R. A. LONG BLDG.

KANSAS CITY, MO.

Manufacturer of Southern Pine, Hardwood, Oak Flooring; Creosoted Lumber, Ties, Posts, Poles, Piling and Wood Blocks.





purchased 40 acre site adjacent to Pennsylvania Railroad and extending 1/2 mile east of Clark Street, and will soon receive bids for plant. \$500,000.

PELHAM, N. Y.—Board of Education is having preliminary sketches prepared by Tooker & Marsh, Architects, 101 Park Avenue, New York City, for building two story, 168 x 171 ft., brick and steel high school. T. J. James, president. \$115,000.

ROME, N. Y.—Rome Gas, Electric Light & Power Co., 139 North James Street, plans to issue \$245,164 bonds to build gas and electric plant.

WENDE (MILGROVE P. O.), N. Y.—Erie County (Buffalo) is having preliminary plans prepared by C. E. Speich and J. Walker, Architects, 575 Elliott Square, Buffalo, for 224 x 550 ft. fireproof penitentiary on Alden County farm site. Plans include almshouse, dormitories, chapel and administration building. \$800,000.

WOODLAWN, N. Y.—St. Matthews Protestant Episcopal is having plans prepared by R. F. Schimmer, 116 Avondale Street, Woodhaven, for new church and parish house. Brick and timber construction; stone and terra cotta trim. \$50,000.

#### NORTH DAKOTA

DICKINSON, N. D.—City will vote on \$50,000 bonds to build armory.

DUNSEITH, N. D.—State Legislature, Bismarck, appropriated \$100,000 bonds to build refractory at Tubercular Sanitarium here. W. F. Kurke, Fargo, Architect.

FARGO, N. D.—W. E. Heller, 604 Front St., plans to build two story fireproof garage. W. D. Gillespie, 64 1/2 Broadway, Architect. \$25,000.

GRAFTON, N. D.—State Legislature, Bismarck, appropriated \$100,000 bonds to build dormitory at School of Feeble Minded here. W. F. Kurke, Fargo, Architect.

JAMESTOWN, N. D.—State Legislature, Bismarck, appropriated \$150,000 bonds to build 150 x 150 ft. addition to State Hospital for Insane, here. W. M. Hotchkiss, superintendent. W. F. Kurke, Fargo, Architect.

VALLEY CITY, N. D.—Masonic Society is having plans prepared for temple. \$75,000.

WALHALLA, N. D.—Farmers' Seed Potato Growers' Association will build two story, 70 x 130 ft., warehouse, 100,000 bu. capacity. A. D. Knutson, secretary. G. L. Saxton, 1228 Plymouth Building, Minneapolis, Minn., Architect.

WILLISTON, N. D.—Orpheum Theater Co. plans to build theater, 37 x 140 ft. \$50,000.

#### OHIO

AKRON, OHIO.—H. P. Moran Co. was awarded contract for the construction of the Mason School annex at \$184,000.

AKRON, OHIO.—E. M. Leatherman, State Bank Building, will build three story, 30 x 165 ft., steel and brick restaurant on South Main Street. Henry & Murphy, Second National Bank, Architects. \$50,000.

CLEVELAND, OHIO.—City Auto Tire & Supply Co., 2415 Chester Avenue, had plans prepared by G. S. Rider Co., Architects, Century Building, for one story, 40 x 137 ft., concrete, steel and brick factory addition. \$25,000.

CLEVELAND, OHIO.—Shaw-Hayden Amusement Co. proposes building three story concrete, steel and brick theater on Shaw and Hayden Avenues. W. Norris, president. W. S. Ferguson Co., 1900 Euclid Building, Architects. \$100,000.

CLEVELAND, OHIO.—Bricklayers' Association, care of L. E. Hoffman, 2416 East Ninth Street, had plans prepared by A. N. Ferguson, Architect, 212 Erie Building, for three story, 61 x 140 ft., concrete, steel and brick garage and club rooms at 2101 East Twenty-first Street. \$100,000.

CLEVELAND, OHIO.—Drake's Process Mch. Co., 1255 West Fourth Street, is receiving bids for building three story, 50 x 150 ft., concrete, steel and brick factory on East 105th Street and Quincy Avenue. \$75,000.

CLEVELAND, OHIO.—Ferry Cap & Set Screw Co., 2151 Scranton Road, had plans prepared by E. McGeorge, Architect, 1900 Euclid Building, for three story, 48 x 155 ft. and 56 x 189 ft., concrete, steel and brick factory addition. \$75,000.

CLEVELAND, OHIO.—Forest City Motor Co., 6504 Euclid Avenue, plans to build one and two story, 55 x 300 ft., concrete, steel and brick service and sales building at 6510 Euclid Avenue. E. E. Smith, 1529 Williamson Building, Architect. \$60,000.

CLEVELAND, OHIO.—Ko-Ko-Mar Co., Leader-News Building, is having plans prepared by A. C. Bishop, Architect, 427 Guardian Building, for converting concrete, steel and brick brewery into food products plant. \$40,000.

CLEVELAND, OHIO.—Paul Bros. Co., Citizens Building, plans to build six story, 99 x 132 ft., reinforced concrete, steel and brick factory and garage on East Eighteenth Street and Euclid Avenue. W. S. Ferguson, 1900 Euclid Building, Architect. \$175,000.

CLEVELAND, OHIO.—Peerless Motor Co., East Fifty-fifth Street and Carnegie Avenue, is having plans prepared by W. J. Carter, Architect, 723 Illuminating Building, for three story, 40 x 80 ft., concrete, steel and brick addition to factory on East Ninety-third Street and Quincy Avenue. \$75,000.

CLEVELAND, OHIO.—Warner & Swasey Co., 5701 Carnegie Avenue, had plans prepared by Truscon Steel Co., Architects, 651 Hippodrome Building, for one story, 90 x 176 ft., steel factory addition at 5815 Cedar Avenue. \$30,000.

CLEVELAND, OHIO.—W. S. Davidson, East Ninety-fifth Street and St. Clair Avenue, had plans prepared by W. Dunbar Co., Architects, 8201 Cedar Avenue, for building one story, 132 x 139 x 140 x 162 ft., steel and brick garage on East Ninety-fifth Street and St. Clair Avenue. \$50,000.

COLUMBUS, OHIO.—H. J. Schwartz, North Fourth Street, plans to build two story, 90 x 96 ft., reinforced concrete and brick business building on East Broad Street. Richards, McCarty & Bulford, Hartman Building, Architects. \$100,000.

DAYTON, OHIO.—F. B. Heathman Co., 220 West Third Street, plans to build two story, reinforced-concrete and brick salesroom, on West Second Street. \$100,000.

DAYTON, OHIO.—Borchers Auto Co., Sixth and Canal Streets, plans to build four story, reinforced concrete garage and salesroom at 366-370 South Main Street. Frank Hill Smith Co., East Third Street, Architects. \$175,000.

#### OREGON

ASTORIA, ORE.—Port of Astoria Commission will build six story, 47 x 100 ft. reinforced concrete flour mill, three story, 32 x 47 ft. packing room annex, and three story, 30 x 47 ft. office annex. R. R. Bartlett, chief engineer.

LINNTON, ORE.—Associated Oil Co. plans to build reinforced concrete warehouse, ten cottages and garage. A. D. Parker, district manager. \$175,000.

SALEM, ORE.—Valley Packing Co. let contract for building packing plant to F. J. Leonard, Lewis Building, Portland. Plans include three story, 82 x 82 ft. main building and 24 x 36 ft. building for rendering tanks, boiler room and fertilizer department. \$130,000.

#### PENNSYLVANIA

ALTOONA, PA.—R. W. Nash, president Altoona Grocery Co., 200 Chestnut Avenue, is receiving bids for building two story, 118 x 120 ft. brick, steel and concrete bakery on Ninth Avenue and Twenty-eighth Street. McCormick Bros., Century Building, Pittsburgh, Architects. \$90,000.

ERIE, PA.—Ed. B. Lee, 840 E. Ninth Street, Erie, Pa., was awarded contract for making alterations to United States post office here at \$12,715.

ERIE, PA.—Eric Malleable Iron Co., Twelfth and Cherry Streets, is having plans prepared by Simons, Brittain & English, Architects, Oliver Building, Pittsburgh, for building four story, 40 x 63 ft., fireproof office. \$60,000.

NORRISTOWN, PA.—Architect, H. P. Friend, Boyer Arcade, Norristown, Pa., is preparing plans for remodeling a packing plant at Claremont at a cost of \$60,000.

PHILADELPHIA, PA.—P. M. Sax, Engineer, Franklin Bank Building, soon lets contract for twelve story, 43 x 80 ft., reinforced concrete and brick factory at 1220-24 Sansom Street.

PITTSBURGH, PA.—Donaldson Commercial Truck Garage, North Side, is receiving bids for building one and two story, 100 x 227 ft., reinforced concrete, steel and brick garage on Weston and Bidwell Streets, North Side. Hunting-Davis Co., Century Building, Architects. \$75,000.

SCRANTON, PA.—Scranton Lace Co., Glenn and Meylert Streets, is having plans prepared by Lockwood, Greene & Co., Architects, 101 Park Avenue, New York City, for three story, 72 x 140 ft., reinforced concrete and steel factory. \$80,000.

#### RHODE ISLAND

HOWARD, R. I.—State Penal and Charitable Commission, Providence, soon receives bids for building three story, fireproof house of correction. J. H. Cady, 10 Weybossett Street, Providence, Architect. \$300,000.

PROVIDENCE, R. I.—M. Nahigan, 1023 Broad Street, will build one story, 106 x 120 ft. brick, concrete and steel garage on Broad and Gallatin Streets. Cost between \$40,000 and \$45,000.

PROVIDENCE, R. I.—W. R. Walker & Son, Architects, 17 Custom House, soon receive bids for building two story, 58 x 110 ft. brick and reinforced concrete fireproof garage on Friendship Street for P. H. Quinn, 1411 Turks Head Building. \$50,000.

WOONSOCKET, R. I.—Jarret & Proulx soon let contract for two story, 75 x 150 ft. brick and mill construction mill on Park Avenue. W. F. Fontaine, 285 Main Street, Architect. \$60,000.

WOONSOCKET, R. I.—Montrose Woolen Co., 292 East School Street, let contract for building, three story, 55 x 170 ft., factory, two story, 32 x 48 ft., office and one story, 34 x 43 ft., on East School Street, to W. Aubin, 1103 Diamond Hill Road. \$80,000.

#### SOUTH DAKOTA

ABERDEEN, S. D.—Farmers' Equity Union Creamery soon receives bids for building two story creamery. \$60,000.

RAPID CITY, S. D.—J. R. Sharp, secretary, Methodist Episcopal Church, will build one story, 50 x 100 ft., brick and reinforced concrete church. Edwins & Edwins, 911 North West Band Building, Architects. \$55,000.

#### TENNESSEE

MEMPHIS, TENN.—The James Alexander Construction Co., Memphis, Tenn., was awarded contract for constructing the new east wing of the Baptist Memorial Hospital, costing approximately \$250,000.

#### TEXAS

BEAUMONT, TEX.—Herman Weber has contract for building an annex to the high school building here at \$78,539.

EASTLAND, TEX.—Holmboe Construction Co., Oklahoma City, Okla., received contract for constructing a five story bank and office building for the First State Bank of Eastland, to cost approximately \$150,000. Also for constructing a six story hotel building for C. U. Connelley, at \$250,000, and constructing a theater for U. C. Connelley and John N. Graves at \$75,000.

GALVESTON, TEX.—M. C. Bowden, general contractor, received contract for constructing building to be occupied by the City National Bank at \$150,000.

SAN ANTONIO, TEX.—Trinity Methodist congregation, 1142 West Magnolia Street, plans to build church on Huistache and Grant Streets. H. C. Leonard, pastor. \$50,000.

SAN ANTONIO, TEX.—Labor Organizations, 114 1/2 South Alamo Street, plans to build labor temple. Cost between \$50,000 and \$100,000.

#### WASHINGTON

HOQUIAM, WASH.—Whitney Motor Co. plans to build two story, 100 x 125 ft. fireproof garage. F. T. Whitney, manager. \$50,000.

OLYMPIA, WASH.—Stevenson Co. of Chicago, Ill., was awarded contract for the construction of a modern hotel structure here at \$308,300.

SEATTLE, WASH.—J. A. McEachern Co., Inc., Seattle, Wash., was low bidder for constructing one story hollow tile addition to the Port Storage Warehouse at \$44,170.

SEATTLE, WASH.—Pike & Lind, Olive and Harvard Streets, plan to construct five story, 120 x 240 ft. automobile building, brick, concrete and heavy mill construction.

SEATTLE, WASH.—Journal Terminals, Inc., plan to build two story, 102 x 690 ft., reinforced concrete terminal on Duwamish Waterway. J. R. Nevins, Hoge Building, Architect. \$100,000.

TACOMA, WASH.—E. Goettling was awarded contract for constructing a three story Rich Reconstruction Clinic and office building at \$40,000.

#### WEST VIRGINIA

CLARKSBURG, W. VA.—Central Automobile Co., Morgantown, plans to build reinforced concrete garage on Main Street here. \$75,000.

CLARKSBURG, W. VA.—Lafayette Glass Co. plans to build one story steel factory. \$125,000.

MULLINS, W. VA.—Roanoke Grocery & Milling Co., Roanoke, let contract for building five story brick and reinforced concrete warehouse on Main Street to D. J. Phipps, Roanoke. \$50,000.

#### WISCONSIN

KENOSHA, WIS.—White, White & White, Architects, Public Service Building, have plans for building two story, 56 x 68 ft. fireproof school, on Division Street, for St. Casimir's congregation. \$80,000.

MILWAUKEE, WIS.—The Milwaukee Corrugating Co. has let the contract for a new addition to its factory to cost \$150,000. It will be 125 x 240 ft., two stories, brick and metal construction.

SHEBOYGAN, WIS.—Northern Furniture Co., Maryland Avenue, let contract for building four story, 66 x 150 ft., mill construction factory, on Maryland Avenue and Water Street, to F. Geib, 1439 South Ninth Street. \$65,000.


ST. ANNA, WIS.—W. J. Stollenwerk plans to build two story, 50 x 100 ft., reinforced concrete and brick garage. \$60,000.

RACINE, WIS.—Mitchie Construction Co. was low bidder for remodeling the city hall building here at \$58,987.

TWO RIVERS, WIS.—Wisconsin Textile Mfg. Co. soon lets contract for building one story, 90 x 200 ft., reinforced concrete, brick and steel plant on Main Street. \$100,000.



## Meet the new standards of Heating with IDEAL TYPE "A" BOILERS



IDEAL TYPE "A" BOILER with Integral Insulated Metallic Jacket for Steam, Vapor, and Hot Water Heating. Particularly adapted for use in Batteries.

Converts the cellar into a cheerful, livable addition to the ideal home. Used for heating cottages, mansions, apartments, hotels, schools, court houses, stores, churches, depots, theaters, banks, hospitals, institutions, and other buildings.

Send today for complete illustrated catalog giving efficiency charts, range of sizes, and remarkable heat control features.

### **AMERICAN RADIATOR COMPANY**

Sales branches and showrooms in all the large cities



# At the Architect's Service

## How Advertising Pays

There is no longer any argument as to the value of advertising for the man who has something to sell. It has more than proved its worth. Business success is now generally accepted as founded on advertising, and the more effective the advertising, the more successful the business.

It is still worth while, however, to call attention to the value of advertising from the point of view of the man who wants to buy. Advertising renders a service to the customer no less important than that which it renders to the dealer.

In these days of technical methods and large scale production it is a physical impossibility that a purchaser should know, at first hand, all the features and details that enter into manufactured articles. He has to gain this information by short cuts—and here advertising helps him. The advertising of a manufacturer tells him clearly and concisely just how that manufacturer's product differs from others; what its special merits are, and for what purposes it may best be used.

Furthermore, advertising is of great value to the man who buys with a close watch on the values his dollars return to him.

The Information and Education Service, Department of Labor, believes this is a time to encourage buying, in order that business, now resuming after the war, may be made normal as quickly as possible. Buying now means aid in the resumption of business; it is an act of patriotism, just as it was patriotic to refrain from buying during the war. But now, as at any other time, buying should be undertaken wisely; and there is no better guide to sane, constructive purchasing than advertisements.

—Department of Labor Bulletin.

|                                            |    |
|--------------------------------------------|----|
| Aeroshade Co., The (e.f.w.)                | 27 |
| Aluminum Cooking Utensil Co., The (o.a.m.) |    |
| American Elevator & Machine Co., Inc.      | 24 |
| American Lead Pencil Co. (o.a.m.)          |    |
| American Pressweld Radiator Corp. (e.f.w.) |    |
| American Radiator Co.                      | 17 |
| American Rolling Mill Co., The (e.f.w.)    |    |
| American Sheet & Tin Plate Co.             | 7  |
| American Steel & Wire Co.                  | 26 |
| American Walnut Mfrs. Assn.                |    |
| Appalachian Marble Co.                     | 7  |
| A. P. W. Paper Co.                         |    |
| Associated Tile Mfrs., The (e.f.w.)        |    |
| Atlas Portland Cement Co.                  | 22 |
| Automatic Refrigerating Co. (e.f.w.)       | 32 |

|                                        |    |
|----------------------------------------|----|
| Barrett Co. (e.f.w.)                   |    |
| Benjamin Elec. Mfg. Co. (e.o.w.)       |    |
| Berger Mfg. Co., The                   | 22 |
| Best Bros. Keene's Cement Co. (e.o.w.) | 30 |
| Bishopric Mfg. Co., The                | 22 |
| Bostwick Steel Lath Co.                | 22 |
| Boyle, John, & Co., Inc.               |    |
| Brooks, John A.                        |    |
| Buffalo Forge Co.                      | 24 |

|                                         |    |
|-----------------------------------------|----|
| Cabot, Samuel, Inc.                     | 7  |
| Cahill Iron Works, The                  | 24 |
| California Redwood Assn. (o.a.m.)       |    |
| Campbell, Walter M.                     |    |
| Carey, Philip, Co., The                 | 25 |
| Carrier Air Conditioning Co. of America |    |
| Carter, Ralph B., Co.                   | 22 |
| Carter White Lead Co.                   |    |
| Clow, James B., & Sons                  | 23 |
| Concrete Engineering Co. (e.o.w.)       | 29 |
| Corbin, P. & F.                         | 24 |
| Crampton-Farley Brass Co. (e.o.w.)      |    |
| Crittall Casement Window Co. (e.o.w.)   | 31 |
| Curtis Companies                        |    |

|                            |       |
|----------------------------|-------|
| Deming Co.                 | 75    |
| Detroit Steel Products Co. | 24    |
| Dixon Crucible Co., Jos.   | 20-22 |
| Dunham, C. A., Co (o.a.m.) |       |

|                               |    |
|-------------------------------|----|
| Edison Electric Appliance Co. | 39 |
| Edwards Mfg. Co.              | 25 |
| Electric Cable Co.            |    |

|                                          |    |
|------------------------------------------|----|
| General Electric Co.                     | 11 |
| General Fireproofing Co. (o.a.m.)        |    |
| General Slate Co.                        | 26 |
| Gillis & Geoghegan (e.f.w.)              |    |
| Globe Automatic Sprinkler Co. (e.f.w.)   |    |
| Gold Car Heating & Lighting Co. (e.f.w.) |    |

|                                             |    |
|---------------------------------------------|----|
| Habirshaw Electric Cable Co., The           |    |
| Hart & Hegeman Mfg. Co., The (e.o.w.)       |    |
| Hartmann-Sanders Co. (o.a.m.)               |    |
| Hemlock Manufacturers, The (o.a.m.)         |    |
| Higgins & Co., Chas. M. (e.o.w.)            | 25 |
| Hoffman Specialty Co. (e.f.w.)              | 19 |
| Hydrex Felt & Engineering Co., The (e.o.w.) |    |

|                                              |  |
|----------------------------------------------|--|
| Imperial Paint Co. (e.f.w.)                  |  |
| Indiana Limestone Quarrymen's Assn. (o.a.m.) |  |
| Isko Co.                                     |  |

|                                    |    |
|------------------------------------|----|
| Jenkins Bros.                      | 36 |
| Johns-Manville Co., H. W. (o.a.m.) |    |
| Johnson Service Co. (e.o.w.)       | 7  |

|                      |    |
|----------------------|----|
| Kaestner & Hecht Co. | 37 |
| Kawneer Mfg. Co.     |    |
| Kimball Co., W. W.   | 23 |
| Kohler Co. (e.o.w.)  |    |

|                                    |    |
|------------------------------------|----|
| Lawson Mfg. Co.                    |    |
| Long-Bell Lumber Co., The (o.a.m.) | 15 |
| Lord & Burnham                     |    |
| Lupton's, David, Sons Co. (e.o.w.) | 40 |

|                                    |    |
|------------------------------------|----|
| Maddock's, Thomas, Sons Co.        | 34 |
| Magnesia Assn. of America (e.f.w.) | 9  |
| McCray Refrigerator Co.            |    |
| McKinney Mfg. Co.                  | 24 |
| Merchant & Evans Co. (e.f.w.)      |    |
| Midland Terra Cotta Co. (e.o.w.)   |    |
| Milwaukee Corrugating Co.          | 28 |
| Mississippi Wire Glass Co.         | 27 |
| Mitchell Tappan Co. (e.o.w.)       | 22 |
| Mitchell Vance Co., Inc.           | 13 |
| Moline Heat                        |    |
| Muller, F. R., & Co.               |    |
| Murphy Varnish Co. (o.a.m.)        |    |

|                                                      |    |
|------------------------------------------------------|----|
| National Building Granite Quarries Association, Inc. |    |
| National Kellastone Co., The                         | 35 |
| National Metal Molding Co.                           | 22 |
| Natural Slate Blackboard (o.a.m.)                    |    |
| North Western Expanded Metal Co.                     | 33 |
| Norton Co.                                           |    |

|                                   |    |
|-----------------------------------|----|
| Oak Flooring Mfrs. Assn. (e.f.w.) | 27 |
| Okonite Co. (e.o.w.)              | 24 |
| Otis Elevator Co., The            | 22 |

|                               |    |
|-------------------------------|----|
| Patton Paint Co. (o.a.m.)     |    |
| Permutit Co.                  |    |
| Pickrel Walnut Co.            |    |
| Pitcairn Varnish Co. (o.a.m.) |    |
| Pomeroy, S. H., Co., Inc.     | 25 |

|                     |    |
|---------------------|----|
| Quantity Survey Co. | 30 |
|---------------------|----|

|                                   |    |
|-----------------------------------|----|
| Raymond Concrete Pile Co.         | 2  |
| Reilly Co., The                   |    |
| Richards-Wilcox Mfg. Co. (e.o.w.) |    |
| Rising & Nelson Slate Co.         | 24 |
| Rookwood Pottery Co. (e.f.w.)     |    |

|                                    |    |
|------------------------------------|----|
| Samson Cordage Works               | 23 |
| Sargent & Co.                      |    |
| Society of Beaux Arts Architects   | 24 |
| Standard Textile Products Co., The | 22 |
| Stanley Works                      | 7  |
| Straus, S. W., & Co. (e.o.w.)      |    |
| Structural Slate Co. (e.o.w.)      |    |

|                                     |       |
|-------------------------------------|-------|
| Taylor Instrument Co.               | 23    |
| Thomas & Co., Inc. (e.o.w.)         |       |
| Trus-Con Laboratories, The (o.a.m.) |       |
| Truscon Steel Co.                   | 31-38 |

|                                         |    |
|-----------------------------------------|----|
| University of Michigan                  | 24 |
| University of Notre Dame                | 24 |
| U. S. Gutta Percha Paint Co. (o. a. m.) |    |

|                            |    |
|----------------------------|----|
| Varon, D.                  |    |
| Vapor Heating Co. (e.o.w.) | 29 |

|                           |    |
|---------------------------|----|
| Weisz, G. A.              | 24 |
| Western Brick Co.         |    |
| Wilson, J. G., Corp., The |    |
| Window Wall Co.           |    |
| Wood-Mosaic Co.           | 28 |


|                                |    |
|--------------------------------|----|
| Yale & Towne Mfg. Co. (o.a.m.) |    |
| Yale School of Fine Arts       | 24 |

Ads. marked E.O.W. appear every other week

Ads. marked E.F.W. appear every fourth week

Ads. marked O.A.M. appear once a month





No. 8 Hoffman  
Return Line Valve

## *Experience Proves*

that the extra first cost you will pay for a good valve minimizes all the after costs (and troubles)—so that the total sum chargeable to that good valve is actually less than you will be called upon to pay for a “cheap” valve. Consider also the manufacturer’s Five Year Guarantee.

Architects everywhere have unhesitatingly expressed their confidence in the ability of the Hoffman Specialty Company to produce a venting valve not only equal to, but superior to, existing types. This confidence has long been justified. From the standpoint of efficiency, longer life and faithful service, the Hoffman Valve has a character all its own.

A special catalog has been prepared for the Architect and Engineer.

**Hoffman Specialty Company, Inc.**

**512 FIFTH AVE., NEW YORK**

Chicago  
130 N. Wells St.

Los Angeles  
215 W. Seventh St.



# DIGEST

## Of Manufacturers' Data

### ARCHITECTS' OFFICE EQUIPMENT

#### INKS:

Higgins, Chas. M., & Co., 271 9th St., Brooklyn.

#### PASTES:

Higgins, Chas. M., & Co., 271 9th St., Brooklyn.

#### PENCILS:

Dixon Crucible Co., Jos., Jersey City, N. J.

### CASEMENT WINDOWS

#### METAL:

Crittall Casement Window Co., Detroit, Mich.  
Crittall metal casement windows for office buildings, banks, public buildings, churches, university buildings, hospitals, residences, stores, factory offices, etc.

Pomeroy Co., Inc., S. H., 30 E. 42d St., N. Y.

### CEMENT AND PLASTER

#### CEMENT:

Atlas Portland Cement Co., 30 Broad St., N. Y.

#### CORNER BEADS:

Milwaukee Corrugating Co., Milwaukee, Wis.

#### PLASTER:

Best Bros. Keene's Cement Co., Dept. C, Medicine Lodge, Kans., New York, Chicago.  
"Regular" for base and finish coats, general plastering; "Fine" for all ornamental plastering; Caen stone, etc.; "Coarse" and "Superfine" for art marble.

National Kellastone Co., The, Chicago, Ill.

#### SPECIALTIES:

Bostwick Steel Lath Co., The, Niles, Ohio.  
Bostwick Corner Bead, Ground Bead, Cement Stops, Wall Plugs and Wall Ties.

Truscon Steel Co., Dept. 68, Youngstown, Ohio. Representatives in principal cities.  
Corner beads, "Kahn" curb bars, "Truscon" slotted inserts; "Kahn" adjustable inserts; "Trus-Con" National socket inserts; "Kahn" elastic filler and armor plates for expansion joints.

#### STUCCO:

National Kellastone Co., The, Chicago, Ill.

### CONCRETE REINFORCEMENT

#### REINFORCEMENT:

American Steel & Wire Co., Chicago-New York.

Berger, The, Mfg. Co., Canton, Ohio.

Bostwick Steel Lath Co., The, Niles, O. Bostwick "Truss-V-Rib."

Concrete Engineering Co., Omaha, Neb.

North Western Expanded Metal Co., 911 Old Colony Bldg., Chicago, Ill.

Truscon Steel Co., Dept. 68, Youngstown, Ohio. Representatives in principal cities.  
"Kahn" system reinforced concrete; "Kahn" bars; "Rib" bars; "Rib" lath; "Florotyles," "Floredome," etc.; flat and beamed ceilings of all types.

### DAMP-PROOFING

(See Water and Damp-proofing)

### DAYLIGHTING

Berger, The, Mfg. Co., Canton, Ohio.

### DOORS AND TRIM

#### DOORS, STEEL:

Lupton's, David, Sons Co., Philadelphia, Pa.

#### HOLLOW STEEL DOORS:

Interior Metal Mfg. Co., Jamestown, N. Y.;  
Bankers Trust Bldg., 501 Fifth Ave., N.Y.C.  
Hollow steel doors in all standard sizes.

#### STEEL ROLLING DOORS:

Edwards Mfg. Co., The, 319-349 Eggleston Ave., Cincinnati, O. Send specifications for estimate.

THIS department is intended to assist our subscribers in readily determining the names and addresses of manufacturers of products in which they may be interested together with brief data about their material.

The headings and sub-headings are arranged alphabetically and have been selected in accordance with the intent of meeting the architect's thought in preparing his specifications.

If the information desired is not found here, it will gladly be supplied by the Service Department of THE AMERICAN ARCHITECT.

### DUMB-WAITERS

Sedgwick Machine Wks., 159 W. 15th St., N.Y.

### ELECTRICAL EQUIPMENT AND SUPPLIES

#### CONDUITS AND FITTINGS:

National Metal Molding Co., 1111 Fulton Bldg., Pittsburgh, Pa. "NATIONAL" metal molding for surface wiring; "SHERADUCT" and "ECONOMY" conduits, "FLEXSTEEL" armored cable and a complete line of fittings.  
Youngstown (O.) Sheet & Tube Co. "Buckeye" rigid conduit. "Realflex" armored conductor.

#### COOKING APPLIANCES:

General Electric Co., Schenectady, N. Y.

#### LIGHTING SYSTEMS:

General Electric Co., Schenectady, N. Y.

#### OUTLET BOXES:

General Electric Co., Schenectady, N. Y.

#### SWITCHES:

General Electric Co., Schenectady, N. Y.

#### WIRES AND CABLES (Insulated):

General Electric Co., Schenectady, N. Y.  
Okonite Co., The, 501 Fifth Ave., N. Y. C. Caudex Potheads, "Mauson" and "Okonite" Tape.

### ELEVATORS AND HOISTS

#### CONVEYORS:

Otis Elevator Co., 11th Ave. and 26th St., N. Y. C. Gravity spiral.

#### ELEVATORS:

American Elevator & Machine Co., Louisville, Ky.

Kaestner & Hecht Co., 500 South Throop St., Chicago, Ill.

Otis Elevator Co., 11th Ave. and 26th St., New York. Offices in principal cities of the world. Electric, hydraulic, belt and hand power, inclined freight elevators and escalators.

#### ELEVATORS (Hand Power):

Sedgwick Machine Wks., 159 W. 15th St., N.Y.

#### ELEVATOR CABLE:

American Steel & Wire Co., Chicago-New York.

### ELEVATORS AND HOISTS—

#### Continued

#### HOISTS (Ash):

Otis Elevator Co., 11th Ave. and 26th St., N. Y. C. Automatic coal and ash hoists, blast furnaces and ship hoists.

### FIREPROOFING MATERIALS

Johns-Manville Co., H. W., New York City.

#### CAGING OR FORMING

Mitchell-Tappen Co., 17 John St., N. Y. C.

#### METAL LATH:

Berger, The, Mfg. Co., Canton, Ohio.

Bostwick Steel Lath Co., The, Niles, O.; 135 N. 22nd St., Phila., Pa. Bostwick "Truss-Loop" and expanded metal in three types; "Diamond A," Niles and "Lock."

Concrete Engineering Co., Omaha, Neb.

Milwaukee Corrugating Co., Milwaukee, Wis.

North Western Expanded Metal Co., 911 Old Colony Bldg., Chicago, Ill.

Truscon Steel Co., Dept. 68, Youngstown, O. Representatives in principal cities. "Hy-rib," "Rib" lath; "Diamond Mesh" lath.

### FIRE PROTECTION

#### FIRE EXIT DEVICES:

Corbin, P. & F., New Britain, Conn.

### FLOORS

#### COMPOSITION:

National Kellastone Co., The, Chicago, Ill.

#### FLOOR COATING:

Trus-Con Laboratories, Dept. 68, Detroit, Mich. Representatives in principal cities. "Trus-Con" floor hardener. "Trus-Con Agatex," "Trus-Con" floor enamel.

#### PARQUET:

Wood-Mosaic Co., New Albany. Parquetry, hardwood flooring, veneer and lumber.

#### WOOD:

Oak Flooring Bureau, Ashland Block, Chicago, Ill.

### FOUNDATIONS

#### PILES:

Raymond Concrete Pile Co., 149 Cedar St., N. Y. C. "Raymond" concrete piles are made by driving a reinforced steel shell which is left permanently in the ground, this shell is then filled with concrete.

### FURNITURE AND DECORATIONS

#### DRAPERIES, UPHOLSTERIES, WALL COVERINGS:

Standard Textile Products Co., The, 320 Broadway, New York. "Sanitas" Tinted, Decorative and Glazed. Fast colors, sanitary. For private homes, hotels, auditoriums, institutions, etc.

#### METAL:

Canton Art Metal Co., Canton, Ohio.

### HARDWARE

#### BOLTS:

Corbin, P. & F., New Britain, Conn.

#### BUILDERS' HARDWARE:

Corbin, P. & F., New Britain, Conn.

Stanley Works, The, New Britain, Conn.

ALPHABETICAL INDEX OF ADVERTISERS ON PAGE 18



**HARDWARE—Continued****BUTTS AND HINGES:**

Corbin, P. & F., New Britain, Conn.  
Lawson Mfg. Co., Superior and Franklin Sts.,  
Chicago, Ill. "Nu" Jamb Hinge.  
McKinney Mfg. Co., Pittsburgh, Pa.  
Stanley Works, The, New Britain, Conn.  
(Ball-Bearing)—steel, brass, bronze.

**DOOR CHECKS:**

Corbin, P. & F., New Britain, Conn.

**GARAGE HARDWARE:**

Stanley Works, The, New Britain, Conn. Garage door holders and garage door hinges.

**HEATING, VENTILATION,  
PLUMBING****BOILERS:**

American Radiator Co., Chicago, Ill.

**BLOWERS AND EXHAUSTERS:**

Buffalo Forge Co., Buffalo, N. Y.

**CLOSETS:**

Clow, James B., & Sons, Chicago, Ill.  
Maddock's, Thomas, Sons Co., Trenton, N. J.

**DRINKING FOUNTAINS:**

Cahill Iron Works, The, Chattanooga, Tenn.  
Clow, James B., & Sons, Chicago, Ill.  
Maddock's, Thomas, Sons Co., Trenton, N. J.

**LAVATORIES:**

Cahill Iron Works, The, Chattanooga, Tenn.  
Clow, James B., & Sons, Chicago, Ill.  
Maddock's, Thomas, Sons Co., Trenton, N. J.

**PIPE (Steel):**

Youngstown Sheet & Tube Co., Youngstown, O.

**RADIATORS:**

American Radiator Co., Chicago, Ill.  
Clow, James B., & Sons, Chicago, Ill.

**RANGES, ELECTRIC:**

Edison Electric Appliance Co., Inc., Chicago, Ill. "Hughes" electric ranges.

**SINKS:**

Cahill Iron Works, The, Chattanooga, Tenn.  
Maddock's, Thomas, Sons Co., Trenton, N. J.

**SINKS (Slop):**

Cahill Iron Works, The, Chattanooga, Tenn.  
Maddock's, Thomas, Sons Co., Trenton, N. J.

**TANKS (Closet):**

Cahill Iron Works, The, Chattanooga, Tenn.  
Maddock's, Thomas, Sons Co., Trenton, N. J.

**TEMPERATURE INSTRUMENTS:**

Taylor Instrument Co., Rochester, N. Y.

**TEMPERATURE REGULATORS:**

Johnson Service Co., Milwaukee, Wis.  
Vapor Heating Co., York, Pa.

**TRAPS (Radiator):**

Johns-Manville Co., H. W., New York City.

**TRAPS (Steam):**

Jenkins Bros., 80 White St., N. Y. C.  
Johns-Manville Co., H. W., New York City.

**TUBS (Bath):**

Cahill Iron Works, The, Chattanooga, Tenn.  
Maddock's, Thomas, Sons Co., Trenton, N. J.

**TUBS (Laundry):**

Cahill Iron Works, The, Chattanooga, Tenn.  
Maddock's, Thomas, Sons Co., Trenton, N. J.

**URINALS:**

Cahill Iron Works, The, Chattanooga, Tenn.  
Clow, James B., & Sons, Chicago, Ill.  
Maddock's, Thomas, Sons Co., Trenton, N. J.

**VALVES (Air):**

Hoffman Specialty Co., 130 No. Fifth Ave.,  
Chicago, Ill. Siphon Air valves; Siphon  
Air and Vacuum valves; "Air Lines" valves;  
Junior Quick Vent Air Valve; Quick Vent  
"Float" air valve; Quick Vent "Float"  
Air and Vacuum valve; Return Line valve  
for vapor, vapor vacuum, modulating and  
vacuum heating systems; vapor vent valve.  
Jenkins Bros., 80 White St., N. Y. C.

**VALVES (Radiator):**

Jenkins Bros., 80 White St., N. Y. C.

**HEATING, VENTILATION,  
PLUMBING—Continued****VALVES (Steam):**

Jenkins Bros., 80 White St., N. Y. C.

**VALVES (Water Line):**

Jenkins Bros., 80 White St., N. Y. C.

**VAPOR HEATING SYSTEMS:**

American Dist. Steam Co., No. Tonowanda, N. Y.  
Vapor Heating Co., York, Pa.

**VENTILATORS:**

Burt Mfg. Co., The, 77 Main St., Akron, O.  
Manufacturers of all types of ventilators,  
both stationary and revolving.  
Milwaukee Corrugating Co., Milwaukee, Wis.

**WATER SYSTEMS:**

Deming Co., Salem, O.

**HOISTS**

(See Elevators and Hoists)

**INSULATION (Sound and Heat)****BUILDING:**

Cabot, Samuel, Inc., Boston. "Cabot's Quilt."  
Hydrex Felt & Eng. Co., 120 Liberty St., N. Y.

**PIPE (Heat and Power):**

Magnesia Association of America, The, 702  
Bulletin Bldg., Philadelphia, Pa. Distributors  
of Standard Specifications for the correct  
application of 85% magnesia pipe and  
boiler coverings to every description of  
heating and power service.

**LIGHTING FIXTURES****GLASSWARE:**

Mitchell Vance Co., 503 W. 24th St., New  
York City.

**METAL:**

Mitchell Vance Co., 503 W. 24th St., New  
York City.

**MARBLE**

Appalachian Marble Co., Knoxville, Tenn.

**MUSICAL INSTRUMENTS****ORGANS:**

Kimball, W. W., Co., Chicago, Ill.

**ORNAMENTAL BRONZE AND  
IRON**

Polachek, John, Bronze & Iron Co., 480 Han-  
cock St., Long Island City, N. Y.

**PAINTS, VARNISHES, STAINS****PAINT (Steel Protective):**

Dixon, Joseph, Crucible Co., Jersey City, N. J.

**STAINS:**

Cabot, Samuel, Inc., Boston. "Cabot's"  
Creosote Stains, Stucco Stains, Brick Stains,  
Old Virginia White and Old Virginia Tints.

**PARTITIONS****METAL:**

Berger, The, Mfg. Co., Canton, Ohio.  
Interior Metal Mfg. Co., Jamestown, N. Y.;  
Bankers Trust Bldg., 501 Fifth Ave., N. Y. C.  
Interchangeable Hollow Metal Partitions.  
Lupton's, David, Sons Co., Philadelphia, Pa.

**PIPE AND BOILER COVERINGS****INSULATION:**

Magnesia Association of America, The, 702  
Bulletin Bldg., Philadelphia, Pa. Distributors  
of Standard Specifications for the correct  
application of 85% magnesia pipe and  
boiler coverings to every description of  
heating and power service.

**PLASTER**

(See Cement and Plaster)

**PLUMBING**

(See Heating, Ventilation, Plumbing)

**REFRIGERATION****REFRIGERATING APPARATUS:**

Automatic Refrigerating Co., Hartford, Conn.

**ROOFING****ASPHALT:**

Carey, Philip, Co., The, Lockland, Cincinnati,  
Ohio. Carey Flexible Cement Roofing. A  
roofing for all classes of buildings, flat or  
steep surfaces; concrete, tile or wood  
sheathing construction. Made of a flexible  
asphalt cement in sheets 26 in. wide by 36  
ft. long.

**CANVAS:**

Hydrex Felt & Eng. Co., 120 Liberty St., N. Y.

**SHEET METAL:**

American Sheet & Tin Plate Co., Frick Bldg.,  
Pittsburgh, Pa.

**SHINGLES, METAL:**

Milwaukee Corrugating Co., Milwaukee, Wis.

**SLATE:**

General Slate Co., 148 State St., Boston, Mass.  
Rising & Nelson Slate Co., West Pawlet, Vt.;  
101 Park Ave. Special slate to architect's  
design.

**TILE (Reinforced-Cement):**

American Cement Tile Mfg. Co., Pittsburgh  
and New York. "Bonanza" roofing tile.

**SAFETY TREADS**

Structural Slate Co., The, Pen Argyl, Pa.

**SASH**

(See Window)

**SHADES****PORCH AND WINDOW:**

Aeroshade Co., The, 962 Oakland Ave., Wau-  
kegan, Ill. "Aerolux" ventilating porch  
shades and window shades. Window shades  
for public and factory buildings.

**SHEET METAL**

American Sheet & Tin Plate Co., Frick Bldg.,  
Pittsburgh, Pa.

**FORMED PRODUCTS:**

American Sheet & Tin Plate Co., Frick Bldg.,  
Pittsburgh, Pa.  
Berger, The, Mfg. Co., Canton, Ohio.

**METAL CEILINGS:**

Berger, The, Mfg. Co., Canton, Ohio.  
Canton Art Metal Co., Canton, Ohio.  
Milwaukee Corrugating Co., Milwaukee, Wis.

**SKYLIGHTS, ROLLED STEEL**

Lupton's, David, Sons Co., Philadelphia, Pa.  
Milwaukee Corrugating Co., Milwaukee, Wis.

**STAINS**

(See Paints, Varnishes and Stains)

ALPHABETICAL INDEX OF ADVERTISERS ON PAGE 18



**STRUCTURAL STEEL****PRESSED STEEL CONSTRUCTION:**

Berger, The, Mfg. Co., Canton, Ohio. "Metal Lumber." Pressed Steel Joints and structural members.

Truscon Steel Co., Dept. 68, Youngstown, O. Representatives in principal cities. "Kahn" pressed steel beams, joists, studs, plates, etc.

**STUCCO AND WALL BOARD****PLASTER BOARD:**

Bishopric Mfg. Co., 744 Este Ave., Cincinnati, O. Bishopric Stucco or Plastic Board. The dove-tailed key locks the plaster. Made of creosoted lath, asphalt-mastic and heavy fibre board.

**STUCCO:**

National Kellastone Co., The, Chicago, Ill.

**TERRA COTTA**

N. Y. Arch. Terra Cotta Co., Tel. Astoria 700.

**TILE**

(See Flooring and Roofing)

**VACUUM CLEANERS**

American Radiator Co., Chicago, Ill.

**VARNISHES**

(See Paints, Varnishes, Stains)

**VENTILATION**

(See Heating, Ventilation, Plumbing)

**WATER AND DAMPPROOFING**

Cabot, Samuel, Inc., 141 Milk St., Boston.

Hydrex Felt & Eng. Co., 120 Liberty St., N. Y.

**WALL BOARD**

(See Stucco and Wall Board)

**WELLS**

Carter, R. B., Co., 152 Chambers St., N. Y. C.

**WINDOWS, METAL**

Crittall Casement Window Co., Detroit, Mich. Solid steel and bronze windows for office buildings, banks, public buildings, churches, university buildings, hospitals, residences, stores, factory offices, etc.

Detroit Steel Products Company, Detroit, Mich. Fenestra Solid Steel Windows; Standard side wall horizontally pivoted—Counterbalanced vertical sliding sash—Center pivoted and top hung continuous sash for monitor. Immediate shipment from warehouse on standard sizes. Representatives in principal cities.

**WINDOWS, METAL—Continued**

Lupton's, David, Sons Co., Philadelphia, Pa.

Pomeroy, S. H., Co., Inc., 30 E. 42d St., N. Y.

Truscon Steel Co., Dept. 68, Youngstown, O. Representatives in principal cities. "United" steel sash in all types; horizontal and vertical pivoted sash; counterbalanced and counterweighted sliding sash; center pivoted and top hung continuous sash; steel and glass partitions; sliding and swinging partitions; sliding and swinging doors; casement sash of all designs.

**WIRE GLASS**

Mississippi Wire Glass Co., 216 5th Ave., N. Y. C. Polished Wire Glass—"Romanesque," "Syenite," "Maze," "Pentecor," "Ribbed," "Rough." Figured Wire Glass—"Apex," "Romanesque," "Syenite," "Maze," "Florentine," "Figure No. 2," "Ondoyant," "Pentecor," "Ribbed," "Rough."

**WOOD****OAK:**

Oak Flooring Bureau, Ashland Block, Chicago, Ill.

**PINE:**

Long-Be'l Lumber Co., R. A., Long Bldg., Kansas City, Mo.

"Wipe  
off the  
Dirt"

**SANITAS**  
MODERN  
WALL COVERING

Write for  
booklet and  
samples

Sanitary, sensible, economical. Styles and colors for any interior. Can't fade or crack. Impervious to water and grease spots. An expert decorator at your service to suggest and advise—write us.  
The Standard Textile Products Co., 320 Broadway, Dept. F, New York 4-3

THE DOVE-TAILED KEY  
LOCKS THE PLASTER  
**BISHOPRIC**  
**STUCCO OR PLASTER**  
**BOARD**  
TRADE-MARK REGISTERED

Before you plan another building write for free sample and book entitled "Wisdom."

The Bishopric  
Manufacturing Co.  
200 Este Avenue  
Cincinnati Ohio

The cement chosen exclusively by the  
U. S. Government for the Panama Canal

**ATLAS** **PORTLAND CEMENT**  
"The Standard by which all other makes are measured"

**WATER SUPPLY**

ARTESIAN WELLS DRILLED  
COMPLETE PUMPING PLANTS INSTALLED

Engineering and contracting service for  
isolated water supply from any source.

**RALPH B. CARTER CO.,** 152 Chambers St.,  
NEW YORK 2-2

**BOSTWICK METAL LATH**

Insures Satisfactory Lath and Plaster Work

**Bostwick Steel Lath Co.** Niles, Ohio


Pioneer Makers of Metal Lath

**DIXON'S SILICA GRAPHITE PAINT**

Paint economy is the number of years of service given, not the "price per gallon."

**DIXON'S SILICA-GRAPHITE PAINT** gives longest protection for metal or wood surfaces. Booklet No. 14-B.

Made in Jersey City, N. J., by the  
**JOSEPH DIXON CRUCIBLE CO.**  
Established 1827

**STANDARDIZED METAL CAGING (S.M.C.)**

*Positively Locks the Concrete  
to the Steel*

**AND INSURES PERMANENCY**

ALL SIZES IN STOCK

**MITCHELL-TAPPEN CO. 15 JOHN ST. NEW YORK**

**The WORLD'S WORD for**

**ELEVATOR SAFETY**

**ELECTRICAL CONDUITS  
AND FITTINGS**

**National Metal Molding Co**

1111 FULTON BUILDING, PITTSBURGH, PA.

**BERGER**  
SEE SWEETS

METAL LUMBER, P. 176 STEEL CEILINGS, P. 417  
REINFORCING MATERIALS, P. 202-05

STEEL LOCKERS, SHELVING, FILES, P. 1406

Branches: **THE BERGER MFG. CO., Canton, Ohio**

Boston, New York, Philadelphia, Chicago, St. Louis, Minneapolis, San Francisco



### Tycos Temperature Instruments

INDICATING - RECORDING - CONTROLLING

In spite of nation-wide agitation as to automatic and positive mechanical regulations there still remain many plants which are not properly equipped in all departments with *Tycos* profit earning instruments. To such we offer our extensive experience to help them select the installation best adapted to their needs.

Taylor Instrument Companies ROCHESTER N.Y.

## Clow Quality Plumbing

Always Pays

James B. Clow & Sons

534-546 So. Franklin St.

CHICAGO



## KIMBALL PIPE ORGANS

For Churches Auditoriums Residences Correspondence invited.

W. W. KIMBALL CO.

W. B. MILNER, Eastern Sales Agent  
507 Fifth Ave., New York

Kimball Hall, Chicago  
Established 1857

## SAMSON SPOT SASH CORD



SAMSON CORDAGE WORKS, BOSTON, MASS.

### RATES for Classified Advertisements

243 West 39th St., New York

Positions Wanted, 75 cents for 25 words or less and 2 cents for each additional word; Help Wanted, Special Notices, Competitions, Proposals, etc., \$1 for 25 words or less and 3 cents for each additional word. Ten lines or more 30 cents per line. Copy received until 12 m. Friday. PAYMENTS STRICTLY IN ADVANCE.

Position Wanted advertisements of men who have been serving in the army and who desire to make connection with architects' offices will be inserted free of charge.

### HELP WANTED

ARCHITECTURAL designers, superintendents and tracers wanted. Our calls for these men come from all States in the Mississippi valley. We charge no registration fee and our rates are reasonable. Registration blanks sent on application. (Architects needing men—communicate with us.) Architects Agency, 115 S. Dearborn St., Chicago. (t.f. 2272)

WANTED AT ONCE—Experienced Architectural Draftsman. Give references, experience, salary and time could report for business. Advancement given to one who can show results. Address 66-C, care The American Architect. (2266-67)

WANTED—Experienced architectural draftsman, good place for right party. Huntington Lumber & Supply Co., Huntington, W. Va.

WANTED—Architectural draftsman for general all around work. Must be able to work up drawings from sketches. Only first-class experienced man need apply. State experience, references and salary desired. Address Ruhe & Lange, 12 North Sixth Street, Allentown, Pa. (2266-67)

GOOD opportunity in growing city for first-class architectural designer and draftsman. Answer immediately, stating age, experience and salary expected. Address 66-A, care The American Architect. (2266-67)

ARCHITECTURAL designers and draftsmen needed for positions in many different states, salaries \$30 to \$50 per week. No advance fee if you mention this advertisement. Address Archt. Dept., The Engineering Agency, Monadnock Bldg., Chicago, Ill. (Twenty-sixth year.) (2266-67-68-69-70)

WANTED—By an established architect, a partner for school work; must be familiar with schools in New York, Connecticut and New Jersey. Address 66-B, care The American Architect. (2266)

ARCHITECTURAL draftsman, capable making complete working drawings from sketches. Accuracy and experience large work essential. Permanent. State age, experience, salary, date available. Submit illustrations and references. The Mills & Millspaugh Co., Columbus, Ohio. (2266)

WANTED—Several competent Architectural Draftsmen. One to be an experienced specification writer. State experience and salary. Guilbert & Betelle, Architects, 665 Broad St., Newark, N. J. (2266)

DRAFTSMAN wanted. Thoroughly experienced on working drawings, also specification writer wanted. Rossell Edward Mitchell & Co., Ltd., Architects, Engineers, Town Planners, Norfolk, Virginia. (2265-66)

### POSITIONS WANTED

POSITION wanted by a high class, rapid architectural draftsman, designer, detailer and perspective. Twenty years' practical experience. Prefer commercial or industrial work as chief draftsman if possible. Salary \$50.00 per week. Address R. E. G., 2902 Euclid Ave., Cleveland, Ohio. (2266)

ARCHITECTURAL draftsman. Technical graduate: 16 years' experience; 6 years on plans and details; 10 years as field supervisor; now inspector of construction work Washington Navy Yard. Reference, Mr. John Lawrence Mauran, Chemical Bldg., St. Louis, Mo. A. E. Garland, 515 Pennsylvania Ave. S. E., Washington, D. C. (2265-66-67)

COLLEGE Graduate A. B., also two years' University work in architecture. Member Am. Assn. Eng. Training; steel work, arches, retaining walls, construction, Beaux Arts plan problems, perspective, water color, physics, mathematics and languages. Use typewriter, etc. Two years' experience drafting marble and building superintendence; 26 months military service E. M. and officer; 28, single, native Anglo-Saxon, desire position with architect in the east. Will consider also steel drafting and superintendence. A. H. Goddard, Fairhaven, Mass. (2266)

OFFICE MANAGER, chief clerk or private secretary. Young man; twelve years with architects, engineers and contractors. Fully conversant with administrative work of architectural profession. Expert stenographer. Salary \$2,000. Address 66-E, care The American Architect. (2266)

ARCHITECTURAL designer and structural engineer, graduate best technical schools, five years' New York experience, two years' U. S. Army as 1st Lieutenant, Engineers, just discharged, desires permanent position in large office. South of middle west preferred. Address 66-F, care The American Architect. (2266-67)

### SPECIAL NOTICES

DRAFTSMAN, architectural good all around man, also steel and concrete engineering would like to rent table and desk room in New York City architect's office. Best references. Address 66-D, care The American Architect. (2266)

FOR SALE—An old established architectural practice in a leading Eastern city. Well equipped office—fixtures, library, utensils, etc., included. Best of reasons given for sale and closest investigation invited. Address 64-R, care The American Architect. (2264-65-66)

### PROPOSALS

NOTICE TO CONTRACTORS: Sealed proposals for Construction, Heating, Sanitary and Electric Work—Additional Quarters for Acute Patients, Central Islip State Hospital, Central Islip, N. Y., will be received by the State Hospital Commission at the Capitol, Albany, N. Y., until 3 o'clock P. M., on Wednesday, June 4, 1919, when they will be publicly opened and read. Proposals shall be enclosed in an envelope furnished by the State Architect sealed and addressed, and shall be accompanied by a certified check in the sum of five per cent (5%) of the amount of the proposal. The contractors to whom the awards are made will be required to furnish surety company bond in the sum of fifty per cent (50%) of the amount of the contract within thirty (30) days after official notice of award of contract and in accordance with the terms of Specifications No. 3219, 3239, 3240, 3241. The right is reserved to reject any or all bids. Drawings and specifications may be consulted at the Central Islip State Hospital, Central Islip, N. Y., at the New York Office of the Department of Architecture, Room 1715, Tribune building, and at the Department of Architecture, Capitol, Albany, N. Y. Drawings and specifications and blank forms of proposal may be obtained at the Department of Architecture, Capitol, Albany, N. Y., upon reasonable notice to and in the discretion of the State Architect, L. F. Pilcher, Capitol, Albany, N. Y.

Dated: May 7, 1919. E. S. ELWOOD,  
Secretary, State Hospital Commission.  
(2265-66)

TREASURY DEPARTMENT, Supervising Architect's Office, Washington, D. C., May 21, 1919.—SEALED PROPOSALS will be opened in this office at 3 p. m. June 18, 1919, for furnishing and delivering at the site the materials required for the construction of the United States Post Office building at Clinton, S. C., including materials for concrete, reinforced concrete, stone, granite, brick, structural terra cotta, structural steel, miscellaneous iron and steel work; composition roofing, slate roofing, sheet-metal work, skylights, plastering, interior marble, sanitary slate, lumber, millwork, painting, glazing, hardware, plumbing, heating, electric work, etc. Bills of quantities and specifications may be obtained from the custodian of the site at Clinton, S. C., or at this office, in the discretion of the Supervising Architect. Jas. A. Wetmore, Acting Supervising Architect. (2266-67)



### School of the Fine Arts Yale University

#### Department of Architecture

1. A four-year general course in Architecture leading to the degree of Bachelor of Fine Arts (B.F.A.). Students may specialize in the above course (a) in Design; (b) in Construction.
2. Special students properly qualified are admitted to the courses in the Department of Architecture. Students of the Department of Architecture may avail themselves of general allied courses in Painting and Modeling. For special catalogue of the Department of Architecture address Secretary of the School of the Fine Arts, Yale University, New Haven, Connecticut.

### UNIVERSITY OF NOTRE DAME NOTRE DAME, INDIANA COLLEGE OF ARCHITECTURE

Four-year courses in Design and Architectural Engineering with degrees. Graduate courses with Master's Degree. Two-year course in Design with certificate.

Catalogues on application

### BEAUX-ARTS INSTITUTE OF DESIGN 126 East 75th Street New York City

LLOYD WARREN, Director  
— FOUR FREE COURSES —

Architectural Design Interior Decoration and Industrial Art Design Sculpture Modeling of Ornament Composition in Mural Painting

These courses, conducted in co-operation with the Society of Beaux Arts Architects, the Art Alliance of America, the National Sculptors Society and the Society of Mural Painters, respectively, are modeled on the principles of teaching of the Ecole des Beaux-Arts of Paris, and are intended for the instruction of students of Architecture, Interior Decoration, Sculpture and Painting, and of apprentices and workmen in the artistic trades allied to Architecture. Any course may be entered at any time during the year. The courses in Architecture, Interior Decoration and Painting may be followed outside of New York City under correspondence of the Institute. For the courses in Sculpture and Ornament Modeling instruction is given in the Studios at the Building of the Institute. Circulars of information concerning any of the courses will be mailed to those applying for them.

### MODERN SCHOOL HOUSES

#### Part II

This volume gives the latest phases of School House Design, Construction and Equipment in the United States; 170 pages of Plates; 80 pages of Illustrated Text. Price (postpaid), \$7.50.

U. P. C. Book Company, Inc., Successor to  
The American Architect Book Department  
241-249 W. 39th Street, New York

### Rendering of Perspectives in any Medium


#### Drawing of Perspectives

G. A. Weisz, 15 East 40th St., N. Y.  
Telephone Murray Hill 3659

### COLLEGE OF ARCHITECTURE UNIVERSITY OF MICHIGAN Ann Arbor, Michigan

#### SUMMER CLASSES

in Architectural Design, Drawing and Painting  
June 30 to August 22, 1919



### LITTLE KNOCKERS FOR INSIDE DOORS

The noted Corbin excellence  
and artistic treatment.

Agents in All Cities

424

### MCKINNEY BUTTS FOR ALL DOORS

LITERATURE ON REQUEST

McKINNEY MANUFACTURING CO., PITTSBURGH, PA., U.S.A.

# "Buffalo"

It's significant that the largest schools and public buildings in the U. S. are equipped with  
Buffalo Heating & Ventilating apparatus

Write for Catalog 198-11

Buffalo Forge Co. Buffalo, N. Y.

Every modern factory is an advertisement for

# Fenestra

SOLID STEEL WINDOWS

Made where most of America's Steel Windows are made—at the  
Detroit Steel Products Company, East 2509 Grand Blvd., Detroit, Mich.

# AMERICAN ELEVATORS

Built by  
AMERICAN ELEVATOR  
and MACHINE CO.  
INCORPORATED  
LOUISVILLE, KY.

### MAURER — STRENGTH OF MATERIALS

By Edward Rose Maurer, B.C.E., Professor of Mechanics, University of Wisconsin. A work of great value to architects, builders and designers. 150 pages. 58 illustrations. Cloth binding. Price, \$1.00.

U. P. C. BOOK COMPANY, Inc.

Successor to The American Architect Book Dept.

241-249 West 39th Street

New York

### ROOFING SLATE

Heavy Graduated Slate  
Tudor Stone  
Verde Unique  
Tudor Stone, Jr.  
Standard Slates all kinds

### RISING & NELSON SLATE CO.

West Pawlet, Vermont

New York

Chicago

Boston

Architects' Service Department, Room 811, Architects' Bldg., N. Y. C. Samples also filed with Architects' Samples Co., 101 Park Ave., N. Y. C.

### "Southern Beauty" Enamelled Ware

Manufactured by

THE CAHILL IRON WORKS  
CHATTANOOGA, TENN.

## Okonite Insulated Electric Light Wires

Are pronounced by leading Architects to be SAFE, DURABLE and EASILY ADJUSTED for the inside wiring of PUBLIC and PRIVATE BUILDINGS.

THE OKONITE CO., PASSAIC, NEW JERSEY

Sole Manufacturers  
CENTRAL ELECTRIC CO., Chicago, Ill., General Western Agents  
Novelty Electric Co., Phila., Pa. Pettingell-Andrews Co., Boston, Mass.  
F. D. Lawrence Electric Co., Cincinnati, O.




TRADE MARK

REG. U. S. PATENT OFFICE



## Edwards Steel Lockers

*Built for Strength  
and Durability*



Require the least number of parts to complete a unit, reducing the labor of erection to a minimum. Can be erected by ordinary workmen, the only tools needed—a wrench and screw driver. Will gladly furnish sketches showing arrangements of lockers suitable for your requirements. Send specifications for estimate.

**The Edwards Mfg. Co.**  
319-349 Eggleston Ave.,  
Cincinnati, O.

Metal Roofing—Metal Garages—Portable Buildings—Steel Lockers—Shelving—Bins—Rolling Steel Doors—Partitions—Steel Trucks, etc.



**HIGGINS'**

VEGETABLE GLUE, Etc.  
DRAWING INKS  
ETERNAL WRITING INK  
ENGROSSING INK  
TAURINE MUCILAGE  
PHOTO-MOUNT PASTE  
DRAWING-BOARD PASTE  
LIQUID PASTE  
OFFICE PASTE

ARE THE FINEST AND BEST GOODS OF THEIR KIND  
Emancipate yourself from the use of corrosive and ill-smelling inks and adhesives and adopt the Higgins' Inks and Adhesives. They will be a revelation to you, they are so sweet, clean and well put up, and withal so efficient. They are specially adapted for use in Architects' and Engineers' offices, as well as for general home and office use.

AT DEALERS GENERALLY

**Chas. M. Higgins & Co., Manufacturers**  
Branches: Chicago, London 271 NINTH ST., Brooklyn, N. Y.

## POMEROY FIRE RETARDANT WINDOWS



**Not Made to Meet a Price, But  
To Set a Standard of Service**

Send for our literature on  
Windows and Partitions

**S. H. POMEROY COMPANY, Incorporated**  
282-296 EAST 134TH ST. NEW YORK

SIXTEENTH EDITION THE NEW KIDDER 57TH THOUSAND

### Architects' and Builders' Pocket-Book

The following Associate Editors and Contributors personally  
EDITOR-IN-CHIEF

By the late FRANK E. KIDDER 16th Edition Rewritten

THOMAS NOLAN, F.A.I.A.,  
Professor of Architectural Construction, University of Pennsylvania,  
prepared various articles

|                       |                   |                  |
|-----------------------|-------------------|------------------|
| R. C. CARPENTER       | THOMAS NOLAN      | A. P. STRADLING  |
| J. I. COSGROVE        | EMIL G. PERROT    | W. H. TIMBIE     |
| F. H. KINDL           | N. A. RICHARDS    | MALVERDA A. HOWE |
| GRENVILLE T. SNELLING | HERMAN C. BERRY   |                  |
| RUDOLPH P. MILLER     | DANIEL E. MORAN   |                  |
| WALLACE C. SABINE     | CHARLES P. WARREN |                  |

1856 pages, 4 1/4 by 7 Morocco, \$5.00 Net

**U. P. C. BOOK COMPANY, Inc.**

Successor to The American Architect Book Dept.

241-249 West 39th Street New York

# Carey

## ROOFINGS


are being advertised.

If you are a reader of The Saturday Evening Post, the Literary Digest or the publications of more special interest to the building trade, you have no doubt noticed the half page and page advertisements for Carey Roofings. You can count on this advertising appearing continuously and in ever increasing volume from year to year. That means that when you specify Carey Roofing you will be specifying something that your client knows something about. You will find your client wanting the Carey Roofing you have specified.

## THE PHILIP CAREY COMPANY

505-525 WAYNE AVE.  
LOCKLAND, CINCINNATI, OHIO

# Deming



## "MARVEL" WATER SYSTEM

Noiseless; self starting;  
self stopping; self oil-  
ing; self priming; self  
operating in all re-  
spects.

For summer cottages;  
suburban residences;  
farm homes, etc.; and  
for pumping soft water  
in city homes. Furnished  
with small gasoline en-  
gine, where electric cur-  
rent is not available.

Complete details in  
folder, "A Turn of the  
Faucet."

**The Deming Company**  
Salem, Ohio  
HAND AND POWER PUMPS  
FOR ALL USES

System No. 2085, Electric Driven

### General Distributing Houses:

|                                                                      |                                 |
|----------------------------------------------------------------------|---------------------------------|
| CHICAGO: Henion & Hubbell                                            | BOSTON: Chas. J. Jager Co.      |
| PITTSBURGH: Harris Pump & Supply Co.                                 | BUFFALO: Root, Neal & Co.       |
| NEW YORK: Ralph B. Carter Co., 152 Chambers St.                      | PHILADELPHIA: W. P. Dallett Co. |
| INDIANAPOLIS, ST. LOUIS, PORTLAND, SEATTLE, SAN FRANCISCO: Crane Co. |                                 |





## MONSON & VERMONT

**Unfading Roofing Slate**  
IN ALL COLORS

Quarries and Mills  
**Monson, Maine and Fair Haven, Vt.**



### GENERAL SLATE COMPANY

Sales Office  
148 STATE STREET  
BOSTON, MASS.

## DIXON'S ELDORADO

*"the master drawing pencil"*

To find the lead best suited for your work is to have a pencil satisfaction such as you have never known. You can not only find this lead in the Eldorado, but you will find a pencil that fits your hand—that seems to be *your* pencil. All Eldorado leads are strong, long-wearing and free from grit with an unrivalled smoothness.

We would appreciate a request from you on your letter head for a free full-size sample of your favorite lead. We believe you will appreciate the Eldorado. Please mention your dealer's name.

Made in **17 LEADS**  
one for every need  
or preference - -

JOSEPH DIXON CRUCIBLE COMPANY

Established 1827

Dept. 14-J, Jersey City, N. J.

Canadian Distributors

A.R. MacDougall & Co. Ltd., Toronto, Ont.

There is a Dixon-Quality Pencil,  
Crayon and Eraser for every purpose

DIXON'S "ELDORADO" - the master drawing pencil - HB

# American Wire Rope

Send for Special Illustrated Catalogue

## American Steel & Wire Company

CHICAGO  
NEW YORK  
CLEVELAND  
PITTSBURGH  
DENVER  
U. S. STEEL PRODUCTS CO.

## Modern School Houses

PART II

This volume will be found of unusual value by any Architect having before him the problem of designing a Modern School House.

170 pages of Plate Reproductions  
80 pages of Illustrated Text,

by well-known Architects and Specialists in the engineering features of School House Work.

Price (postpaid), \$7.50

**U. P. C. BOOK COMPANY, Inc.**

Successor to The American Architect Book Dept.

241-249 West 39th Street

New York



# OAK FLOORS

**Beautiful—Distinctive  
Substantial—Economical**

## FOUR VITAL QUALITIES

The owners always emphasize OAK FLOORS in newspaper ads when they offer their houses for sale or for rent. They know OAK FLOORS increase the selling or renting values, besides attracting a better class of buyers or renters.

For bungalows and moderate cost houses  $\frac{3}{8}$ -inch OAK FLOORS, CLEAR Plain or SELECT Plain, is the ideal flooring, because it is very economical in cost, and when laid, has the appearance of  $\frac{13}{16}$ -inch flooring.

The woman of today wants OAK FLOORS, because they will harmonize with any kind of furniture or color decoration, besides being susceptible to any kind of finish. In color it is rich and cheerful and imparts an air of refinement and elegance to a home.

There is a solid satisfaction and lasting pleasure in the substantial and dignified appearance of OAK FLOORS.

Write for Folders.

*"America's Best Flooring"*

**OAK FLOORING MF'RS ASS'N**

1014 Ashland Block

Chicago

# AEROLUX

VENTILATING REG. U. S. PAT. OFF.

## WINDOW SHADES

Good light and proper ventilation in factories means increased efficiency for workers, larger output, better work. We specialize in solving factory shading problems, and our engineering service is at the disposal of architects.

Aerolux Ventilating Window Shades shut out glare but afford perfect ventilation. They also prevent the possible danger to machinery and materials through direct sunlight. Write for samples and full information.

**The Aeroshade Company**

978 Oakland Ave.  
Waukesha, Wis.

for  
**Scientific  
Window  
Shading**



RAILWAY EXCHANGE  
St. Louis

Mauran, Russell & Crowell  
Architects.

Every window above ground floor is  
Wire Glass.

Permanence—Minimum Maintenance  
Fire and Breakage Protection were important factors considered.

MISSISSIPPI WIRE GLASS CO.  
216 Fifth Avenue  
New York

St. Louis

Chicago



## Teak Flooring


At our parquetry factory we have a large quantity of fine texture and color Java Teak. This is suitable for making herringbone, squares, Fontainebleau and other fancy and special designs. We have floor laying agents in most of the Northern and Eastern cities. Our show room and warehouse is at Bldg. No. 4, Bush Terminal, Brooklyn.



**WOOD-MOSAIC CO. INC.**

Established 1883

NEW ALBANY, IND.



**Because  
Metal  
Lasts**

### You can safely specify "Netmesh"

for either plaster or stucco work. It is a rigid, flat-lying, uniform metal lath that can be secured in any quantity on short notice.

*Send for Circular "No Man Hath a Better Lath"*

"Superior" inside corner beads are patented. They prevent the sprangling crack. Superior outside corner beads protect the corner. Work fine with any kind of lath, also tile.



**Milwaukee Corrugating Co.**

MILWAUKEE, WIS.

Branch at  
KANSAS CITY, MO.

Minneapolis Sales Office:  
929 Lumber Exchange



PATENTED MARCH 12, 1912



## BUILDING MODERN OMAHA

WITH MEYER STEELFORMS AND CECO FIREPROOFING MATERIALS

*Our Materials and Construction Methods used in*


- |                              |                             |
|------------------------------|-----------------------------|
| 10 Schools                   | 20 Hotels and Apartments    |
| 2 Hospitals                  | 14 Garage Buildings         |
| 4 Office and Store Buildings | 11 Warehouses and Factories |

*and many others—large and small.*

Offices:  
Omaha, Chicago,  
Kansas City

### CONCRETE ENGINEERING CO.

Warehouses:  
Omaha, Chicago,  
Kansas City



CONCEALED RADIATOR WITH FRONT PANEL REMOVED

## BROOMELL VAPOR HEATING

While suitable for buildings of every size and kind, working perfectly from central stations or exhaust steam—in Hotels, Apartment Houses, Schools, Office buildings, etc., etc., it is especially desirable for **fine residence work**.

Direct radiators of any size or height fitted to the available space, radiators concealed behind ornamental screens, indirect radiators taking air from the outside or using a circulating system can be used in such a way that the

completed work as designed by our Heating Engineers, who are competent to carry out the Architect's ideas and the Owner's wishes, is satisfactory and pleasing.

The time has gone by when heating plants are installed in a haphazard "cut and try" method.

We make real drawings that mean something and we see to it that the work is put in properly and according to the drawings.

### VAPOR HEATING CO., YORK, PA.

597 Fifth Ave., New York City

North American Bldg., Philadelphia, Pa.



## What do you depend upon to win clients?

### QUANTIFIED CONTRACTS

1. Architects should issue complete Quantities together with Drawings and Specifications.
2. When bids are taken they should be based on the architect's Quantities and the bidders should not be obliged to check them or assume any responsibility for their accuracy for bidding purposes.
3. The contractor to whom the job is given (the Builder) should have an opportunity to satisfy himself of the accuracy of the Quantities and to adjust his bid or have his compensation made to conform with any errors he can find.
4. If the Quantities are made a part of the contract, the checking and adjustments would be made as construction proceeds but with any other form of contract they should be made before signing a contract.

Whether you are in the architectural profession to make money or to satisfy your soul's desire, you are looking for clients. They look to you for service. If you'll learn what we can do for you, you'll discover something to convince prospective clients that your service is perfected. Don't take it for granted that you know all about it. If you have not had our latest bulletins, you are about four years behind the development of this idea.

### The Quantity Survey Company, Inc.

17 West 45th Street


WM. GRAVES SMITH, Pres.  
Phone Bryant 3120  
Established 1914

New York City

## PERMANENCY



*Passing years  
cause no  
deterioration in*



### Best Bros. Keene's Cement

*"The Permanent Interior Plaster"*

Age only increases its hardness and durability. The one interior plaster that can be used to wonderful advantage for general plastering or for ornamental work—a plaster with permanency as one of its chief char-

acteristics. Experienced architects know it—hence their recommendation and constant specification for buildings of any size or purpose. *Our Free Book sent postpaid on request.*

The Montefiore Home, Gun Hill Road, New York. Arnold W. Brunner and Buchman & Fox, Architects. *Best Bros. Keene's Cement* used for interior plastering.

### The Best Bros. Keene's Cement Co.

NEW YORK


Established 1889  
MEDICINE LODGE, KANSAS

CHICAGO





## For attaching Shaft Hangers, Fixtures, etc., in Concrete Buildings




### TRUSCON ADJUSTABLE INSERTS

Manufactured from the highest grade of open hearth steel. So cut and formed that when the concrete is poured the insert is thoroughly imbedded at all points, making loosening or tearing out impossible. Made to carry  $\frac{1}{2}$ ",  $\frac{3}{4}$ ",  $\frac{5}{8}$ " and  $\frac{7}{8}$ " bolts.



### TRUSCON PRESSED STEEL SLOTTED INSERTS



Manufactured from the highest grade of pressed steel and suitable for  $\frac{5}{8}$ " or  $\frac{3}{4}$ " bolts. Only  $1\frac{1}{8}$ " deep, permitting reinforcing steel to pass over it without reducing the strength of the construction.

### TRUSCON TAPPED INSERTS

Made from pressed steel of highest quality and furnished tapped for  $\frac{1}{2}$ ",  $\frac{5}{8}$ " and  $\frac{3}{4}$ " bolts. Particularly adapted for work where arrangement has been determined before start of construction.



Write for Prices and Descriptive Pamphlet

## TRUSCON STEEL COMPANY

(FORMERLY TRUSSED CONCRETE STEEL CO.)

YOUNGSTOWN, OHIO.

WAREHOUSES AND REPRESENTATIVES IN PRINCIPAL CITIES



Frank Scott Clark Studio, Detroit Chittenden & Kotting, Architects

## CRITTALL STEEL CASEMENTS

for  
Artistic Residences  
and other substan-  
tial buildings

Made in varied designs  
to meet all conditions



Crittall Casement Window Co.

Detroit

Manufacturers of Steel Casements and Windows

Manor Works, Braintree, England



## Perfect Automatic Refrigeration

**For Apartment Houses, Residences, Hotels, Restaurants, Hospitals, Office Buildings, Institutions, Industrial Plants.**

We are able to place at the disposal of architects an experience in the design and installation of refrigerating plants, probably not elsewhere to be had. This experience covers actual work in probably every class of service, so that our recommendations are based upon first-hand knowledge of facts and precedents. Automatic Systems embody unique features of design, control and operation which can be had in no other system and which contribute to high efficiency, low operating cost, minimized maintenance, and sustained satisfaction. We offer our services to architects for the proper equipment of any building with a refrigerating plant specifically adapted to the purposes in hand and backed by a far-reaching guarantee. Confer with us.

**The Automatic Refrigerating Company**

Main Office and Works: **Hartford, Connecticut**





**I**N housing projects and other construction wherein cost must be kept down, back plastering can be omitted *without* detracting from the strength of the *structure*, by using KNO-BURN Corrugated Metal Lath. The method of procedure is simple:—

**T**HE wood studs are erected just as if the usual wood exterior or sheathing and siding were to be used. A heavy waterproofed building paper is then fastened on the outside of the studs to prevent the wet stucco from coming into contact with the wood and also to act as backing for the lath. Over this is applied KNO-BURN Corru-

gated — a *Self-Furring* Expanded Metal Lath.



**T**HE stucco is then put on in three coats on the exterior of the lath *only*. The wet plaster forces itself through the corrugated mesh, completely embedding it and forming an almost smooth surface on the back. The need for back plastering is thus eliminated. A definite saving of plastering materials results.

## **Kno-Burn** CORRUGATED METAL LATH

**NORTH WESTERN  
EXPANDED METAL  
CO.**

911 Old Colony Bldg.

CHICAGO



NOTE THE  $\frac{1}{4}$  INCH  
CORRUGATIONS WHICH  
FUR THE LATH OUT  
FROM THE PAPER

*A section of the tarred paper is cut away to show how thoroughly the lath is embedded*

## **How Back Plastering Can Be Satisfactorily Omitted**


**T**HE fibres of the tarred paper work themselves into the plastic body. The paper thus prevents the wood studs from absorbing moisture and is an added insulation against temperature changes. The metal lath is thoroughly protected, since there is no chance for moisture reaching the interior of the wall. The interior walls are then finished in the usual way.

**T**HE durability, *economy* and ultimate satisfaction of this form of construction has been repeatedly demonstrated to the satisfaction of architects, owners, engineers and contractors.

*Write us for Recommended Specifications.  
Also for free KNO-BURN Catalog and  
Samples.*



THOMAS MADDOCK'S SONS COMPANY  
TRENTON, NEW JERSEY  
INSTALLATIONS




Graham, Anderson, Probst & White, Architects  
W. G. Cornell Co.  
Plumbing Contractors

—AND IN THE HOTEL CLEVELAND

IN FURTHERANCE OF THE PLAN TO GIVE EACH GUEST THE  
BEST OF EVERYTHING—THE SELECTION OF MADDOCK'S  
MODERN, SANITARY PLUMBING FIXTURES WAS MADE





# Build Now!

*U. S. Department of Labor  
W. B. Wilson, Secretary*

Build Now! That is the command of Uncle Sam which is echoing across the country. Today the building world quivers with activity and thousands of Americans are answering the call.

If you have your fingers on the pulse of the prevailing situation, you are then aware of the ever increasing demand for stucco construction. In responding to the public's choice you must inevitably recognize the supremacy of



## KELLASTONE

IMPERISHABLE STUCCO

In KELLASTONE you have the real fulfillment of the home beautiful—a building material which appeals to the present generation of home builders. It is a scientifically balanced composition which doesn't contain a particle of lime, gypsum or portland cement. Unlike ordinary stucco it doesn't contract, chip or crack. It sets as hard as granite—not affected by wear or weather—a perfect insulator, always maintains its original brilliancy.

We have recently appointed a member of our organization to co-operate with the architectural profession. It is his one duty to work with you and for you in the interest of increased business. Send for details of our national advertising campaign and a copy of our new booklet—"The Story of Kellastone."

**National Kellastone Company**  
1316 Mallers Building Chicago, Illinois





# SATISFACTION

## —in full measure

The unerring service of Jenkins Radiator Valves is assurance against complaints and "come-backs."

The dependability of Jenkins Valves is the result of superior construction. A much heavier and stronger steam metal is used, obviating trouble that frequently arises from expansion and contraction, lifting or settling in the piping and other strains to which valves are subjected.

The Jenkins renewable composition discs give Jenkins Globe Valves extensive life and long service with the least care and attention.



Jenkins Automatic Air Valves quickly remove the dead air from the heating system—and do it without human assistance.

The Jenkins "Diamond Mark" is the symbol of service—and has been for over fifty years.

For all time satisfaction, make the specification read:—"Radiator Valves to be genuine Jenkins having the Jenkins "Diamond Mark."

### JENKINS BROS.

New York Boston Philadelphia Chicago  
Montreal London



# Jenkins Valves



K &amp; H

K &amp; H



**Kimball Hall Building**  
Graham, Burnham & Co., Architects  
Chicago

*Equipped With*

|                                                                                            |                                                                                           |
|--------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------|
| Seven Gearless Traction Passenger Elevators, Two Worm Gear Passenger Elevators, One Duplex | Gear Service Elevator, One Hydraulic Service Elevator, One Automatic Electric Dumbwaiter. |
|--------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------|

## K & H ELEVATORS

THE QUALITY PRODUCT  
OF A RESPONSIBLE  
ORGANIZATION

The position that K & H Elevators have to-day obtained thru the service they are rendering in prominent buildings thruout the country may be largely attributed to the policy of this organization to build exclusively those elevators that we know are suitable for the requirements.

To be above the price plane.

To deal fairly with our customers.


To exert every effort to build elevators that actually possess in every degree the highest possible perfection.

**KAESTNER & HECHT CO.**  
ELECTRIC ELEVATOR BUILDERS  
CHICAGO

K &amp; H

K &amp; H





Bright as day, the interior of the erection building of Ford Shipbuilding plant, 250 ft. wide.

## From Daylight to Daylight

Extending 1,700 feet in length and 250 feet in width, the erection building of the great Ford shipbuilding plant for constructing Eagle submarine chasers has four acres of Truscon Steel Windows. When an Eagle was conveyed outside the plant, ready for launching, the daylight there was scarcely brighter than that inside the plant, coming as it did through the great expanse of windows.


In other industries, no less than in shipbuilding, the well-lighted workroom is a prime asset. It insures greater accuracy, less waste, fewer accidents, and better health. Increased output, better products and economy in lighting bills are additional benefits.

Truscon Steel Windows, characterized by trim, cleancut lines and flat surfaces, represent the highest quality in design, construction, workmanship and hardware. Stock units, in thirty different types and sixty sizes, meet practically all requirements, as regards size of window openings and ventilation. Their specification obviates delay and insures satisfaction.

Copy of handsome Truscon Steel Window Book mailed free on request. Use coupon if convenient.



The first Eagle leaves building




The Eagle passes "from daylight to daylight."

# TRUSCON STEEL WINDOWS

TRUSCON STEEL CO.  
Youngstown, Ohio  
Warehouses and Representatives  
in Principal Cities



Erection building of Ford Eagle plant, 1700 feet long, 250 feet wide. Four acres of Truscon Steel Windows. Albert Kahn, Architect.



A. A.

Truscon  
Steel Co.,  
Youngstown, Ohio.

Send Truscon Window  
Book and suggestions for

building .....

to be used for .....

Name .....

Address .....





The rapidity with which electric ranges are being installed is nothing less than astonishing. Today approximately 40,000 are in successful operation and they have become distinctly the vogue.

## HUGHES ELECTRIC RANGES

And this is no doubt largely due to the fact that thereby the dictation of servants is banished and the home-keeping woman acquires full control of her household. And it is interesting to note that the Architectural Profession is keeping fully abreast of this move toward the electrically equipped home.

Specifications covering electric wiring will be found quite complete in The American Architect Specification Manual.

The smaller appliances such as Toaster, Iron, etc., are commonly referred to as lamp socket appliances because they can be attached to any socket. Nevertheless, it is a great convenience to be able to use properly placed baseboard receptacles and there is a demand for them in every room.

What is called heavy duty material, including ranges, bake ovens, stoves, etc., requires special wiring and should by all means be included in every up-to-date domicile.

We cordially invite you to take up your wiring problems with our Engineering Department. They will gladly give you the benefit of their wide experience. Kindly address our nearest office.

### HUGHES DIVISION

Edison Electric Appliance Company, Inc.  
CHICAGO

NEW YORK

ONTARIO, CALIF.

ATLANTA

Manufacturers of the four well known lines of household electrical appliances

HOTPOINT

GENERAL ELECTRIC TYPE

EDISON

HUGHES





# Hot Windless Days

—the kind that make any movement an effort! A hurry order must be filled—the factory must be kept running—the sick list must be kept down.

If you've never yet appreciated Lupton Counterbalanced Sash, you will on such days. Its large ventilating area— $\frac{1}{2}$  or  $\frac{3}{4}$  the glass area,—the balanced top and bottom openings, and the distance between them, all insure maximum air movement.

## Lupton STEEL SASH COUNTERBALANCED TYPE

was designed to give maximum ventilation with individual windows. It opens easily, shuts tight, and is readily used in connection with an overhead line of Pond Continuous Sash if desired. For most wide multiple-story factories it is the ideal sash.

It is strongly made of heavy rolled sections with oxyacetylene welded sash joints. Head, meeting

rails and sill are weather-tight by design, without stripping. The large lights make cleaning and painting easy.

Booklet, "Air, Light and Efficiency," tells how we helped the owners of some famous factories to get maximum returns from their investment in Lupton Products. It's free to plant officials, architects and engineers.

### David Lupton's Sons Company

Tulip and Janney Sts.

Philadelphia, Pa.

Makers of Modern Equipment for Daylighting and Natural Ventilation

Canadian Manufacturers: THE A. B. ORMSBY CO., Ltd., Toronto

**BUILD NOW**  
and begin earning the  
profits on a modern plant

